

FURNISH MATERIALS, LABOR, TOOLS, EQUIPMENT, SERVICES AND SUPPLIES FOR REPLACEMENT OF GANGWAY TO COURTESY DOCK, EVA BEACH AREA, N.B. FORREST STATE PARK, EVA TN 38333.

PROJECT TO BE COMPLETED WITHIN 90 CALENDAR DAYS AFTER RECEIVING PURCHASE ORDER.

**PROJECT TO BE BID AS ONE (1) JOB.**

**PROJECT TO INCLUDE BUT NOT LIMITED TO REMOVAL OF EXISTING GANGWAY AND RELATED COMPONENTS, INSTALLING A NEW GANGWAY AND COMPONENTS FOR A COMPLETED, SAFE, GANGWAY SYSTEM, CORRECTING DOCK FLOTATION AS NEEDED, EVA BEACH COURTESY DOCK, N.B. FORREST STATE PARK, EVA TN 38333.**

**NEW GANGWAY SHALL BE DESIGNED FOR A MINIMUM LIVE LOAD OF 50 PSF, A COLLATERAL/DEAD LOAD OF 10 PSF TO BE APPLIED IN ADDITION TO THE ACTUAL SELF WEIGHT OF THE STRUCTURE. THE STRUCTURE SHALL ALSO BE DESIGNED FOR A MINIMUM 300 LB. CONCENTRATED LOAD TO BE APPLIED NON-CONCURRENT WITH THE UNIFORM LIVE LOAD. DESIGN LOAD SUCH AS GUARDRAIL/HANDRAIL LOADING, LATERAL LOADS, ETC SHALL BE INCLUDED IN THE DESIGN.**

**GANGWAY TO BE "ADA" COMPLIANT.**

**REQUIRED CORRECTIONS OR ADJUSTMENTS TO FLOTATION, SPUD POLES AND MAINTAINING LEVEL PLANE OF COURTESY DOCK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.**

CONTRACTOR TO PAY ALL FEES AND COST, IS RESPONSIBLE FOR SELECTING AN ENGINEER KNOWLEDGABLE AND EXPERIENCED IN GANGWAY DESIGN AND CONSTRUCTION. HAVE DELIVERED AND INSTALLED A NEW GANGWAY SYSTEM BUILT AND INSTALLED IN COMPLIANCE WITH STAMPED DRAWINGS BY AN ENGINEER LICENSED AND/OR REGISTERED AS REQUIRED TO PRACTICE BUSINESS IN THE STATE OF TENNESSEE. CONTRACTOR SHALL SCHEDULE MANUFACTURING, DELIVERY, INSTALLATION, INSPECTION AND APPROVALS OF NEW GANGWAY AND RELATED COMPONENTS.

CONTRACTOR SHALL PROTECT COURTESY DOCK, SPUD POLES, FLOTATION AND ANCHORING SYSTEMS DURING REPLACEMENT ACTIVITIES, REPAIR ANY DAMAGE TO ORIGINAL STATE OR BETTER.

CONTRACTOR SHALL OBTAIN AND PAY REQUIRED PERMITS OR FEES, ARRANGE INSPECTIONS OR APPROVALS WITH AUTHORITY HAVING JURISDICTION.

CONTRACTOR SHALL BE LICENSED, CERTIFIED, REGISTERED OR APPROVED AS APPLICABLE TO PERFORM WORK.

CONTRACTOR SHALL FIELD VERIFY AND ASCERTAIN TO PERSONAL SATISFACTION, SCOPE OF WORK, SPECIAL CONDITIONS, ACCESS, TOOLS AND EQUIPMENT NEEDED, QUANTITY OF MATERIALS AND SKILL LEVEL REQUIRED FOR IMPLEMENTATION OF PROJECT.

CONTRACTOR SHALL REPAIR, AT NO COST TO AGENCY, DAMAGE CAUSED BY CONSTRUCTION OR CONTRACTOR'S ACTIVITIES. REPAIRS SHALL BE COMPATABLE WITH ADJACENT AREA'S MATERIALS AND WORKMANSHIP.

CONTRACTOR SHALL COMPLY WITH LATEST EDITION OF LOCAL, STATE AND NATIONAL CODES, TRADE STANDARDS, REGULATIONS, SPECIFICATIONS, AND AGENCY'S APPROVAL.

CONTRACTOR SHALL ATTEND AN ON SITE PROGRESS MEETING AND FINAL INSPECTION, CONTACT JERRY TUBBS 731-968-6608 FOR DATE AND TIME OF MEETINGS.

CONTRACTOR SHALL MAINTAIN A CLEAN SAFE WORK SITE ON A DAILY BASIS, REMOVE ALL SCRAP AND UNUSED MATERIALS FROM STATE PROPERTY WHEN PROJECT IS COMPLETED LEAVING AREA IN A CLEAN CONDITION SUITABLE FOR INTENDED USE.

A COPY OF SPECIFICATIONS SHALL BE ON SITE AND AVAILABLE WHEN WORK IS BEING PERFORMED.

CONTRACTOR SHALL WARRANTY MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE.