



Civil & Environmental Consultants, Inc.

Challenges of Early Closure of Landfills

TDEC-Environmental Show of the South

Presented By

Brian Wolf, PE & Chris Murray, PE, PLS, PP

May 16, 2018

Introduction – What is Early Closure?

► Definition:

- Capping at least a portion of a facility prior to reaching final grades
- Can be lateral or vertical



Introduction – What is Early Closure?

Causes:

▶ Vertical Early Closure


- Not filling to permitted top of waste elevations
- Settlement

▶ Lateral Early Closure


- Not constructing full permitted footprint
- Mothballing – Corporate Strategy
- Financial Issues – Site Abandonment



Vertical Early Closure – What we mean



Vertical Early Closure – What we mean



Vertical Early Closure – Potential Problems

▶ Lost Airspace – Revenue Loss

▶ Stormwater Design Impacts

- Diversion berms and downchutes may need to be addressed

▶ Landfill Gas Collection System Impacts

- Reduction in collection capabilities




Vertical Early Closure – Potential Issues (cont'd)

► Stability Concerns - Veneer

- Design is for 3:1 but slopes less
 - Increased infiltration vs. runoff
 - Decreased flow in geocomposite drainage layer
 - Significant reduction in forces
- Probably no decrease in safety factor but designer should verify
 - Geocomposite could be inundated without failure

Lateral Early Closure – What we mean



Lateral Early Closure – Potential Issues

► Internal Slopes

- Internal slopes should not exceed external slopes
- Fill areas should not be overfilled to extend constructed remaining life – need for a new cell
- Slopes should not be overfilled anticipating settlement


Lateral Early Closure – Potential Issues (cont'd)

► If slopes exceed cap design criteria:

- Move waste – Costly, odorous, and may not have anywhere to move it
- Find alternate design for cap – Permitting issues, costly
- Extend the base to allow cap design criteria to be met



Lateral Early Closure – Base Liner Extension



Lateral Early Closure – Potential Issues (cont'd)

► Stormwater

- Site drainage patterns will not be as initially designed
- Potential increased loading to existing ponds/not all ponds constructed
- Diversion berms and downchutes required where not initially designed
- Potentially need to redesign entire system for new conditions



Lateral Early Closure – Potential Issues (cont'd)

► Landfill Gas Collection System

- Well spacing/depth likely impacted
- Header closed loop will be impacted
- Blower/Flare sizing – may have larger infrastructure than needed
- Potentially need to redesign entire system for new conditions



Lateral Early Closure – Potential Issues (cont'd)

► Leachate Management

- Seeps and outbreaks – design considerations
- Probably, minimal impacts...probably
- Rainflaps – impact on final cap tie-in design
- Base Liner Extension



Lateral Early Closure – Potential Issues (cont'd)

► Stability

- Likely need to re-evaluate static and seismic stability for new conditions
- Base Liner Extension



Prevention of Potential Issues

► **Employ Good Filling Practices**

- Proper slopes
- Proper compaction
- Proper daily and intermediate cover

► **Plan Ahead**

- Start thinking about capping years in advance
- Know your filling plans in the near and long term – cap sequence plans
- Survey, Survey, Survey



Lessons Learned

- ▶ **Know how much leachate is in the landfill!**
- ▶ **Know the characteristics of the leachate!**
- ▶ **No slopes steeper than 3:1!**
- ▶ **Ensure that closure/post-closure costs are accurate!**
- ▶ **Confirm availability of soil for cap construction!**



Questions?

Connect with us!



www.cecinc.com



Civil & Environmental Consultants, Inc.