

Contractor is to furnish all materials, equipment, supplies and labor to install new playground system at Pin Oak Lodge on Natchez Trace State Park at 567 Pin Oak Lodge Road Wildersville, TN 38388.

SPECIFICATIONS AND GENERAL CONDITIONS:

Contractor will install a new mini play system at Pin Oak Lodge on Natchez Trace State park by Playmart Series: **(KILIMANJARO)** or an approved equal according to manufactures recommendations. Ground level ADA components shall meet ASTM F 1951 Standard for ADA accessible. Ages:5-12, Accommodates: 58-70, Contains the following : sixteen (16) decks, sloping super glider with handles, step up blocks and metal supports, outset monkey graphics panel, sloping rubber bridges with pickets, inset 5-pipe with teleidoscope, inset 5-pipe rail, 3' 90 degree curved slide with single slide hood, peek-a-boo turning tunnel, inset 5-pipe rail, pipe ladder with handle panels, ada Daytona panel, wiggle step bridge with handles and metal supports, inset gecko graphics panel, arch bridge with plastic panels and camel graphics, 6' wave slide with single slide hood, casa grande roof, (5) inset 5-pipe rail, rock wall climber with handle panels, two 72" tunnel slide-serpentine- with slide hood, (2) noahs ark panels with animals, storefront panel with farmers market graphics, vortex climber with handle panels, inset frog graphics panel with steering wheel, storefront panel with farmers market graphics with (2) kids benches arch climber with handle panels, safety plate, inset tic-tac-toe panel, vertical pipe ladder with handle panels, inset snake panel, inset pipe rail, inset chime panel, inset monkey graphics panel. Install four (4) 6" x 6" support post and six (6) 4" x 6" support post two (2) feet below ground level incased in concrete. Install all other support post according to manufactures recommendations for use on asphalt surface. Color will be Park (green and brown). Contractor shall be responsible for all broken or missing components.

Install six inches (6") of loose fill rubber for playground surface in 58x47 area color brown with a six (6") brown containment border surface materials shall meet the current CPSC recommendations and ASTM F 1951 standard for ADA accessible surface material and the ASTM 1292 standard for impact attenuation

Contractor shall be responsible for complying with current edition of local, state, federal safety codes. At any time the contractor becomes aware of a safety issue, he shall take measures to prevent park employees and guest from entering the work area, project shall cease until safety issue is corrected. Code violations shall be corrected and brought to the attention of park management and West TN Regional Office.

The contractor shall commence work within approximately (30) days after receiving purchase order and be completed within approximately (30) days after commencement of work.

The contractor is required to visit job site prior to quoting and verify scope of work, dimensions, and circumstances which may exist. Bidders who do not attend the mandatory pre-bid meeting will not be considered for this contract.

The successful vender will be required to attend an on- site pre-construction meeting and on-site final inspection.

After completion of work, the contractor, a representative from WEST TENNESSEE REGIONAL OFFICE, PARK MANAGEMENT and a park representative will inspect completed work performed by the contractor.

During the course of work, the contractor will maintain a clean work area and upon completion of the work shall remove all debris and trash from job site.

During the construction period, coordinate construction schedules and operations with the agency. The successful contractor shall contact Roger Blankenship, Facilities surveyor, West Tenn. Regional Office, at 731-968-6608, to confirm dates and times for pre-construction conference and final inspection. Contact Park Manager Chris Hill at 1-731-968-3742, who will assist in site locations.

The contractor shall have insurance sufficient to protect himself/herself from all claims which result from the contractor's operations or operation of his/her sub-contractors. The contractor shall return to original conditions any property damaged or lost as a result of his acts or actions of his/her sub-contractor.

The contractor shall hold the state of TENNESSEE, and NATCHEZ TRACE STATE PARK and employees harmless from damage or loss of property or injury of personnel resulting from actions of the contractor or his/her sub-contractor.

The successful vender shall provide a one (1) year warranty on all labor and materials beginning on day of acceptance by PARK MANAGEMENT and WEST TENNESSEE REGIONAL OFFICE.