

FURNISH MATERIALS, LABOR, EQUIPMENT, TOOLS, SERVICES AND SUPPLIES FOR REPLACEMENT OF STEPS, RELATED POST, RAILS AND BENCHES AT SAUL'S MOUND, PINSON MOUND STATE PARK; 460 OZIER ROAD, PINSON TN 38360.

PROJECT TO BE COMPLETED WITHIN 30 CALENDAR DAYS AFTER RECEIVING NOTICE TO PROCEED.

THE MOUND IS A FRAGILE ARCHAEOLOGICAL RESOURCE AND IT IS IMPERATIVE THAT GREAT CARE BE TAKEN TO AVOID DAMAGE TO THE MOUND DURING REPLACEMENT OF STEPS AND PLATFORM. THE SUCCESSFUL BIDDER WILL ACKNOWLEDGE THE FRAGILE NATURE OF THE WORK SITE AND TAKE NECESSARY STEPS TO PREVENT POTENTIAL DAMAGE TO THE MOUND AND SURROUNDING AREA.

WORK WILL CEASE AT THE AGENCY'S DISCRETION WHEN WEATHER CONDITIONS OR OTHER FACTORS POSE A THREAT OF IMPACTING THE ARCHAEOLOGICAL INTEGRITY OF THE MOUND AND SURROUNDING SITE.

IT SHALL BE THE RESPONSIBILITY OF THE SUCCESSFUL BIDDER TO DEFINE AND MARK A SAFETY ZONE AROUND THE WORK AREA TO ENSURE THE SAFETY OF PARK VISITORS AND STAFF. PROVIDE ERECT AND MAINTAIN A HIGH VISIBILITY PORTABLE FENCE AROUND THE PERIMETER OF THE SAFETY ZONE. ONLY AUTHORIZED PERSONS WILL BE ALLOWED TO ENTER THE SAFETY ZONE.

THE WORK AREA IS DEFINED AS AREA CONTAINING THE EXISTING STAIRS UP TO THE OBSERVATION PLATFORM, INCLUDE STAGING AND STORAGE IN FENCED AREA WITH REALIZATION CRANE MAY BE USED IN IMPLEMENTING OF WORK.

CONTRACTOR SHALL REPLACE IN ENTIRITY EXISTING POST, BENCHES, STAIRS, AND RELATED ITEMS IN STEP SYSTEM.

PULL EXISTING POST, SET NEW POST IN HOLES CREATED BY REMOVAL.

REPLACEMENT MATERIALS SHALL BE PRESSURE TREATED #2 OR BETTER YELLOW PINE, S4S, DIMENSIONAL TIMBER AND BOARDS TO MATCH EXISTING IN SIZE, LENGTH, LOCATION AND ATTACHMENT METHODS. POST IN CONTACT WITH SOIL SHALL BE PRESSURE TREATED WITH A MINIMUM 0.60 LB CCA PER CUBIT FOOT WOOD PRODUCT.

TREAD ON STEPS TO BE (2) 2"X6" BOARDS", ENCLOSE BACK OF RISER, STEP RISE/RUN TO MATCH EXISTING OR AS REQUIRED BY CODE.

HAND RAILS SHALL BE "2X4" HAND RAIL BOARDS", AT CONTRACTORS DISCRETION EXISTING SPACER ALLOWED TO BE REUSED.

POST SHALL BE OF CONTINUOUS LENGTH EXTENDING INTO SOIL A MINIMUM OF 24" ENCASE IN CONCRETE, EXTEND 42" ABOVE STEPS.

TOP OF STEP POST TO BE CAPPED WITH A CONTINUOUS RUN 2"x6" BOARD, JOINT CENTER ON POST, EXTEND TO OUTSIDE OF END POST.

BENCHES AND SEATS TO BE INSTALLED AT 18" HEIGHT.

WORK TO BE PERFORMED 7:00 A.M. – 4:00 P.M. MONDAY-FRIDAYS OR AS DIRECTED BY AGENCY, EXCLUDING STATE RECOGNIZED HOLIDAYS.

CONTRACTOR SHALL FIELD VERIFY TO PERSONAL SATISFACTION, SCOPE OF WORK, ACCESS, TOOLS, EQUIPMENT, SKILL LEVEL NEEDED TO PERFORM WORK.

CONTRACTOR SHALL REPAIR AT NO COST TO AGENCY DAMAGE CAUSED BY CONSTRUCTION OR CONTRACTORS ACTIVITIES. REPAIRS SHALL BE COMPATIBLE WITH ADJACENT AREA'S MATERIALS AND WORKMANSHIP.

CONTRACTOR SHALL COMPLY WITH LATEST EDITION OF LOCAL, STATE AND FEDERAL CODES, TRADE STANDARDS, REGULATIONS, SPECIFICATIONS AND AGENCY'S APPROVAL.

CONTRACTOR SHALL ATTEND AN ON SITE PRE-CONSTRUCTION MEETING, PROGRESS MEETINGS AND FINAL INSPECTION, CONTACT : REID MULLINS, 731-968-6608 FOR DATE AND TIME OF MEETINGS.

CONTRACTOR SHALL MAINTAIN A CLEAN SAFE WORK SITE, REMOVE SCRAP AND UNUSED MATERIALS FROM STATE PROPERTY WHEN PROJECT IS COMPLETED LEAVING AREA IN A CLEAN CONDITION SUITABLE FOR INTENDED USE.

A COPY OF SPECIFICATIONS SHALL BE ON SITE AND AVAILABLE WHEN WORK IS BEING PERFORMED.

CONTRACTOR SHALL WARRANTY MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE.