

**TIMS FORD STATE PARK
NEALS BRIDGE, ROCK CREEK, AND DEVIL'S STEP BOAT RAMP REPAIR**

THIS JOB IS FOR THE REMOVAL OF DAMAGED CONCRETE AND INSTALLATION OF NEW CONCRETE AT THE THREE AFOREMENTIONED BOAT RAMPS. CONTRACTOR SHALL FURNISH ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR THE COMPLETION OF THIS JOB.

CONTRACTOR SHALL REMOVE ALL CONCRETE AT NEALS BRIDGE AND ROCK CREEK BOAT RAMPS. 10 LINEAL FEET THE WIDTH OF THE RAMP OF DAMAGED CONCRETE SHALL BE REMOVED AT DEVIL'S STEP WHERE IT MEETS THE ASPHALT.

CONCRETE WILL BE EXTENDED 6' INTO THE WATER AT NEALS BRIDGE ONLY.

CONTRACTOR SHALL REPLACE ALL BAD CONCRETE WITH NEW 5000 PSI CONCRETE 6" DEEP. 6X6 STEEL WIRE WILL BE INSTALLED WITH #4 REBAR 4" DEEP AND 4" ABOVE 4' APART TO HOLD UP THE STEEL WIRE. IT WILL BE FASTENED WITH COATED TIE WIRE.

CONTRACTOR IS RESPONSIBLE FOR ALL MEASUREMENTS.

CONTRACTOR WILL BE RESPONSIBLE TO REPAIR/REPLACE ANY AND ALL DAMAGES TO STATE PROPERTY THAT OCCUR DURING THIS JOB.

CONTRACTOR WILL BE RESPONSIBLE TO KEEP ALL MATERIALS, TOOLS, EQUIPMENT, TRASH, AND TRASH RECEPTACLES PROPERLY BARRICADED AND SECURE.

CONTRACTOR SHALL CLEAN THE JOBSITE DAILY AND MUST COMPLETE A THOROUGH FINAL CLEAN-UP AT THE COMPLETION OF THE JOB

CONTRACTOR SHALL DISPOSE OF ALL TRASH AND DEBRIS OFF STATE PROPERTY.

WORK IS TO BEGIN WITHIN 10 DAYS AFTER RECEIPT OF PURCHASE ORDER AND BE COMPLETED WITHIN 30 DAYS.

CONTRACTOR SHALL PROVIDE A 1 YEAR WORKMANSHIP WARRANTY TO BEGIN ON THE DATE OF THE FINAL INSPECTION AND ACCEPTANCE OF WORK BY THE STATE OF TENNESSEE.

THIS JOB IS TO BE STARTED AS SOON AS TVA LOWERS THE LAKE WATER LEVEL, APPROXIMATELY 11/15/2020.