

DUNBAR CAVE STATE PARK – SIDEWALK REPLACEMENT AND ASPHALT WALKWAY

Contractor is to furnish all labor, tools, and materials to remove and replace the existing sidewalk at the rear of Dunbar Cave State Park Visitor Center.

Contractor shall remove existing sidewalk and dirt approximately 4” deep. Contractor is to construct a new sidewalk that is approximately 345’ long and 10’ wide with 2” of crusher run gravel packed and 4” thick of 3000 psi concrete. Contractor shall install 3 runs of # 4 rebar. The new sidewalk will be stamped concrete to look like brick and tinted a red/brown color. The color and stamp patten will be selected by the Park Manager. The sidewalk shall be level with the ground.

ASPHALT WALKWAY TO BRIDGE

Construct an asphalt walkway from stairs near visitor center to the metal bridge. Path shall be 2” thick, 8’ wide, 500’ feet long. Contractor shall excavate to suitable substrate and shall install suitable base material to support the pave walkway. Geotextile fabric shall be installed as appropriate.

CONTRACTOR WILL BE RESPONSIBLE FOR ALL MEASUREMENTS.

Contractor will be responsible for securing the job site for the duration of this job.

Contractor will be responsible to repair or replace all damages to state property during this job.

Contractor shall seed and straw any area that is damaged during this project.

Contractor will dispose of all debris off state property.

All workmanship will have a 1-year warranty from date of final inspection.

Contractor shall begin work within 15 days after receipt of order and shall be completed within 30 days.