

**State of Tennessee**  
**Sourcing Event 34101-11475**

**Demolition of Barracks Buildings #517 & #518**

**Objective:**

Complete demolition of two WWII two-story wooden barracks buildings in order to construct one new barracks Facility. VTS-Smyrna, 680 Fitzhugh Blvd, Smyrna, TN 37167.

**Demolition must be completed no later than May 15, 2020.**

**Scope of Work:**

Complete demolition and removal of all debris to include structures, contents, foundations, steps and landings. Each building consists of pier style concrete/CMU footings and wooden WWII two story structure. Each structure has 4970 square feet of floor space.

**The Contractor will:**

- Notify 811- "Call Before You Dig" prior to start of demolition
- Obtain demolition permits. Contractor will provide copies of the permits to the agency prior to the start of the demolition.
- Provide all equipment, waste containers, dust control and labor
- All demolition debris to be taken to certified landfill/solid fill site for disposal
- Final clean up and prepare rough grading and leveling of the area to avoid hazards
  - No requirement for final compaction of soil in the demolition area
  - Backfill open pits from the removal of foundations as required to minimize hazards

**The Owner will:**

- Close all utility service accounts, disconnect services at existing meters, transformers and sewer taps.
- Provide/install construction fence around hazards after demo is complete (as required)
- Provide backfill materials as needed by the contractor to fill open pits
- Final grading, seed and straw (as required)

**Contacts:**

Steve Watts, 615-313-0584, [steven.e.watts.nfg@mail.mil](mailto:steven.e.watts.nfg@mail.mil)

Stephen Pate, 615-426-5930, [stephen.pate@tn.gov](mailto:stephen.pate@tn.gov)