

Estimated Quantities -- Letting August 19, 2022

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNW919 - KNOX

Contract ID: CNW919

Letting Date: August 19, 2022 10:00 AM

Projects: 47024-3239-94

HSIP-71(33)

Counties: KNOX

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, retaining walls and paving on U.S. 441 (S.R. 71) from south of Simpson Road (L.M. 1.00) to Hendron Chapel Road (L.M. 1.98) in Knoxville.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	1,720.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.57	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (CB & EW)	(1)	LS
202-01.58	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (PIPES)	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	4,122.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	57,163.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	5,236.000	TON
203-04	PLACING AND SPREADING TOPSOIL	6,678.000	C.Y.
203-06	WATER	152.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	3,938.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	30.000	C.Y.
209-02.05	12" TEMPORARY SLOPE DRAIN	1,441.000	L.F.
209-02.07	18" TEMPORARY SLOPE DRAIN	552.000	L.F.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
209-05	SEDIMENT REMOVAL	398.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	13,224.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	21,672.000	L.F.
209-08.07	ROCK CHECK DAM	9.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	26.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	17.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	8.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	19.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	2.000	EACH
209-40.48	CATCH BASIN FILTER ASSEMBLY(TYPE 8)	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	198.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	15,599.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	266.000	TON
303-01.03	GRANULAR BACKFILL (RETAINING WALLS)	2.500	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	261.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	956.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	1,060.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	2,384.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,192.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	23.300	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	33.500	TON
411-01.10	ACS MIX(PG64-22) GRADING D	439.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	3,014.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	1.800	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	0.300	L.M.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	2,299.000	TON
602-01	STRUCTURAL STEEL	645.000	LB.
604-01.01	CLASS A CONCRETE (ROADWAY)	38.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	5,922.000	LB.
604-07.01	RETAINING WALL (DESCRIPTION) (WALL 1)	1,397.000	S.F.
604-07.02	RETAINING WALL (DESCRIPTION) (WALL 2)	1,109.000	S.F.
604-07.03	RETAINING WALL (DESCRIPTION) (WALL 3)	1,321.000	S.F.
604-07.04	RETAINING WALL (DESCRIPTION) (WALL 4)	1,039.000	S.F.
604-07.05	RETAINING WALL (DESCRIPTION) (WALL 5)	6,338.000	S.F.
604-07.06	RETAINING WALL (DESCRIPTION) (WALL 6)	572.000	S.F.
604-07.07	RETAINING WALL (DESCRIPTION) (WALL 7)	732.000	S.F.
604-07.08	RETAINING WALL (DESCRIPTION) (8)	372.000	S.F.
604-10.01	CONCRETE REPAIRS	(1)	LS
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	14.000	L.F.
607-03.30	18" PIPE CULVERT	2,840.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	72.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	156.000	L.F.
611-02.10	JUNCTION BOX, TYPE 1	9.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	39.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	2,117.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.59	24IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-09.03	CAPPING EXISTING CATCHBASIN	4.000	EACH
611-25.01	CATCH BASINS, TYPE 25, 0' - 4' DEPTH	6.000	EACH
611-25.02	CATCH BASINS, TYPE 25, > 4' - 8' DEPTH	10.000	EACH
611-25.03	CATCH BASINS, TYPE 25, > 8' - 12' DEPTH	1.000	EACH
611-26.02	CATCH BASINS, TYPE 26, > 4' - 8' DEPTH	2.000	EACH

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
611-41.01	CATCH BASINS, TYPE 41, 0' - 4' DEPTH	3.000	EACH
611-41.02	CATCH BASINS, TYPE 41, > 4' - 8' DEPTH	2.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	3.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	3.000	EACH
611-45.02	CATCH BASINS, TYPE 45, > 4' - 8' DEPTH	2.000	EACH
701-02	CONCRETE DRIVEWAY	10,514.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	520.000	C.Y.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	59.000	C.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	3.000	EACH
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	64.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	3,465.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	9.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	12.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	42.000	EACH
706-01	GUARDRAIL REMOVED	130.000	L.F.
706-10.26	ROUNDED END ELEMENT	6.000	EACH
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	58.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	105.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1,131.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	514.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	380.000	TON
710-04	FILTER CLOTH UNDERDRAIN (WITH PIPE)	8,019.000	L.F.
710-05	LATERAL UNDERDRAIN	462.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	5.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	4.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	16.000	EACH
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	55.000	L.F.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
711-05.72	SINGLE SLOPE HALF CONCRETE BARRIER WALL	718.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	5,434.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-06	SIGNS (CONSTRUCTION)	676.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	66.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-12.10	TEMPORARY CURB W/FLEXIBLE DELINEATOR	2,850.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	590.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	65.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	10.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.06	DEAD END SIGN AND SUPPORT	3.000	EACH
713-16.07	END OF ROADWAY SIGN AND SUPPORT	5.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	308.000	EACH
716-01.07	TEMPORARY RAISED PAVEMENT MARKER,YELLOW	115.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	161.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	161.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	180.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	117.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	7.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.800	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	51,348.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	149.000	L.F.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	0.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	6.200	L.M.
717-01	MOBILIZATION	(1)	LS
740-06.01	GEOMEMBRANE	555.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,938.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,131.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	218.000	L.F.
801-02	SEEDING (WITHOUT MULCH)	260.000	UNIT
801-03	WATER (SEEDING & SODDING)	60.000	M.G.
803-01	SODDING (NEW SOD)	7,135.000	S.Y.
805-01.03	TURF REINFORCEMENT MAT (CLASS III)	651.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	27,624.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL
204-06.01	FLOWABLE FILL (GENERAL)	27.000	C.Y.
791-02.02	2IN MDPE GAS MAIN	520.000	L.F.
791-02.06	8IN MDPE GAS MAIN	6,590.000	L.F.
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-04.02	HDD 2IN PE PIPE - UNCONSOLIDATED	120.000	L.F.
791-04.06	HDD 8IN PE PIPE - UNCONSOLIDATED	215.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	1.000	EACH
791-06.05	CONNECT TO 8IN EX. PE MAIN	3.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	6.000	EACH
791-07.04	8IN PE GAS VALVE ASSEMBLY	2.000	EACH
791-07.21	EXCESS FLOW VALVE (EFV)	4.000	EACH
791-08.03	1IN SERVICE ASSEMBLY	4.000	EACH
791-08.08	1IN PE SERVICE PIPE	500.000	L.F.
791-08.41	GAS MAIN REMOVAL	200.000	L.F.
791-09.05	RESTORE ASPHALT	500.000	S.Y.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
791-09.06	RESTORE CONCRETE	100.000	S.Y.
791-09.07	RESTORE GRAVEL	100.000	S.Y.
791-10.10	RETIRE GAS MAIN	(1)	LS
791-99.01	ADDER FOR FULL CLEAN STONE BACKFILL	500.000	L.F.
791-99.02	CLEAN UP RESTORATION & CLOSEOUT	(1)	LS
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	40.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	460.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	430.000	L.F.
795-01.06	8IN DIP SLIP JOINT WATER LINE	7,630.000	L.F.
795-05.02	HDD 4IN HDPE CASING PIPE-UNCON	525.000	L.F.
795-05.65	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	70.000	L.F.
795-05.79	BORE/JACK 16IN STEEL CASING PIPE-ROCK.	150.000	L.F.
795-06.01	CONNECT TO 2IN WATER LINE	1.000	EACH
795-06.03	CONNECT TO 4IN WATER LINE	2.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	2.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	5.000	EACH
795-06.31	CUT AND CAP 2IN WATER LINE	2.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	2.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	1.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	2.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-08.01	2IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.03	4IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	27.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	32.000	EACH
795-09.28	3/4IN COPPER SERVICE PIPE	1,760.000	L.F.
795-11.01	BLOW-OFF ASSEMBLY	1.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	3.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	6,660.000	L.F.

Contract ID CNW919 - KNOX

Item No.	Description	Quantity	Units
795-12.01	REMOVE FIRE HYDRANT	1.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-13.01	DI FITTINGS	2,500.000	LB.
795-13.05	CREEK CROSSING (DESCRIPTION) (STA 396+50)	(1)	LS
795-13.06	CREEK CROSSING (DESCRIPTION) (STA 407+55)	(1)	LS
795-14.08	RESTORE ASPHALT	450.000	S.Y.
795-14.09	RESTORE CONCRETE	80.000	S.Y.
795-15.02	12IN STEEL CASING PIPE OPEN CUT METHOD	40.000	L.F.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	210.000	L.F.
795-20.01	RECONNECT SERVICE ASSEMBLY	32.000	EACH
797-03.04	2IN PVC FORCE MAIN	200.000	L.F.
797-03.06	4IN PVC FORCE MAIN	1,300.000	L.F.
797-06.02	HDD 4IN HDPE CARRIER PIPE-UNCON	175.000	L.F.
797-06.87	OPEN CUT 8IN STEEL CASING PIPE	80.000	L.F.
797-08.02	PVC FITTINGS	300.000	LB.
797-08.12	2IN END OF LINE FLUSHING ASSEMBLY	1.000	EACH
797-09.04	2IN PVC BALL VALVE	2.000	EACH
797-09.06	4IN PLUG VALVE ASSEMBLY	3.000	EACH
797-09.41	CUT AND CAP 2IN FORCE MAIN	2.000	EACH
797-09.43	CUT AND CAP 4IN FORCE MAIN	2.000	EACH
797-10.14	CONNECT TO 2IN FORCE MAIN	6.000	EACH
797-10.16	CONNECT TO 4IN FORCE MAIN	4.000	EACH
797-11.30	RETIREIN PLACE EXISTING SEWER <8IN	1,490.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.40	RESTORE ASPHALT	80.000	S.Y.
797-11.41	RESTORE CONCRETE	20.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW268 - ANDERSON , BLOUNT , ETC.

Contract ID: CNW268

Letting Date: August 19, 2022 10:00 AM

Projects: R1BVAR-M3-014

NA

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER, GREENE,
HAMBLEN, HANCOCK, JEFFERSON,
JOHNSON, KNOX, LOUDON, MONROE,
MORGAN, ROANE, SCOTT, SEVIER,
SULLIVAN, UNICOI, UNION, WASHINGTON

District:

DBE Goal Percent:

Description: The random on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	520.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	3,200.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	200.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	40.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	70.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	165.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	320.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	2,000.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	35.000	EACH

Contract ID CNW268 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	2,040.000	L.F.
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	3.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	5.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	20.000	EACH

() Item will be bid as lump sum.

Contract ID CNW296 - ANDERSON , CLAIBORNE, ETC.

Contract ID: CNW296

Letting Date: August 19, 2022 10:00 AM

Projects: R1SVAR-F3-015

HSIP-REG1(212)

Counties: ANDERSON, CLAIBORNE, KNOX, MONROE,
ROANE, SEVIER

District:

DBE Goal Percent: 6.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	6.000	S.Y.
701-01.02	CONCRETE SIDEWALK (6 ")	1,025.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	16,447.000	S.F.
701-02.03	CONCRETE CURB RAMP	5,479.000	S.F.
702-01	CONCRETE CURB	3.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	11.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	809.000	S.F.
713-15.40	SIGN INSTALLATION (DESCRIPTION)	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-26.07	FLASHING WARNING BEACON (DESCRIPTION) (RECTANGULAR RAPID FLASHING BEACON)	6.000	EACH

() Item will be bid as lump sum.

Contract ID CNW255 - BEDFORD & LEWIS

Contract ID: CNW255

Letting Date: August 19, 2022 10:00 AM

Projects: R3SVAR-F3-020

HSIP-REG3(216)

Counties: BEDFORD, LEWIS

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
701-02.01	CONCRETE CURB RAMP (RETROFIT)	6,600.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	144.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,408.000	S.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW291 - BENTON , CROCKETT, ETC.

Contract ID: CNW291

Letting Date: August 19, 2022 10:00 AM

Projects: R4BVAR-M3-020

NA

Counties: BENTON, CROCKETT, DECATUR, DYER,
FAYETTE, HAYWOOD, HENDERSON,
MADISON, OBION, SHELBY, TIPTON

District:

DBE Goal Percent:

Description: The random on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	75.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	2,170.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	70.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	15.000	EACH
705-80.09	DRIVEN SOCKETED LINE POST W/ALL ACCESSORIES	150.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	10.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	15.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	60.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	600.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	20.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	100.000	L.F.

Contract ID CNW291 - BENTON , CROCKETT, ETC.

Item No.	Description	Quantity	Units
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	5.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	35.000	EACH

() Item will be bid as lump sum.

Contract ID CNW283 - BRADLEY , COFFEE, ETC.

Contract ID: CNW283

Letting Date: August 19, 2022 10:00 AM

Projects: R2BVAR-M3-012

NA

Counties: BRADLEY, COFFEE, CUMBERLAND,
GRUNDY, HAMILTON, MARION, PUTNAM,
SEQUATCHIE

District:

DBE Goal Percent:

Description: The random on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	500.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	1,700.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	70.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	10.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	20.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	25.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	100.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	500.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	35.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	700.000	L.F.
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	10.000	EACH

Contract ID CNW283 - BRADLEY , COFFEE, ETC.

Item No.	Description	Quantity	Units
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	2.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	4.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	20.000	EACH

() Item will be bid as lump sum.

Contract ID CNW297 - CARROLL , DECATUR, ETC.

Contract ID: CNW297

Letting Date: August 19, 2022 10:00 AM

Projects: R4SVAR-F3-008

HSIP-REG4(217)

Counties: CARROLL, DECATUR, MADISON

District:

DBE Goal Percent: 5.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	342.000	S.Y.
630-01.15	6" PVC (SCHEDULE 40) PIPE	20.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	2,785.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	9,184.000	S.F.
701-02.03	CONCRETE CURB RAMP	2,375.000	S.F.
702-01	CONCRETE CURB	14.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (STOP, R1-1)	1.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	10.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	25.000	L.F.
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	2.000	EACH
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	200.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,050.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (HANDICAP SYMBOL)	2.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW249 - CARTER

Contract ID: CNW249

Letting Date: August 19, 2022 10:00 AM

Projects: 10013-3215-94
10016-3219-94

HSIP-159(10)
HSIP-362(12)

Counties: CARTER

District:

DBE Goal Percent: 6.00

Description: The miscellaneous safety improvements on S.R. 362 from S.R. 361 (L.M. 0.00) to Gap Creek Road (L.M. 5.34) and on U.S. 321 (S.R. 159) from Andrew Finney Road (L.M. 2.83) to Buntontown Road (L.M. 8.14).

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	10.500	L.M.
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	37,790.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,266.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	6,790.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	481.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	5,806.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,000.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	564.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	108.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	134.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	348.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	257.000	L.F.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	21.000	L.M.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	810.000	L.F.
717-01	MOBILIZATION	(1)	LS

Contract ID CNW249 - CARTER

() Item will be bid as lump sum.

Contract ID CNW261 - CHEATHAM , DAVIDSON, ETC.

Contract ID: CNW261

Letting Date: August 19, 2022 10:00 AM

Projects: R3BVAR-M3-018

NA

Counties: CHEATHAM, DAVIDSON, DICKSON, GILES,
HICKMAN, HUMPHREYS, LAWRENCE,
MARSHALL, MAURY, MONTGOMERY,
ROBERTSON, RUTHERFORD, SMITH,
SUMNER, WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The random on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	200.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	2,500.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	125.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	15.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	30.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	15.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	100.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	415.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	30.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	125.000	L.F.

Contract ID CNW261 - CHEATHAM , DAVIDSON, ETC.

Item No.	Description	Quantity	Units
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	4.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	50.000	EACH

() Item will be bid as lump sum.

Contract ID CNW260 - CHEATHAM , DAVIDSON, ETC.

Contract ID: CNW260

Letting Date: August 19, 2022 10:00 AM

Projects: R3BVAR-M3-028

NA

Counties: CHEATHAM, DAVIDSON, ROBERTSON,
RUTHERFORD, SUMNER, WILLIAMSON,
WILSON

District:

DBE Goal Percent:

Description: The random on-call asphalt pothole patching on various Interstate and State Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
411-51.01	POTHOLE EMERGENCY REPAIR (ASPHALT) CONTROLLED-ACCESS	500.000	TON
411-51.02	POTHOLE EMERGENCY REPAIR (ASPHALT) NON- CONTROLLED-ACCESS	250.000	TON
411-51.05	POTHOLE PERMANENT REPAIR (ASPHALT) CONTROLLED-ACCESS	1,500.000	TON
411-51.06	POTHOLE PERMANENT REPAIR (ASPHALT) NON- CONTROLLED-ACCESS	750.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	8.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	140.000	EACH
712-06	SIGNS (CONSTRUCTION)	400.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	15.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	15.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW254 - CHEATHAM , DICKSON, ETC.

Contract ID: CNW254

Letting Date: August 19, 2022 10:00 AM

Projects: R3SVAR-F3-019

HSIP-REG3(215)

Counties: CHEATHAM, DICKSON, HUMPHREYS,
MONTGOMERY

District:

DBE Goal Percent: 5.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
701-02.01	CONCRETE CURB RAMP (RETROFIT)	3,584.000	S.F.
701-02.03	CONCRETE CURB RAMP	110.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	16.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	34.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,728.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	10.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW256 - CHESTER

Contract ID: CNW256

Letting Date: August 19, 2022 10:00 AM

Projects: 12945-3441-94

HSIP-1200(28)

Counties: CHESTER

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	22.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	1.570	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	696.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,256.500	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,417.660	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	644.800	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	758.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	1,165.800	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	17.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	306.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	6.670	S.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	34.510	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW280 - CLAY

Contract ID: CNW280

Letting Date: August 19, 2022 10:00 AM

Projects: 14002-3258-94
14002-3259-94

PHSIP-52(93)
PHSIP-52(94)

Counties: CLAY

District:

DBE Goal Percent: 3.50

Description: The miscellaneous safety improvements on S.R. 52 from Hill Top Road to Harve Knight Road (L.M. 0.69 to L.M. 3.08) and from near Meadow Lane to Hummingbird Lane (L.M. 14.00 to L.M. 15.00).

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	920.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.20	ROADSIDE OBSTACLE DELINEATION	5.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	342.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	250.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	247.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,802.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	757.000	LB.
713-11.21	P POST SLIP BASE	6.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	242.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	503.500	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	53.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	44.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	22.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	176.000	L.F.
716-09.31	STOP LINE	72.000	L.F.

Contract ID CNW280 - CLAY

Item No.	Description	Quantity	Units
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	12.200	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	630.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW284 - CLAY

Contract ID: CNW284

Letting Date: August 19, 2022 10:00 AM

Projects: 14NMSC-S3-003

NA

Counties: CLAY

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 40')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW272 - COCKE

Contract ID: CNW272

Letting Date: August 19, 2022 10:00 AM

Projects: 15I040-M3-016

NA

Counties: COCKE

District:

DBE Goal Percent:

Description: The replacement of a rockfall catchment fence on I-40 EB at MM 444.3 (L.M. 14.44).

Contract Time: DT - 5/31/2023

Item No.	Description	Quantity	Units
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	500.000	C.Y.
707-10.01	ROCKFALL FENCE (TYPE I)	120.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW234 - CUMBERLAND

Contract ID: CNW234

Letting Date: August 19, 2022 10:00 AM

Projects: 18003-3244-04

N/A

Counties: CUMBERLAND

District:

DBE Goal Percent:

Description: The installation of a flashing beacon and miscellaneous safety improvements on U.S. 70 (S.R. 1) at the intersection of Market Street (L.M. 24.84) in Crab Orchard.

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	128.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	137.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	17.000	EACH
712-06	SIGNS (CONSTRUCTION)	228.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.09	REMOVABLE PAVEMENT MARKING (4" line)	120.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	20.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	75.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	75.000	LB.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	45.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	200.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	40.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	36.000	S.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.100	L.M.

Contract ID CNW234 - CUMBERLAND

Item No.	Description	Quantity	Units
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	200.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	46.000	L.F.
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	83.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	5,805.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	400.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	106.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	83.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (RXR)	4.000	EACH
716-08.19	REMOVAL OF PAVEMENT MARKING (YIELD LINE)	36.000	S.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.100	L.M.
717-01	MOBILIZATION	(1)	LS
730-02.01	SIGNAL HEAD ASSEMBLY (110)	2.000	EACH
730-02.21	SIGNAL HEAD ASSEMBLY (220)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	101.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	118.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	118.000	L.F.
730-15.07	CABINET (DESCRIPTION) (NEMA TYPE 3R FLASHING SIGNAL CONTROLLER)	1.000	EACH
730-16.03	CONTROLLER (FLASHING BEACON)	1.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNW018 - CUMBERLAND

Contract ID: CNW018

Letting Date: August 19, 2022 10:00 AM

Projects: 18006-4219-04

NA

Counties: CUMBERLAND

District:

DBE Goal Percent:

Description: The repair of bridges on U.S. 127 (S.R. 28) over Byrds Creek (L.M. 10.69) and Three Mile Creek (L.M. 11.08).

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
201-05.31	VEGETATION REMOVAL	(1)	LS
204-06.01	FLOWABLE FILL (GENERAL)	6.500	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	275.000	L.F.
603-02.15	REPAINT EXISTING BEARINGS	(1)	LS
604-10.05	CONCRETE	415.000	S.F.
604-10.54	CONCRETE REPAIRS	245.000	S.F.
604-10.58	EPOXY INJECTION (INJECTION)	23.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	439.000	L.F.
610-10.45	DECK DRAINS (DESCRIPTION) (SPAN 2, LEFT SIDE EXTEND DRAIN)	1.000	EACH
705-01.04	METAL BEAM GUARD FENCE	200.000	L.F.
706-01	GUARDRAIL REMOVED	102.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	296.000	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
717-01	MOBILIZATION	(1)	LS
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	150.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW285 - CUMBERLAND

Contract ID: CNW285

Letting Date: August 19, 2022 10:00 AM

Projects: 18NMSC-S3-004

NA

Counties: CUMBERLAND

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 100')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW253 - DAVIDSON , SUMNER, ETC.

Contract ID: CNW253

Letting Date: August 19, 2022 10:00 AM

Projects: R3SVAR-F3-018

HSIP-REG3(214)

Counties: DAVIDSON, SUMNER, WILLIAMSON

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
701-01.01	CONCRETE SIDEWALK (4 ")	100.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	6,270.000	S.F.
701-02.03	CONCRETE CURB RAMP	200.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	924.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,240.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	10.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW294 - DEKALB

Contract ID: CNW294

Letting Date: August 19, 2022 10:00 AM

Projects: 21NMSC-S3-002

NA

Counties: DEKALB

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 60')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW251 - DYER

Contract ID: CNW251

Letting Date: August 19, 2022 10:00 AM

Projects: 23945-3482-94

HSIP-2300 (45)

Counties: DYER

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	2,335.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	4.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	497.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	565.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,421.000	LB.
713-11.21	P POST SLIP BASE	69.000	EACH
713-11.22	U POST SLIP BASE	20.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	303.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	468.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	35.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	137.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	42.998	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW252 - GIBSON

Contract ID: CNW252

Letting Date: August 19, 2022 10:00 AM

Projects: 27946-3418-94

HSIP-2700 (62)

Counties: GIBSON

District:

DBE Goal Percent: 4.00

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-01.01	GUARDRAIL AT BRIDGE ENDS	80.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	6,870.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	10.000	S.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	140.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.11	REMOVAL OF EXISTING DELINEATORS	2.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,239.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,374.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,861.000	LB.
713-11.21	P POST SLIP BASE	145.000	EACH
713-11.22	U POST SLIP BASE	45.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	686.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	872.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	79.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	12.000	S.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	68.700	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	1,100.000	L.F.

Contract ID CNW252 - GIBSON

Item No.	Description	Quantity	Units
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	2,267.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW262 - GRAINGER

Contract ID: CNW262

Letting Date: August 19, 2022 10:00 AM

Projects: 29001-3233-04

N/A

Counties: GRAINGER

District:

DBE Goal Percent:

Description: The installation of signals on U.S. 11W (S.R. 1) at the intersection of S.R. 61/Indian Ridge Road (L.M. 1.81) in Blaine.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
209-05	SEDIMENT REMOVAL	10.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	160.000	L.F.
209-09.43	CURB INLET PROTECTION (TYPE 4)	5.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	178.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	60.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (M3-4, 24"x12")	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (M5-1R, 21"x15")	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (R3-8, 30"x30")	2.000	EACH
713-16.23	SIGNS (DESCRIPTION) (R3-17, 24"x18")	2.000	EACH
713-16.24	SIGNS (DESCRIPTION) (TN-6A, 24"x24")	1.000	EACH
713-16.25	SIGNS (DESCRIPTION) (W3-3, 30"x30")	4.000	EACH
714-04.03	CONDUIT (DESCRIPTION) (LIGHTING - 1" RGS)	100.000	L.F.

Contract ID CNW262 - GRAINGER

Item No.	Description	Quantity	Units
714-05.04	PULL BOXES (TYPE C)	3.000	EACH
714-08.50	REMOVE WOOD POLE & ROADWAY LUMINARE	1.000	EACH
714-09.03	LUMINAIRES (250 WATT)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	58.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	37.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	65.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	10.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	145.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	5.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	190.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	305.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	400.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	4.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	20.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	100.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	50.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	7.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT- TURN ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	40.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	2.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	2.000	L.M.

Contract ID CNW262 - GRAINGER

Item No.	Description	Quantity	Units
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	400.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	4.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	4.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,365.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	410.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC)	20.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC)	100.000	L.F.
730-12.08	CONDUIT 2" DIAMETER (RGS)	30.000	L.F.
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	350.000	L.F.
730-12.14	CONDUIT 3" DIAMETER (JACK AND BORE)	350.000	L.F.
730-13.13	VEHICLE DETECTOR (RADAR)	8.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (10' PEDESTAL POLE TYPE A)	1.000	EACH
730-23.36	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 50')	1.000	EACH
730-23.37	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 55')	1.000	EACH
730-23.38	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 60')	1.000	EACH
730-23.39	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 65')	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSH BUTTON & 15IN SIGN	8.000	EACH
803-01	SODDING (NEW SOD)	25.000	S.Y.

Contract ID CNW262 - GRAINGER

() Item will be bid as lump sum.

Contract ID CNW269 - HOUSTON

Contract ID: CNW269

Letting Date: August 19, 2022 10:00 AM

Projects: 42002-3213-94

BR-STP-49(48)

Counties: HOUSTON

District:

DBE Goal Percent: 7.50

Description: The construction of a concrete box beam bridge on S.R. 49 (East Main Street) over Wells Creek (L.M. 5.87) in Erin, including grading, drainage and paving.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,180.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (18" CMP, STA. 64+52.08)	42.000	L.F.
202-01.14	REMOVAL OF PIPE (SIZE, STA.) (18" CMP, STA. 65+48.06)	40.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	514.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	1,620.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	536.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	165.000	C.Y.
203-06	WATER	32.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.400	L.M.
209-05	SEDIMENT REMOVAL	27.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	838.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	6.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	3.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	1.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	1.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	143.000	L.F.

Contract ID CNW269 - HOUSTON

Item No.	Description	Quantity	Units
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,210.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	847.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	349.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	229.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.800	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	10.100	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.400	TON
411-02.10	ACS MIX(PG70-22) GRADING D	503.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	85.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	266.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	127.000	L.F.
611-01.03	MANHOLES, > 8' - 12' DEPTH	1.000	EACH
611-07.31	18IN ENDWALL (SIDE DRAIN)	1.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	1.000	EACH
620-05.10	CONCRETE PARAPET CURVED WALL (<=TO 40MPH)	24.000	L.F.
621-03.02	18" TEMPORARY DRAINAGE PIPE	50.000	L.F.
702-03	CONCRETE COMBINED CURB & GUTTER	43.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	182.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	3.000	EACH
705-08.11	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	340.000	L.F.
706-10.26	ROUNDED END ELEMENT	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	115.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	124.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	705.000	TON

Contract ID CNW269 - HOUSTON

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	650.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	19.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-06	SIGNS (CONSTRUCTION)	890.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	140.000	L.F.
713-02.26	CONCRETE BARRIER/PARAPET DELINEATOR	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	5.000	EACH
713-16.90	RESET GROUND MOUNTED SIGN	14.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	37.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	37.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	15.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	13.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	250.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	15.000	S.Y.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.800	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,427.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	342.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,428.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	870.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	20.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	7.700	UNIT
801-02.01	CROWN VETCH MIXTURE (WITHOUT MULCH)	12.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.200	M.G.

Contract ID CNW269 - HOUSTON

Item No.	Description	Quantity	Units
805-12.02	EROSION CONTROL BLANKET (TYPE II)	400.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EX. BR. NO. 42-SR049-05.87)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	130.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	62.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	21,770.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	54.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	8,677.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	58.000	C.Y.
604-03.74	CLASS X CONCRETE	47.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,172.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-10.39	PRECAST REINFORCED CONCRETE UNITS	1,230.000	S.F.
606-02.03	STEEL PILES (10 INCH)	540.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	16.000	EACH
606-20.03	STEEL PIPE PILES (18-INCH)	564.000	L.F.
606-20.06	PILE TIPS (STEEL PIPE PILES, 18-INCH)	14.000	EACH
615-02.37	PRESTRESSED CONCRETE BOX BEAM (30" X 36")	1,028.000	L.F.
615-04.03	PRECAST DECK PANEL (5,000 PSI)	201.000	C.Y.
615-04.10	NON-SHRINK GROUT	134.000	C.F.
615-04.11	EPOXY GROUT	8.000	C.F.
615-04.30	PRECAST BRIDGE ABUTMENT WALL	32.000	C.Y.
615-04.40	PRECAST BRIDGE CAP BEAM	36.000	C.Y.
617-01	BRIDGE DECK SEALANT	1,184.000	S.Y.
620-06	CONCRETE RAILING	471.000	L.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	33.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	126.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	26.000	L.F.

Contract ID CNW269 - HOUSTON

() Item will be bid as lump sum.

Contract ID CNW287 - JACKSON

Contract ID: CNW287

Letting Date: August 19, 2022 10:00 AM

Projects: 44NMSC-S3-003

NA

Counties: JACKSON

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 40')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW295 - JEFFERSON , SEVIER, ETC.

Contract ID: CNW295

Letting Date: August 19, 2022 10:00 AM

Projects: R1SVAR-F3-014

HSIP-REG1(211)

Counties: JEFFERSON, SEVIER, SULLIVAN,
WASHINGTON

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
701-01.02	CONCRETE SIDEWALK (6 ")	155.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	9,421.000	S.F.
701-02.03	CONCRETE CURB RAMP	1,075.000	S.F.
702-01	CONCRETE CURB	1.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	1.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	873.000	S.F.
713-15.40	SIGN INSTALLATION (DESCRIPTION)	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-26.07	FLASHING WARNING BEACON (DESCRIPTION) (DESCRIPTION)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNW267 - KNOX

Contract ID: CNW267

Letting Date: August 19, 2022 10:00 AM

Projects: 471040-M3-003

NA

Counties: KNOX

District:

DBE Goal Percent:

Description: The repair of the bridges on I-40 over 17th Street (L.M. 18.30).

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-20.21	LOW MAINT CRASH CUSHION WIDE (MASH TL-3)	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	770.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	190.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	990.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	26.000	L.F.
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	1,062.000	HOURL
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	41,740.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	23,440.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	2,300.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
717-01	MOBILIZATION	(1)	LS
603-02.01	REPAINTING EXISTING STEEL STRUCTURES (LOC. & DES.) (BRIDGE NO. 47-140-18.30 R&L)	(1)	LS
603-05.20	CONTAINMENT & DISPOSAL OF WASTE(LOCATION & DESCRP) (BR. NO. 47-I40-18.30 R & L)	(1)	LS
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	50.000	LB.

Contract ID CNW267 - KNOX

Item No.	Description	Quantity	Units
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	2,951.000	S.Y.
604-10.05	CONCRETE	172.000	S.F.
604-10.22	CONCRETE PARAPET REPAIR	92.000	L.F.
604-10.29	CONCRETE SLOPE PAVING REPAIRS	15.000	S.Y.
604-10.54	CONCRETE REPAIRS	157.000	S.F.
604-10.55	CONCRETE (FOUNDATION REPAIRS)	6.000	C.Y.
604-10.58	EPOXY INJECTION (INJECTION)	1.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	45.000	L.F.
604-10.83	COMPOSITE FIBER ENCASMENT	1,318.000	S.F.
604-10.89	MISCELLANEOUS BRIDGE ITEMS (Description) (JET FILTER SYSTEM 4" DIA. OPEN END)	(1)	LS
620-09	REMOVAL & REPLACEMENT OF EXISTING BRIDGE RAIL	15.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW273 - LAUDERDALE

Contract ID: CNW273

Letting Date: August 19, 2022 10:00 AM

Projects: 49946-3411-94

HSIP-4900(70)

Counties: LAUDERDALE

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	985.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	32.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	3.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	637.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	615.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,482.000	LB.
713-11.21	P POST SLIP BASE	75.000	EACH
713-11.22	U POST SLIP BASE	23.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	326.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	489.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	56.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	3.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	312.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	40.340	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	1,485.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW275 - MADISON

Contract ID: CNW275

Letting Date: August 19, 2022 10:00 AM

Projects: 57201-3160-44
57201-3161-44

NH-SIP-I-40-1(363)
HSIP-I-40-1(365)

Counties: MADISON

District:

DBE Goal Percent: 7.00

Description: The ramp improvement on I-40 (Exit 93) at the S.R. 152 (Law Road) interchange (L.M. 25.85 - L.M. 26.86) and miscellaneous safety improvements on I-40 from L.M. 22.35 - L.M. 27.95.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	2,900.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	16,349.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	243.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	3,514.000	C.Y.
203-06	WATER	232.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	3,176.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	7.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	23.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	2.000	L.M.
209-03.23	FILTER SOCK (24 INCH)	1,080.000	L.F.
209-05	SEDIMENT REMOVAL	413.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,320.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	825.000	L.F.
209-08.07	ROCK CHECK DAM	7.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	7.000	EACH
209-09.01	SANDBAGS	300.000	BAG

Contract ID CNW275 - MADISON

Item No.	Description	Quantity	Units
209-09.04	SEDIMENT FILTER BAG(15' X 10')	1.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	10.000	S.Y.
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	10.000	S.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	591.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	11,514.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	110.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	67.000	TON
307-01.22	ASP. CONC. MIX(PG76-22) (BPMB-HM) GR. A-S	458.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	1,004.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,184.000	TON
307-03.10	ASPHALT CONC MIX (PG76-22)(BPMB-HM) GR CS	302.000	TON
309-01.01	MINERAL AGGREGATE (A-CBC)	2,582.000	TON
309-01.02	PORTLAND CEMENT (A-CBC)	126.000	TON
309-02	BITUMINOUS MATERIAL (A-CBC)	8.000	TON
313-03	TREATED PERMEABLE BASE	5,623.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	12.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	38.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	8.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	2,750.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	30.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	575.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	3.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	394.000	TON
501-01.06	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 13"	5,623.000	S.Y.
502-03.13	CONCRETE PAVEMENT REMOVAL	2,550.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	2,780.000	L.F.
604-01.01	CLASS A CONCRETE (ROADWAY)	45.000	C.Y.

Contract ID CNW275 - MADISON

Item No.	Description	Quantity	Units
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	7,872.000	LB.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	160.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	60.000	L.F.
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	4.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	147.000	LB.
611-07.64	36IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.73	18IN ENDWALL (MEDIAN DRAIN)	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	80.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	84.000	L.F.
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	5,600.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	350.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	3,368.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	150.000	L.F.
707-03.01	STOCK FENCE	350.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	6.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (STOCK R.O.W. FENCE)	350.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	970.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	420.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	195.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	34.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	480.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	5,530.000	L.F.
710-05	LATERAL UNDERDRAIN	392.000	L.F.
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	28.000	EACH

Contract ID CNW275 - MADISON

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	5,950.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	214.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	300.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	70.000	EACH
712-06	SIGNS (CONSTRUCTION)	850.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	200.000	HOUR
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	37,580.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	121.000	LB.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	370.000	EACH
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	1,451.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	150.000	LB.
713-11.01	"U" SECTION STEEL POSTS	224.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	44.000	LB.
713-11.22	U POST SLIP BASE	4.000	EACH
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	51.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	338.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	250.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	67.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	276.000	EACH

Contract ID CNW275 - MADISON

Item No.	Description	Quantity	Units
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	350.000	L.F.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	7.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	6.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,978.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,367.000	S.Y.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	10,760.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	400.000	UNIT
801-03	WATER (SEEDING & SODDING)	408.000	M.G.
803-01	SODDING (NEW SOD)	46,563.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW250 - MARION

Contract ID: CNW250

Letting Date: August 19, 2022 10:00 AM

Projects: 58946-3406-94

HSIP-5800(47)

Counties: MARION

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	9.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	215.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	528.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,612.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,532.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	266.250	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	709.500	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	87.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	537.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	257.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	3.000	EACH
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	32.600	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW153 - MARSHALL

Contract ID: CNW153

Letting Date: August 19, 2022 10:00 AM

Projects: 59003-3226-94

BR-STP-11(99)

Counties: MARSHALL

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete Bulb-Tee beam bridge on U.S. 31A (S.R. 11, Nashville Highway) over Rock Creek (L.M. 13.18) in Lewisburg, including grading, drainage and paving.

Contract Time: DT - 11/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,180.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	470.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,088.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	88.000	C.Y.
203-06	WATER	44.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	52.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,143.000	L.F.
209-08.07	ROCK CHECK DAM	3.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-08.09	FILTER SOCK CHECK DAM	7.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	668.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,131.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,082.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	274.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	182.000	TON

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	12.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	187.000	TON
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	100.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	70.000	LB.
621-03.02	18" TEMPORARY DRAINAGE PIPE	80.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	325.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	384.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	216.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	6.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	261.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	400.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	21.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	6.000	EACH
712-06	SIGNS (CONSTRUCTION)	421.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	52.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	2,124.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	50.000	L.F.
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	5.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	11.000	EACH

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	11.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.600	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.01	GEO GRID REINFORCEMENT	1,326.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,960.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	500.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	710.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	805.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	10.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	5.000	UNIT
801-03	WATER (SEEDING & SODDING)	8.000	M.G.
802-02.33	CUTTINGS: SAMBUCUS CANADENSIS (18IN-24IN)	1,340.000	EACH
802-12.02	ACER RUBRUM (RED MAPLE SEEDLNG B.R.)	30.000	EACH
802-12.17	JUGLANS NIGRA (BLACK WALNUT SEEDLNG B.R.)	30.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	30.000	EACH
803-01	SODDING (NEW SOD)	529.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	446.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 59-SR11-13.18)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	339.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	41.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	72.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	48.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.1,STA.75+13.00)	(1)	LS

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.2,STA.76+05.00)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	27.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	63.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	34.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	85,159.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	338.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	46,438.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	235.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	365.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,605.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,533.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	252.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	18.000	EACH
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	1,358.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	324.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	2.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	620.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	148.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	48.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW282 - MCMINN

Contract ID: CNW282

Letting Date: August 19, 2022 10:00 AM

Projects: 54023-4225-04

N/A

Counties: MCMINN

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 163 over Chestuee Creek (L.M. 11.74).

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
209-05	SEDIMENT REMOVAL	1.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	730.000	L.F.
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	91.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	190.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	0.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	152.000	TON
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	18.000	EACH
706-02.01	GUARDRAIL REMOVED AND RESET	60.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	160.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	380.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	22.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,362.000	S.F.

Contract ID CNW282 - MCMINN

Item No.	Description	Quantity	Units
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,800.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	7.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	9.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	9.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.550	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 54-SR163-11.74)	(1)	LS
602-10.01	STRUCTURAL STEEL REPAIRS	(1)	LS
603-02.01	REPAINTING EXISTING STEEL STRUCTURES (LOC. & DES.) (BRIDGE NO. 54-SR163-11.74)	(1)	LS
603-05.20	CONTAINMENT & DISPOSAL OF WASTE(LOCATION & DESCRP) (BRIDGE NO. 54-SR163.1174)	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	8,663.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	7.000	C.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	31.000	C.Y.
604-10.05	CONCRETE	77.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.18	REINFORCING STEEL (REPAIRS)	139.000	LB.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	21.000	S.Y.
604-10.44	EXPANSION JOINT REPAIRS	324.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	21.000	S.Y.
604-10.54	CONCRETE REPAIRS	76.000	S.F.
604-10.58	EPOXY INJECTION (INJECTION)	1.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	2.000	L.F.

Contract ID CNW282 - MCMINN

Item No.	Description	Quantity	Units
604-10.90	MISCELLANEOUS BRIDGE ITEMS	(1)	LS
610-10.40	BRIDGE DECK DRAINS	(1)	LS
615-02.52	PRESTRESSED CONCRETE BOX BEAM (--" X --") (16" X 48")	114.000	L.F.
617-01	BRIDGE DECK SEALANT	932.000	S.Y.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	7.000	TON

() Item will be bid as lump sum.

Contract ID CNW276 - OBION

Contract ID: CNW276

Letting Date: August 19, 2022 10:00 AM

Projects: 66001-3284-94

R-NH-SIP-3(142)

Counties: OBION

District:

DBE Goal Percent: 3.00

Description: The grading, drainage and paving on U.S. 51 (S.R. 3) at the intersection of Wynridge Street/Gates Drive (L.M. 11.42).

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03.03	REMOVAL OF ASPHALT PAVEMENT	219.000	C.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	500.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	669.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	78.000	C.Y.
203-06	WATER	17.000	M.G.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	2.000	C.Y.
209-05	SEDIMENT REMOVAL	20.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	100.000	L.F.
209-09.01	SANDBAGS	25.000	BAG
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	50.000	S.Y.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,005.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	25.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	25.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	453.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	167.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	7.000	TON

Contract ID CNW276 - OBION

Item No.	Description	Quantity	Units
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,000.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	97.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.240	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	152.000	S.Y.
621-03.02	18" TEMPORARY DRAINAGE PIPE	18.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	87.000	C.Y.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	50.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	2,060.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	54.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	103.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	40.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	330.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,260.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	75.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	325.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	185.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	131.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	109.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	32.000	EACH

Contract ID CNW276 - OBION

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	17.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	62.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	15.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.300	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	632.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	110.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	86.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	540.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	24.000	UNIT
801-03	WATER (SEEDING & SODDING)	7.000	M.G.
803-01	SODDING (NEW SOD)	470.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW257 - PERRY

Contract ID: CNW257

Letting Date: August 19, 2022 10:00 AM

Projects: 68001-3258-94

PHSIP-13(88)

Counties: PERRY

District:

DBE Goal Percent: 6.00

Description: The miscellaneous safety improvements on S.R. 13 from 4-H Lane (L.M. 2.39)to Baptist Camp Road (L.M. 5.61).

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	8.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	4,140.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	4,140.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	816.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	427.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	267.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	94.750	S.F.
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	280.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	105.000	L.F.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	12.900	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW288 - PUTNAM

Contract ID: CNW288

Letting Date: August 19, 2022 10:00 AM

Projects: 71NMSC-S3-002

NA

Counties: PUTNAM

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 100')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW258 - RUTHERFORD

Contract ID: CNW258

Letting Date: August 19, 2022 10:00 AM

Projects: 75840-3135-94
75840-3138-54

HSIP-I-840(16)
STP-M-I-840(19)

Counties: RUTHERFORD

District:

DBE Goal Percent: 4.00

Description: The installation of signals and lighting at the I-840/Veteran's Parkway interchange and widening of the I-840 WB ramp to Veteran's Parkway (L.M. 5.04 - L.M. 5.83).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,017.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	743.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	258.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	3.800	C.Y.
209-02.03	8" TEMPORARY SLOPE DRAIN	800.000	L.F.
209-03.22	FILTER SOCK (18 INCH)	493.140	L.F.
209-05	SEDIMENT REMOVAL	9.404	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	650.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	1,009.224	L.F.
209-08.07	ROCK CHECK DAM	2.000	EACH
209-09.01	SANDBAGS	120.000	BAG
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	500.000	S.Y.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	122.015	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	39.556	TON
313-03	TREATED PERMEABLE BASE	386.812	S.Y.
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	342.790	S.Y.
621-03.02	18" TEMPORARY DRAINAGE PIPE	50.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	350.000	L.F.

Contract ID CNW258 - RUTHERFORD

Item No.	Description	Quantity	Units
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	760.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	500.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	731.808	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	375.000	L.F.
710-05	LATERAL UNDERDRAIN	63.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	505.769	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	10.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	10.115	EACH
712-05.01	WARNING LIGHTS (TYPE A)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	886.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	682.000	L.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	32.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W3-3, 48"X48")	4.000	EACH
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (R5-1A, 42"X30")	4.000	EACH
713-16.51	REMOVE AND REPLACE SIGN (DESCRIPTION) (R5-1, 48"X48")	4.000	EACH
713-16.52	REMOVE AND REPLACE SIGN (DESCRIPTION) (R6-1R, 54"X18")	4.000	EACH
713-16.53	REMOVE AND REPLACE SIGN (DESCRIPTION) (R6-1L, 54"X18")	4.000	EACH
713-16.54	REMOVE AND REPLACE SIGN (DESCRIPTION) (E5-1A, 96"X60")	1.000	EACH
714-03	JACKED OR BORED CONDUIT	1,275.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	11,810.000	L.F.

Contract ID CNW258 - RUTHERFORD

Item No.	Description	Quantity	Units
714-03.02	DIRECT BURIAL CONDUIT (3" PVC, SCHEDULE 40)	840.000	L.F.
714-04.01	CONDUIT (STRUCTURES - 1" RGS)	240.000	L.F.
714-05.04	PULL BOXES (TYPE C)	32.000	EACH
714-05.05	PULL BOXES (DESCRIPTION) (JUNCTION BOX 6"X6")	2.000	EACH
714-05.06	PULL BOXES (DESCRIPTION) (SECONDARY PULL BOX (LARGE))	12.000	EACH
714-06.05	CABLE (1/C # 6 AWG)	6,420.000	L.F.
714-06.06	CABLE (1/C # 4 AWG)	9,045.000	L.F.
714-06.07	CABLE (1/C # 2 AWG)	27,785.000	L.F.
714-06.08	CABLE (DESCRIPTION) (#6 AWG SOLID COPPER SOFT DRAWN)	13,915.000	L.F.
714-06.09	CABLE (DESCRIPTION) (#6 SOLID COPPER SOFT DRAWN) (GROUND)	1,670.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (45' M.H.)	19.000	EACH
714-08.10	LIGHT STANDARDS (DESCRIPTION) (130'HIGH MAST)	4.000	EACH
714-08.11	LIGHT STANDARDS (DESCRIPTION) (120' HIGH MAST)	4.000	EACH
714-08.23	FOUNDATION (ONLY) FOR LIGHT STANDARDS	19.000	EACH
714-08.46	FOUNDATION (ONLY) FOR HIGH MAST LIGHT STANDARD	8.000	EACH
714-09.09	LUMINAIRES (DESCRIPTION) (255 WATT-LED)	19.000	EACH
714-09.10	LUMINAIRES (DESCRIPTION) (295 WATT-LED HIGH MAST)	44.000	EACH
714-09.11	LUMINAIRES (DESCRIPTION) (81 WATT-LED UNDERPASS)	4.000	EACH
714-12.01	CONTROL CENTER (NO. 1)	(1)	LS
714-12.02	CONTROL CENTER (NO. 2)	(1)	LS
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO.1)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO.2)	(1)	LS
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	97.900	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	245.000	L.F.

Contract ID CNW258 - RUTHERFORD

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	379.830	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.165	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	441.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	2.079	L.M.
716-09.87	CONTRAST PAVEMENT MARKINGS WORDS AND SYMBOLS	12.000	EACH
716-09.88	CONTRAST PAVEMENT MARKING 8"	0.165	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	1.001	L.M.
716-13.03	SPRAY THERMO PVMT MRKNG (60 mil) (8IN BARRIER LINE)	441.000	L.F.
717-01	MOBILIZATION	(1)	LS
725-02.16	CONDUIT (STRUCTURES - DESCRIPTION) (STRUCTURES)	550.000	L.F.
725-03.80	CCTV CAMERA SYSTEM	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	9.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (140 A1 WITH BACKPLATE)	1.000	EACH
730-02.31	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130 A3 WITH BACKPLATE)	3.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	7.000	EACH
730-03.23	INSTALL PULL BOX (FIBER OPTIC-TYPE A)	3.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	3.000	EACH
730-03.33	FIBER OPTIC SPLICE FUSION	2.000	EACH
730-03.35	FIBER OPTIC TERMINATION SPLICE UNIT	2.000	EACH
730-03.36	FIBER SPLICE ENCLOSURE (DESCRIPTION) (48F)	3.000	EACH
730-03.40	NETWORK SWITCH (DESCRIPTION) (CISCO 3200 SERIES)	2.000	EACH
730-03.50	FIBER OPTIC CABLE (48F)	2,090.000	L.F.
730-03.55	FIBER OPTIC DROP CABLE (6F)	100.000	L.F.
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	2,325.000	L.F.

Contract ID CNW258 - RUTHERFORD

Item No.	Description	Quantity	Units
730-12.02	CONDUIT 2" DIAMETER (PVC)	1,900.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC)	575.000	L.F.
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	90.000	L.F.
730-12.14	CONDUIT 3" DIAMETER (JACK AND BORE)	610.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (RADAR DETECTION - STOP LINE)	6.000	EACH
730-13.09	VEHICLE DETECTOR (DESCRIPTION) (RADAR DETECTION - ADVANCE)	6.000	EACH
730-15.07	CABINET (DESCRIPTION) (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-24.41	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 70' AND 40' CCTV ARM)	1.000	EACH
730-24.42	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (2 @ 55' & 65' AND 40' CCTV ARM)	1.000	EACH
730-24.89	CANTILEVER SIGNAL SUPPORT (2 @ 40' & 70')	1.000	EACH
730-25.17	CANTILEVER SIGNAL SUPPORT (1 ARM @ 85')	1.000	EACH
730-35.50	ROAD SIDE UNIT (RSU)	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,861.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	600.000	L.F.
801-01	SEEDING (WITH MULCH)	30.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	57.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	27.000	UNIT
801-03	WATER (SEEDING & SODDING)	6.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	1,498.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW281 - SHELBY

Contract ID: CNW281

Letting Date: August 19, 2022 10:00 AM

Projects: R4SVAR-F3-009

HSIP-REG4(218)

Counties: SHELBY

District:

DBE Goal Percent: 6.00

Description: The ADA curb ramp upgrades on various routes in Memphis.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	488.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	174.000	C.Y.
411-01.10	ACS MIX(PG64-22) GRADING D	1.000	TON
701-01.01	CONCRETE SIDEWALK (4 ")	4,071.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	6,670.000	S.F.
701-02.03	CONCRETE CURB RAMP	2,530.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	416.000	S.F.
702-01	CONCRETE CURB	38.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (STOP, R1-1)	3.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	36.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	100.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	1.000	M.G.
803-01	SODDING (NEW SOD)	108.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW290 - SHELBY

Contract ID: CNW290

Letting Date: August 19, 2022 10:00 AM

Projects: 79S004-F3-002
79S004-F8-002
79S004-M3-005

NH/HSIP-4(12)
NH/HSIP-4(12)
NH/HSIP-4(12)

Counties: SHELBY

District:

DBE Goal Percent: 6.50

Description: The resurfacing on U.S. 78 (S.R. 4) from S.R. 176 (L.M. 5.34) to near I-240 (L.M. 7.68), including bridge deck and expansion joint repairs.

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	698.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,712.000	S.Y.
203-06	WATER	1.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	2.400	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	44.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	13.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	447.000	TON
403-02.01	TRACKLESS TACK COAT	54.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	8,227.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,070.000	TON
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	8.000	C.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	90.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	50.000	EACH
502-04.03	TRANSVERSE TIE-BARS	27.000	EACH
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	15,750.000	LB.
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	31.000	EACH

Contract ID CNW290 - SHELBY

Item No.	Description	Quantity	Units
701-01.01	CONCRETE SIDEWALK (4 ")	3,360.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	3,989.000	S.F.
701-02.03	CONCRETE CURB RAMP	2,918.000	S.F.
702-01	CONCRETE CURB	10.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	2,410.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	181.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	92.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	130.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	96.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,752.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	128.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	7,709.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	14.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
714-05.03	PULL BOXES (TYPE B)	7.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	267.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	578.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	1,080.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	45.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	618.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	25.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	885.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	20.000	EACH

Contract ID CNW290 - SHELBY

Item No.	Description	Quantity	Units
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	45.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	13.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,931.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	13.400	L.M.
717-01	MOBILIZATION	(1)	LS
730-12.01	CONDUIT 1" DIAMETER (PVC)	110.000	L.F.
730-14.02	SAW SLOT	2,545.000	L.F.
730-14.03	LOOP WIRE	6,290.000	L.F.
730-26.14	PEDESTRIAN PUSHBUTTON ADJUSTMENT	28.000	EACH
604-10.44	EXPANSION JOINT REPAIRS	414.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	41.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW265 - SULLIVAN

Contract ID: CNW265

Letting Date: August 19, 2022 10:00 AM

Projects: 82011-4233-04

N/A

Counties: SULLIVAN

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 93 over the South Fork Holston River and Plant Road (L.M. 7.82).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	325.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	200.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,160.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	65.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	25.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.300	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1.100	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.100	TON
411-02.10	ACS MIX(PG70-22) GRADING D	325.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	1.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	4,400.000	S.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	475.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	735.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	350.000	L.F.

Contract ID CNW265 - SULLIVAN

Item No.	Description	Quantity	Units
709-05.06	MACHINED RIP-RAP (CLASS A-1)	25.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,760.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	390.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	65.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	6.000	EACH
712-06	SIGNS (CONSTRUCTION)	890.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	36.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	38,000.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	36.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	35.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	35.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	2,150.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	560.000	S.Y.
201-05.31	VEGETATION REMOVAL	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 82-SR093-07.82)	(1)	LS
603-02.01	REPAINTING EXISTING STEEL STRUCTURES (LOC. & DES.) (BR. NO. 82-SR093-07.82)	(1)	LS
603-05.20	CONTAINMENT & DISPOSAL OF WASTE(LOCATION & DESCRP) (BR. NO. 82-SR093-07.82)	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	396,750.000	LB.

Contract ID CNW265 - SULLIVAN

Item No.	Description	Quantity	Units
604-03.04	PAVEMENT @ BRIDGE ENDS	335.000	S.Y.
604-03.35	CLASS L CONCRETE	800.000	C.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	3,000.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	3,340.000	S.Y.
604-10.05	CONCRETE	5.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.54	CONCRETE REPAIRS	5.000	S.F.
604-10.55	CONCRETE (FOUNDATION REPAIRS)	10.000	C.Y.
604-10.58	EPOXY INJECTION (INJECTION)	4.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	40.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	1,060.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW278 - TIPTON

Contract ID: CNW278

Letting Date: August 19, 2022 10:00 AM

Projects: 84946-3405-94

HSIP-8400(85)

Counties: TIPTON

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2023

Item No.	Description	Quantity	Units
303-01.09	MINERAL AGGREGATE, TYPE A BASE,GRADING D LIMESTONE	125.050	TON
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	592.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	525.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	585.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	786.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,424.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,688.000	LB.
713-11.21	P POST SLIP BASE	40.000	EACH
713-11.22	U POST SLIP BASE	45.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	530.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	322.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	45.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	1.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	363.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	46.000	L.M.

Contract ID CNW278 - TIPTON

Item No.	Description	Quantity	Units
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	2,088.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW263 - WASHINGTON

Contract ID: CNW263

Letting Date: August 19, 2022 10:00 AM

Projects: 90946-3465-04

N/A

Counties: WASHINGTON

District:

DBE Goal Percent:

Description: The grading, drainage and paving on a S.I.A. route serving Project Starlight, including restriping at the intersection of U.S. 321 (U.S. 11E, S.R. 34) and Precision Boulevard/Stockyard Road in Telford.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	22,839.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	1,814.000	TON
203-04	PLACING AND SPREADING TOPSOIL	1,721.000	C.Y.
203-06	WATER	87.000	M.G.
204-06.02	FLOWABLE FILL (EXCAVATABLE)	18.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.500	L.M.
209-05	SEDIMENT REMOVAL	237.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,008.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	1,432.000	L.F.
209-08.07	ROCK CHECK DAM	9.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	6.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	7,971.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	148.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	9.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,307.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	944.000	TON

Contract ID CNW263 - WASHINGTON

Item No.	Description	Quantity	Units
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	12.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	619.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	327.000	S.Y.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	137.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	4.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	141.000	LB.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,007.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	105.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	46.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	8.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	293.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	36.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	100.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	178.000	LB.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	53.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	65.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	5.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,360.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.200	L.M.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH

Contract ID CNW263 - WASHINGTON

Item No.	Description	Quantity	Units
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	3.000	L.M.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.500	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	8,115.000	L.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
740-06.01	GEOMEMBRANE	1,193.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	194.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,127.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	3,981.000	L.F.
801-02	SEEDING (WITHOUT MULCH)	185.000	UNIT
801-03	WATER (SEEDING & SODDING)	17.000	M.G.
803-01	SODDING (NEW SOD)	762.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	10,323.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW289 - WHITE

Contract ID: CNW289

Letting Date: August 19, 2022 10:00 AM

Projects: 93NMSC-S3-002

NA

Counties: WHITE

District:

DBE Goal Percent:

Description: The construction of a salt brine shed.

Contract Time: DT - 12/15/2022

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 60')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW310 - CHEATHAM & ROBERTSON

Contract ID: CNW310

Letting Date: August 19, 2022 10:00 AM

Projects: 111040-S8-005
741065-S8-007

NA
NA

Counties: CHEATHAM, ROBERTSON

District:

DBE Goal Percent:

Description: The sealing on I-40 from the Williamson County line (L.M. 0.00) to the Davidson County line (L.M. 7.15) and on I-65 from the Sumner County line (L.M. 0.00) to the bridge over Honey Run Creek (L.M. 7.47).

Contract Time: DT - 10/15/2022

Item No.	Description	Quantity	Units
403-01.10	HIGH PERFORMANCE FOG SEALS	270,284.000	S.Y.
405-01.01	BITUMINOUS MATERIAL (BSC)	175.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	30.000	S.F.
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	30.000	DAY
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	8.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.