

Estimated Quantities -- Letting December 09, 2022

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNW921 - DAVIDSON

Contract ID: CNW921

Letting Date: December 09, 2022 10:00 AM

Projects: 19103-4107-04
191040-F8-012

NA
NH-I-40-3(180)

Counties: DAVIDSON

District:

DBE Goal Percent: 9.00

Description: The resurfacing on I-40 from U.S. 70S (S.R. 1) (L.M. 4.71) to near U.S. 70 (S.R. 24, Charlotte Pike) (L.M. 9.61), including bridge deck repairs and thin epoxy overlay.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	20.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	815.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	141.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	21,570.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	20.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	21,367.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	850.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	23.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,738.000	S.F.

Contract ID CNW921 - DAVIDSON

Item No.	Description	Quantity	Units
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	13.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,800.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,800.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,700.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	3,710.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	59,400.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	44.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	5,908.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	1.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVTM MRKNG (6IN LINE)	44.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVTM MRKNG (8IN BARRIER LINE)	5,805.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVTM MRKNG (6IN DOTTED LINE)	4,555.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	140.000	S.Y.
604-10.53	CONCRETE REPAIRS	20.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	3,614.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW925 - FAYETTE & SHELBY

Contract ID: CNW925

Letting Date: December 09, 2022 10:00 AM

Projects: R4BVAR-M3-021

NA

Counties: FAYETTE, SHELBY

District:

DBE Goal Percent:

Description: The sweeping on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
719-01.41	SWEEPING (YEAR 1)	15,308.000	L.M.
719-01.42	SWEEPING (YEAR 2)	15,308.000	L.M.
719-01.43	SWEEPING (YEAR 3)	15,308.000	L.M.

() Item will be bid as lump sum.

Contract ID CNW923 - JACKSON

Contract ID: CNW923

Letting Date: December 09, 2022 10:00 AM

Projects: 44NMSC-S3-004

NA

Counties: JACKSON

District:

DBE Goal Percent:

Description: The construction of a TDOT maintenance building at 2636 S Grundy Quarles Highway in Gainesboro.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
607-65.20	SITE PREPARATION	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (FOUNDATION AND STRUCTURE)	1.000	EACH
680-02.02	BUILDING (DESCRIPTION) (INTERIOR CONSTRUCTION)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW926 - MOORE

Contract ID: CNW926

Letting Date: December 09, 2022 10:00 AM

Projects: 64005-3224-14

STP-55(24)

Counties: MOORE

District:

DBE Goal Percent: 8.50

Description: The grading, drainage, construction of a concrete box beam bridge and paving on S.R. 55 from near Goodbranch Road (L.M. 2.80) to near Moore County High School (L.M. 3.00).

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,180.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	4,110.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,300.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	1,149.000	C.Y.
203-06	WATER	342.000	M.G.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	92.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.100	L.M.
209-05	SEDIMENT REMOVAL	100.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	352.000	L.F.
209-08.07	ROCK CHECK DAM	30.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	5.000	EACH
209-08.09	FILTER SOCK CHECK DAM	30.000	EACH
209-09.01	SANDBAGS	1,900.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	311.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	5,304.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	14.000	TON

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	495.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	603.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	483.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	9.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	34.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	11.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	1,034.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	1.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	709.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	9.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	5.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	170.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	160.000	L.F.
702-03	CONCRETE COMBINED CURB & GUTTER	4.900	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	25.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	160.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	89.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	20.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	400.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	46.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	317.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	3,567.000	L.F.
710-05	LATERAL UNDERDRAIN	309.000	L.F.

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	10.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	4,446.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	211.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	485.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	20.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,478.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	108.000	L.F.
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	1.000	EACH
713-02.17	REMOVE & REPLACE DELINEATORS (SINGLE WHITE)	1.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (OBJECT MARKERS)	4.000	EACH
713-16.21	SIGNS (DESCRIPTION) (STOP, 30"X30")	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (END SCHOOL SPEED LIMIT, S5-3, 24" X 30")	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	187.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	40.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	40.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	771.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	108.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.200	L.M.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	3.300	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	4,470.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	108.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-15.07	CABINET (DESCRIPTION) (POLE MOUNTED SCHOOL FLASHER)	2.000	EACH
730-16.14	CONTROLLER (DESCRIPTION) (SCHOOL ZONE FLASHER)	2.000	EACH
730-23.72	CANTILEVER SIGNAL SUPPORT (1 ARM @ 35')	1.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	1.000	EACH
730-50.10	SOLAR POWERED FLASHING ASSEMBLY	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	866.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	3,519.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	175.000	UNIT
801-03	WATER (SEEDING & SODDING)	105.000	M.G.
803-01	SODDING (NEW SOD)	8,700.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 64-SR055-2.77 STA. 97+90.82)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	90.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	7.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 1 STA. 97+91.01)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (ABUT. NO. 2 STA 98+10.98)	(1)	LS

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
204-14	CORE DRILLING FOR PILES(ROCK)	160.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	240.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	30.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	4,575.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	70.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	9,763.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	35.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	18.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	243.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	2.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	90.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	440.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	40.000	EACH
615-02.02	PRESTRESSED CONCRETE BOX BEAM (17" X 36")	37.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	71.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	1.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	41.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	44.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	36.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	140.000	L.F.
790-02.04	POLE 35FT CLASS 5 WOOD	1.000	EACH
790-03.01	POLE 40FT CLASS 2 WOOD	1.000	EACH
790-04.02	POLE 45FT CLASS 2 WOOD	1.000	EACH
790-04.04	POLE 45FT CLASS 4 WOOD	1.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	1.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	1.000	EACH
790-20.30	TOP EXISTING POLE	1.000	EACH
790-22.13	1PH DEAD END 25KV	1.000	EACH
790-22.15	1PH DEAD END TAP W/ EXTENSION 25KV	1.000	EACH

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
790-26.14	3PH CROSSARM DBL 10FT SM ANGLE 25KV	1.000	EACH
790-26.21	3PH VERTICAL DDE ANGLE 25KV	2.000	EACH
790-26.25	3PH CROSSARM DDE 25KV	2.000	EACH
790-26.27	3PH CROSSARM DBL DDE 25KV	1.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	2.000	EACH
790-30.06	SECONDARY CONDUCTOR 6 AL DUPLEX	165.000	L.F.
790-30.12	SECONDARY CONDUCTOR 4 AL TRIPLEX	22.000	L.F.
790-32.01	DOWN GUY - THROUGH BOLT TYPE	19.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	2.000	EACH
790-32.23	GUY GUARD	19.000	EACH
790-33.02	EXPANDING TYPE ANCHOR 10,000LB-12,000LB	14.000	EACH
790-36.09	TRANSFER - 1TR XFMR ASSEMBLY	2.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	5.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	5,070.000	L.F.
790-41.55	UG SEC COND 1/0 AL QPLX	90.000	L.F.
790-42.04	2IN DIA GALVINIZED METAL PIPE	160.000	L.F.
790-42.08	2IN DIA PVC PIPE	160.000	L.F.
790-42.16	1 DUCT @ 36IN-48IN DEPTH	40.000	L.F.
790-42.18	3 DUCT BANK @ 36IN-48IN DEPTH	40.000	L.F.
790-43.50	SECONDARY RISER W/ 2IN CONDUIT	4.000	EACH
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	2.000	EACH
790-47.02	2PH XFMR BNK POLE MTD W/ FUSE/ARRESTERS	1.000	EACH
790-54.03	10KVA 1PH OH XFORMER 14.4KV 120/240	1.000	EACH
790-54.04	15KVA 1PH OH XFORMER 14.4KV 120/240	1.000	EACH
790-64.01	SEC MTG 1PH 120/240 VOLTS	2.000	EACH
790-68.06	POLE TOP PROTECTION ASSEMBLY	5.000	EACH
790-69.08	GROUND-GROUND ROD	4.000	EACH
790-69.22	POLE TOP PIN	1.000	EACH
790-69.31	STICK PIN	6.000	EACH
790-69.32	ARM PIN	1.000	EACH

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
790-98.01	REMOVE WIRE	4,553.000	L.F.
790-98.02	REMOVE POLES	8.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	78.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
791-03.04	4IN HDPE GAS MAIN	971.000	L.F.
791-04.13	HDD 4IN PE PIPE - ROCK	152.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-06.13	CONNECT TO 8IN EX. STL MAIN	1.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	2.000	EACH
791-08.02	3/4IN SERVICE ASSEMBLY	2.000	EACH
791-08.07	3/4IN PE SERVICE PIPE	27.000	L.F.
791-09.04	REGULATOR STATION	1.000	EACH
791-10.04	RETIRE IN PLACE 2IN SERV CUT & PLUG	2.000	EACH
791-10.05	RETIRE IN PLACE 4IN SERV CUT & PLUG	1.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
793-01.08	POLE 35FT CLASS 5 WOOD	3.000	EACH
793-01.41	ANCHOR 1IN	3.000	EACH
793-11.17	COMPOSITE HANDHOLE 5FTX3FTX3FT	4.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	6,025.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	195.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	2,915.000	L.F.
793-14.19	4IN SCH 80 ORANGE FLEXPipe	290.000	L.F.
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	290.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	4.000	EACH
795-03.05	6IN PVC WATER LINE	780.000	L.F.
795-05.63	BORE/JACK 12IN STEEL CASING PIPE-UNCON.	30.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	3.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	4.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	2.000	EACH

Contract ID CNW926 - MOORE

Item No.	Description	Quantity	Units
795-09.05	3IN WATER SERVICE METER ASSEMBLY	1.000	EACH
795-11.03	RECONNECT FIRE HYDRANT	1.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	960.000	L.F.
795-13.01	DI FITTINGS	800.000	LB.
795-14.07	CONCRETE VAULT	1.000	EACH
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	4.000	EACH
795-16.40	6IN EXISTING WATER MAIN TERMINATION	1.000	EACH
797-01.01	4IN DIP FORCE MAIN	1,760.000	L.F.
797-02.06	4IN HDPE FORCE MAIN	310.000	L.F.
797-03.30	2IN PVC FORCE MAIN (0-8FT)	100.000	L.F.
797-06.21	HDD 12IN HDPE CASING PIPE-ROCK	310.000	L.F.
797-06.61	BORE/JACK 10IN STEEL CASING PIPE-UNCON.	70.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	1.000	EACH
797-08.01	DI FITTINGS	700.000	LB.
797-08.07	4IN CLEAN OUT ASSEMBLY	3.000	EACH
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	1.000	EACH
797-09.06	4IN PLUG VALVE ASSEMBLY	4.000	EACH
797-09.43	CUT AND CAP 4IN FORCE MAIN	2.000	EACH
797-10.14	CONNECT TO 2IN FORCE MAIN	1.000	EACH
797-10.16	CONNECT TO 4IN FORCE MAIN	2.000	EACH
797-10.26	CONNECT PUMP STATION TO FORCE MAIN	1.000	EACH
797-11.25	RETIREIN PLACE 48IN MANHOLE	1.000	EACH
797-11.30	RETIREIN PLACE EXISTING SEWER <8IN	1,971.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW922 - ROBERTSON

Contract ID: CNW922

Letting Date: December 09, 2022 10:00 AM

Projects: 74I065-F8-009

NH-I-65-3(138)

Counties: ROBERTSON

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-65 from the Sumner County line (L.M. 0.00) to the bridge over Honey Run Creek (L.M. 7.47).

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	30.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,954.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	250.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	146.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	24,151.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	30.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	23,923.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	2.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,292.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-02.14	FLEXIBLE DELINEATOR (WHITE)	100.000	EACH

Contract ID CNW922 - ROBERTSON

Item No.	Description	Quantity	Units
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	100.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,100.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,100.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	3,500.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	4,700.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	33.900	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	3.800	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	3.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.900	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	7,400.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW924 - ROBERTSON

Contract ID: CNW924

Letting Date: December 09, 2022 10:00 AM

Projects: 74007-4122-04

NA

Counties: ROBERTSON

District:

DBE Goal Percent:

Description: The repair of bridges on S.R. 49 (L.M. 0.14), S.R. 256 (L.M. 0.39), Gause Road and Jack Teasley Road, over I-24.

Contract Time: DT - 8/15/2023

Item No.	Description	Quantity	Units
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
602-10.51	STRUCTURAL STEEL REPAIR(DESCRIPTION)	63.000	EACH
604-10.07	CONCRETE REMOVAL	(1)	LS
604-10.89	MISCELLANEOUS BRIDGE ITEMS (Description) (OSHA CONFINED SPACE REQ.)	(1)	LS
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	265.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	5,296.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	144.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	144.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,816.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	8.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	2,640.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	3,397.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW920 - SHELBY

Contract ID: CNW920

Letting Date: December 09, 2022 10:00 AM

Projects: 79947-4111-04

N/A

Counties: SHELBY

District:

DBE Goal Percent:

Description: The repair of the bridge on Shady Grove Road over I-240 (L.M. 1.48).

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	200.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.400	TON
411-01.10	ACS MIX(PG64-22) GRADING D	74.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	356.000	S.Y.
604-03.01	CLASS A CONCRETE (BRIDGES)	4.000	C.Y.
604-03.60	BRIDGE JOINT SEISMIC MODIFICATION (DESCRIPTION) (HMWM)	38.000	EACH
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	300.000	S.Y.
604-10.05	CONCRETE	50.000	S.F.
604-10.09	CONCRETE	66.000	C.Y.
604-10.13	CONCRETE SLAB REMOVAL	(1)	LS
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.18	REINFORCING STEEL (REPAIRS)	15,344.000	LB.
604-10.26	BRACING	12.000	EACH
604-10.42	CONCRETE REPAIRS	300.000	C.F.
604-10.46	EXPANSION JOINT REPAIRS (TYPE G)	81.000	L.F.
604-10.54	CONCRETE REPAIRS	50.000	S.F.
604-10.83	COMPOSITE FIBER ENCASEMENT	1,900.000	S.F.
604-10.90	MISCELLANEOUS BRIDGE ITEMS	(1)	LS
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	96.000	EACH

Contract ID CNW920 - SHELBY

Item No.	Description	Quantity	Units
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	311.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,119.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	320.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	8.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	5,700.000	L.F.
714-02.02	ENCASED CONDUIT (2" PVC, SCHEDULE 40)	65.000	L.F.
714-06.07	CABLE (1/C # 2 AWG)	195.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.400	L.M.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
803-01	SODDING (NEW SOD)	300.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW381 - ANDERSON , BLOUNT, ETC.

Contract ID: CNW381

Letting Date: December 09, 2022 10:00 AM

Projects: R1BVAR-M3-022

NA

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER,
HAMBLEN, HANCOCK, HAWKINS,
JEFFERSON, JOHNSON, KNOX, LOUDON,
MONROE, MORGAN, ROANE, SCOTT,
SEVIER, SULLIVAN, UNICOI, UNION,
WASHINGTON

District:

DBE Goal Percent:

Description: The on-call concrete pavement repair at various locations on various Interstate and State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
502-02	HOLES	5.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	100.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	7,000.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	3,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	350.000	EACH
502-08	PRE-ROLLING	50.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	1,300.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	2,000.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	350.000	L.F.
502-10	CEMENT-FLY ASH GROUT	50.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	500.000	S.Y.
503-60	RETROFIT DOWEL BAR	50.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	8.000	EACH

Contract ID CNW381 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
712-01.03	LANE CLOSURE(NIGHT WORK)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	180.000	EACH
712-06	SIGNS (CONSTRUCTION)	410.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	4.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	4,500.000	L.F.
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	460.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	5.000	EACH

() Item will be bid as lump sum.

Contract ID CNW382 - ANDERSON , CAMPBELL, ETC.

Contract ID: CNW382

Letting Date: December 09, 2022 10:00 AM

Projects: R1IVAR-F3-002

HSIP-I-098-1(22)

Counties: ANDERSON, CAMPBELL, KNOX, SULLIVAN

District:

DBE Goal Percent:

Description: The installation of longitudinal cable barrier on various Interstate Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	50,952.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	34.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW376 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNW376

Letting Date: December 09, 2022 10:00 AM

Projects: R3BVAR-M3-029

NA

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The on-call concrete pavement repair at various locations on various Interstate and State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
502-02	HOLES	10.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	50.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	10,900.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	3,800.000	EACH
502-04.03	TRANSVERSE TIE-BARS	600.000	EACH
502-08	PRE-ROLLING	8.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	6,800.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	1,600.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	375.000	L.F.
502-10	CEMENT-FLY ASH GROUT	40.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	375.000	S.Y.
503-60	RETROFIT DOWEL BAR	50.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNW376 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	9.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	140.000	EACH
712-06	SIGNS (CONSTRUCTION)	460.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	20.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	3,100.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	8.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNW375 - BEDFORD , DICKSON, ETC.

Contract ID: CNW375

Letting Date: December 09, 2022 10:00 AM

Projects: R3IVAR-F3-004

HSIP-I-098-3(34)

Counties: BEDFORD, DICKSON, HICKMAN,
HUMPHREYS, RUTHERFORD, WILLIAMSON

District:

DBE Goal Percent:

Description: The installation of longitudinal cable barrier on various Interstate Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	52,827.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	38.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW384 - BENTON , CARROLL, ETC.

Contract ID: CNW384

Letting Date: December 09, 2022 10:00 AM

Projects: R4BVAR-M3-029

NA

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
DECATUR, DYER, FAYETTE, GIBSON,
HARDEMAN, HARDIN, HAYWOOD,
HENDERSON, HENRY, LAKE, LAUDERDALE,
MADISON, MCNAIRY, OBION, SHELBY,
TIPTON, WEAKLEY

District:

DBE Goal Percent:

Description: The on-call concrete pavement repair at various locations on various Interstate and State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	40.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	12,600.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	4,800.000	EACH
502-04.03	TRANSVERSE TIE-BARS	620.000	EACH
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	6,500.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	4,000.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	250.000	L.F.
503-01	GRINDING CONCRETE PAVEMENT	500.000	S.Y.
503-60	RETROFIT DOWEL BAR	15.000	EACH
706-10.74	CONCRETE BARRIER WALL REPAIR	5.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	350.000	EACH
712-06	SIGNS (CONSTRUCTION)	675.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	144.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH

Contract ID CNW384 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	15.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	15.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	400.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	400.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNW379 - BLEDSOE , BRADLEY, ETC.

Contract ID: CNW379

Letting Date: December 09, 2022 10:00 AM

Projects: R2BVAR-M3-016

NA

Counties: BLEDSOE, BRADLEY, CANNON, CLAY,
COFFEE, CUMBERLAND, DEKALB,
FENTRESS, FRANKLIN, GRUNDY,
HAMILTON, JACKSON, MARION, MCMINN,
MEIGS, OVERTON, PICKETT, POLK,
PUTNAM, RHEA, SEQUATCHIE, VAN BUREN,
WARREN, WHITE

District:

DBE Goal Percent:

Description: The on-call concrete pavement repair at various locations on various Interstate and State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
502-02	HOLES	5.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	100.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	9,900.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	4,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	1,600.000	EACH
502-08	PRE-ROLLING	5.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	7,800.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	2,500.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	425.000	L.F.
502-10	CEMENT-FLY ASH GROUT	50.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	500.000	S.Y.
503-60	RETROFIT DOWEL BAR	25.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	6.000	EACH

Contract ID CNW379 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
712-01.03	LANE CLOSURE(NIGHT WORK)	5.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	220.000	EACH
712-06	SIGNS (CONSTRUCTION)	590.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	6.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	1,500.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	3.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	6.000	EACH

() Item will be bid as lump sum.

Contract ID CNW366 - BLOUNT

Contract ID: CNW366

Letting Date: December 09, 2022 10:00 AM

Projects: 05032-3213-04

N/A

Counties: BLOUNT

District:

DBE Goal Percent:

Description: The installation of signals on S.R. 333 at S.R. 334 (Louisville Road) and Topside Road in Louisville (L.M. 9.03).

Contract Time: DT - 7/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
209-03.20	FILTER SOCK (8 INCH)	100.000	L.F.
209-05	SEDIMENT REMOVAL	14.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	13.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	250.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
706-10.26	ROUNDED END ELEMENT	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	216.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	37.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	1.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W3-3)	3.000	EACH
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (W3-3)	3.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	75.000	L.F.

Contract ID CNW366 - BLOUNT

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	0.190	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	3.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	3.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	1.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	450.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	125.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	125.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	1.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC)	35.000	L.F.
730-13.14	VEHICLE DETECTOR (360-DEGREE CAMERA)	1.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-21.03	WOOD POLE (SIGNAL SUPPORT) CLASS 3, 45' LENGTH	2.000	EACH
730-22.02	GUYING DEVICE (ANGLE ANCHOR)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNW320 - BLOUNT

Contract ID: CNW320

Letting Date: December 09, 2022 10:00 AM

Projects: 05950-3540-04

N/A

Counties: BLOUNT

District:

DBE Goal Percent:

Description: The grading, drainage, construction of a concrete box bridge, signals and paving on a S.I.A. route (including S.R. 334) serving Project Python Meteor.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	26,104.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	2,319.000	TON
203-04	PLACING AND SPREADING TOPSOIL	4,253.000	C.Y.
203-06	WATER	62.000	M.G.
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	175.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-02.03	8" TEMPORARY SLOPE DRAIN	34.000	L.F.
209-02.05	12" TEMPORARY SLOPE DRAIN	145.000	L.F.
209-02.06	15" TEMPORARY SLOPE DRAIN	38.000	L.F.
209-02.07	18" TEMPORARY SLOPE DRAIN	798.000	L.F.
209-05	SEDIMENT REMOVAL	204.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,408.000	L.F.
209-08.07	ROCK CHECK DAM	62.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	13.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	24,462.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	612.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	80.000	TON

Contract ID CNW320 - BLOUNT

Item No.	Description	Quantity	Units
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	3,461.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	2,234.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	18.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	174.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	46.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	780.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	1.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	274.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	66.000	C.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	352.000	L.F.
607-13.03	72" CONCRETE PIPE CULVERT (CLASS III)	19.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	28.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	1,853.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	6.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	10.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	32.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	65.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	70.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,560.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	4.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-10.26	ROUNDED END ELEMENT	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	304.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	20.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON

Contract ID CNW320 - BLOUNT

Item No.	Description	Quantity	Units
709-05.06	MACHINED RIP-RAP (CLASS A-1)	46.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	240.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,610.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	85.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	24.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,060.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	148.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	12,000.000	L.F.
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	56.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (OM4-1, OBJECT MARKER)	6.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R1-1, STOP SIGN)	3.000	EACH
713-16.22	SIGNS (DESCRIPTION) (R2-1, SPEED LIMIT SIGN)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (W4-1, MERGE SIGN)	1.000	EACH
713-16.24	SIGNS (DESCRIPTION) (W4-2R, LANE ENDS)	1.000	EACH
713-16.25	SIGNS (DESCRIPTION) (W7-6, HILL BLOCK VIEW SIGN)	1.000	EACH
713-16.26	SIGNS (DESCRIPTION) (W13-1P, ADVISORY SPEED PLAQUE)	1.000	EACH
713-16.27	SIGNS (DESCRIPTION) (W14-1, DEAD END)	1.000	EACH
713-16.28	SIGNS (DESCRIPTION) (W14-2, NO OUTLET)	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	28.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	20.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	375.000	S.Y.

Contract ID CNW320 - BLOUNT

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	870.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	150.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.03	PLASTIC PAVEMENT MARKING (4" DOTTED LINE)	40.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	2.000	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	26,050.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	375.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	870.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	11.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	150.000	L.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	2.000	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	40.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	2.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	2.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130 A3 WITH BACKPLATE)	1.000	EACH
730-02.31	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (150 A4H WITH BACKPLATE)	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	1.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	46.000	L.F.

Contract ID CNW320 - BLOUNT

Item No.	Description	Quantity	Units
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	629.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	475.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	336.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	1.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC)	70.000	L.F.
730-13.14	VEHICLE DETECTOR (360-DEGREE CAMERA)	1.000	EACH
730-15.07	CABINET (DESCRIPTION) (BATTERY BACK-UP POWER)	1.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-21.01	WOOD POLE (SIGNAL SUPPORT) CLASS 3, 35' LENGTH	1.000	EACH
730-21.02	WOOD POLE (SIGNAL SUPPORT) CLASS 3, 40' LENGTH	1.000	EACH
730-21.03	WOOD POLE (SIGNAL SUPPORT) CLASS 3, 45' LENGTH	2.000	EACH
730-35.06	BATTERY BACK-UP AND POWER CONDITIONER	1.000	EACH
740-06.01	GEOMEMBRANE	594.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	433.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,470.000	S.Y.
801-01	SEEDING (WITH MULCH)	103.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	103.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	206.000	UNIT
801-03	WATER (SEEDING & SODDING)	33.000	M.G.
803-01	SODDING (NEW SOD)	9,873.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	22,877.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	350.000	S.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	192.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	223.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	50,336.000	LB.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	100.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	1,120.000	L.F.

Contract ID CNW320 - BLOUNT

Item No.	Description	Quantity	Units
795-03.02	2IN PVC WATER LINE	250.000	L.F.
795-03.06	8IN PVC WATER LINE	1,000.000	L.F.
795-05.01	HDD 2IN HDPE CARRIER PIPE-UNCON	110.000	L.F.
795-05.99	FLOWABLE FILL (TRENCH PLUGS)	23.000	C.Y.
795-06.01	CONNECT TO 2IN WATER LINE	1.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	2.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	1.000	EACH
795-06.31	CUT AND CAP 2IN WATER LINE	1.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	2.000	EACH
795-08.01	2IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.08	12IN BUTTERFLY VALVE ASSEMBLY	3.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	4.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	300.000	L.F.
795-10.03	1IN AUTO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	1,945.000	L.F.
795-13.01	DI FITTINGS	3,500.000	LB.
795-13.03	PVC FITTINGS	600.000	LB.
795-14.01	CLASS A CONCRETE	5.000	C.Y.
795-15.03	14IN STEEL CASING PIPE OPEN CUT METHOD	100.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW372 - BRADLEY

Contract ID: CNW372

Letting Date: December 09, 2022 10:00 AM

Projects: 06006-3236-04

NA

Counties: BRADLEY

District:

DBE Goal Percent:

Description: The installation of an over height warning system on U.S. 64 (S.R. 40) from near Parker Street NE to near S.R. 74 (Wildwood Avenue) in Cleveland (L.M. 0.82 - L.M. 1.06).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	135.000	EACH
712-06	SIGNS (CONSTRUCTION)	332.000	S.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.220	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	425.700	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	775.000	LB.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	64.000	S.F.
713-15.41	SIGN REMOVAL (DESCRIPTION)	(1)	LS
717-01	MOBILIZATION	(1)	LS
725-02.01	CLOSED CIRCUIT TELEVISION(CCTV) TYPE 1	2.000	EACH
725-03.22	CABINET (TYPE B)	3.000	EACH
725-03.23	CABINET (TYPE C)	1.000	EACH
725-04.20	OVERHEIGHT VEHICLE DETECTION SYSTEM	2.000	EACH
725-20.43	PULL BOX (TYPE C)	7.000	EACH
725-20.44	PULL BOX (TYPE D)	9.000	EACH
725-20.55	CABLE (1/C #6 AWG.)	1,420.000	L.F.
725-20.71	ELECTRICAL CONNECTION	(1)	LS
725-20.76	COMMUNICATION CONNECTION (DESCRIPTION) (SEE PLANS)	(1)	LS

Contract ID CNW372 - BRADLEY

Item No.	Description	Quantity	Units
725-21.18	DMS COMM CABLE	200.000	L.F.
725-21.19	DMS POWER CABLE	400.000	L.F.
725-21.26	DYNAMIC MESSAGE SIGN (OVER SHOULDER DMS)	2.000	EACH
725-21.85	UNINTERRUPTIBLE POWER SUPPLY	2.000	EACH
725-22.72	2IN CONDUIT BORED	770.000	L.F.
725-23.01	ITS CABLE MARKER	4.000	EACH
725-23.21	FIBER OPTIC DROP CABLE (12 F)	2,515.000	L.F.
725-24.51	SYSTEM INTEGRATION	(1)	LS
725-24.55	AS-BUILT PLANS	(1)	LS
725-28.07	ETHERNET SWITCH (FIELD LAYER 2)	2.000	EACH
790-64.07	PRI MTG 1PH	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNW367 - CAMPBELL

Contract ID: CNW367

Letting Date: December 09, 2022 10:00 AM

Projects: 07I075-F8-006

NH-I-75-3(195)

Counties: CAMPBELL

District:

DBE Goal Percent: 8.00

Description: The resurfacing on I-75 from near mile post 147 (L.M. 17.41) to near mile post 154 (L.M. 24.52).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.000	L.M.
307-03.09	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING C	13,312.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	63.000	TON
403-02.02	HOT APPLIED TACK COAT	152.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	23.000	L.M.
411-03.23	ACS MIX (PG76-22) OGFC	15,235.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	23.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,707.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	260.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	130.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,220.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	8.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY

Contract ID CNW367 - CAMPBELL

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	665.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	665.000	EACH
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	26.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	26.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW279 - CAMPBELL

Contract ID: CNW279

Letting Date: December 09, 2022 10:00 AM

Projects: 07946-3622-14

STP-700(39)

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The stream mitigation for Dog Creek in Cove Lake State Park.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
203-01.13	ROAD & DRAINAGE EXCAVATION (STREAM MITIGATION)	12,640.000	C.Y.
203-02.02	BORROW EXCAVATION (GRADED SOLID ROCK)	303.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,702.000	C.Y.
203-15.03	COMPACTED CLAY	469.000	C.Y.
209-03.34	STREAM MITIGATION-LOG VANES	280.000	L.F.
209-03.36	STREAM MITIGATION-STEP POOL	18.000	EACH
209-03.37	STREAM MITIGATION CROSS VANE STRUCTURE	1.000	EACH
209-03.38	STREAM MITIGATION -J -HOOK	5.000	EACH
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	711.000	L.F.
209-03.62	STREAM MITIGATION - ROOT WAD	47.000	EACH
209-03.66	PLACING NATIVE STONE IN NEW CHANNEL	258.000	S.Y.
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	711.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	841.000	L.F.
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (PUMP AROUND)	(1)	LS
303-10.01	MINERAL AGGREGATE (SIZE 57)	134.000	TON

Contract ID CNW279 - CAMPBELL

Item No.	Description	Quantity	Units
621-03.09	60" TEMPORARY DRAINAGE PIPE	96.000	L.F.
621-03.11	72" TEMPORARY DRAINAGE PIPE	192.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,156.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	208.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	702.000	TON
709-05.81	ROCK RIFFLES	(1)	LS
712-01	TRAFFIC CONTROL	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (CONSTRUCTION)	4.000	EACH
713-16.21	SIGNS (DESCRIPTION) (PROTECTED AREA SIGNS)	35.000	EACH
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	2,310.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,115.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	146.000	UNIT
801-01.08	SEEDING (SPECIAL MIXTURE) WITH MULCH	175.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	5.600	UNIT
801-03	WATER (SEEDING & SODDING)	0.400	M.G.
802-02.40	CUTTINGS: SALIX NIGRA (24-48IN LENGTH)	700.000	EACH
802-02.41	CUTTINGS: SALIX SERICEA (24-48IN)	1,000.000	EACH
802-02.42	CUTTINGS: CORNUS AMOMUM (24-48IN)	1,000.000	EACH
802-02.43	CUTTINGS: SAMBUCUS CANADENSIS (24-48IN)	700.000	EACH
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	100.000	EACH
802-12.07	BETULA NIGRA (RIVER BIRCH SEEDLNG B.R.)	300.000	EACH
802-12.14	DIOSPYROS VIRGINIANA (PERSIMMON SEEDLNG B.R.)	200.000	EACH
802-12.16	FRAXINUS PENNSYLVANICA (GREEN ASH SEEDLNG B.R.)	200.000	EACH
802-12.17	JUGLANS NIGRA (BLACK WALNUT SEEDLNG B.R.)	100.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	300.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	300.000	EACH
802-12.38	QUERCUS PHELLOS (WILLOW OAK SEEDLNG B.R.)	200.000	EACH

Contract ID CNW279 - CAMPBELL

Item No.	Description	Quantity	Units
802-12.45	CARPINUS CAROLINIANA (AMERICAN HORNBEAM SEEDLING B.R.)	220.000	EACH
802-12.63	HAMAMELIS VIRGINIANA (AMERICAN WITCHHAZEL SEEDLING B.R.)	220.000	EACH
802-13.59	LINDERA BENZOIN (SPICEBUSH SDLNG BARE ROOT)	220.000	EACH
805-12.01	EROSION CONTROL BLANKET (TYPE I)	499.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	3,300.000	S.Y.
797-02.62	18IN HDPE GRAVITY SEWER 6FT-12FT DEPTH	1,300.000	L.F.
797-06.94	OPEN CUT 30IN STEEL CASING PIPE	180.000	L.F.
797-07.14	60IN MANHOLE 6FT-8FT DEPTH	6.000	EACH
797-07.80	REMOVE SEWER MANHOLE	6.000	EACH
797-10.03	CONNECT 10-18IN SEWER TO EXIST. MANHOLE	2.000	EACH
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.45	PIPE CHECK DAM	5.000	C.Y.

() Item will be bid as lump sum.

Contract ID CNW354 - CHEATHAM

Contract ID: CNW354

Letting Date: December 09, 2022 10:00 AM

Projects: 111040-F8-004

NH-I-40-3(179)

Counties: CHEATHAM

District:

DBE Goal Percent: 9.00

Description: The resurfacing on I-40 from the Williamson County line (L.M. 0.00) to the Davidson County line (L.M. 7.15).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	28.600	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,632.000	TON
307-03.07	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M	500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	148.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	22,499.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	28.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	22,286.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	33.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	33.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	33.000	EACH
706-01	GUARDRAIL REMOVED	1,650.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,658.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH

Contract ID CNW354 - CHEATHAM

Item No.	Description	Quantity	Units
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	944.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	543.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	110.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	450.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	34.300	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	3,089.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.600	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,750.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	3,620.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW358 - CHEATHAM

Contract ID: CNW358

Letting Date: December 09, 2022 10:00 AM

Projects: 11005-3234-04

N/A

11950-3510-04

NA

Counties: CHEATHAM

District:

DBE Goal Percent:

Description: The grading, drainage and paving on a S.I.A. route serving Caymas Boats and Nashville Fabrication, and on S.R. 12 supporting Nashville Fabricators and Engineers (from near L.M. 1.74 to near L.M. 2.37) in Ashland City.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	13,640.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	1,160.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	14,538.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	10,277.000	C.Y.
203-06	WATER	44.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	533.000	C.Y.
204-06.01	FLOWABLE FILL (GENERAL)	10.000	C.Y.
209-02.07	18" TEMPORARY SLOPE DRAIN	16.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	4.000	EACH
209-05	SEDIMENT REMOVAL	318.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,839.000	L.F.
209-08.07	ROCK CHECK DAM	65.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	16.000	EACH
209-08.09	FILTER SOCK CHECK DAM	9.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	11.000	EACH

Contract ID CNW358 - CHEATHAM

Item No.	Description	Quantity	Units
209-40.48	CATCH BASIN FILTER ASSEMBLY(TYPE 8)	1.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	50.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	13,169.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	92.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	908.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	781.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	3,538.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,070.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	22.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	74.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	26.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	487.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	2,402.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.600	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	1,759.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	273.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	53.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	98.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	126.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	8.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	209.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	2.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.70	48IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	4.000	EACH
611-43.02	CATCH BASINS, TYPE 43, > 4' - 8' DEPTH	1.000	EACH

Contract ID CNW358 - CHEATHAM

Item No.	Description	Quantity	Units
701-01.01	CONCRETE SIDEWALK (4 ")	168.000	S.F.
701-02	CONCRETE DRIVEWAY	1,812.000	S.F.
701-02.02	CONCRETE DRIVEWAY (8")	5,929.000	S.F.
702-01.01	EXTRUDED SLOPING CURB	281.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,875.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	4.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	7.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	828.000	L.F.
706-06.03	RADIUS RAIL	113.000	L.F.
706-10.26	ROUNDED END ELEMENT	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	2,768.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	544.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	835.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	16.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	270.000	L.F.
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	7,066.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	197.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	70.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	14.000	EACH
712-06	SIGNS (CONSTRUCTION)	776.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	68.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	7,170.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	51,560.000	L.F.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	72.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	10.000	EACH

Contract ID CNW358 - CHEATHAM

Item No.	Description	Quantity	Units
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	64.000	LB.
713-11.21	P POST SLIP BASE	37.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	88.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	266.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	56.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	90.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	132.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	198.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	3.400	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	116.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	11.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	45.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	3.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.500	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	565.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,623.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,507.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	5,146.000	L.F.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,000.000	L.F.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	649.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	97.000	UNIT

Contract ID CNW358 - CHEATHAM

Item No.	Description	Quantity	Units
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	8.000	UNIT
801-01.65	TEMPORARY MULCH	130.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	65.000	UNIT
801-03	WATER (SEEDING & SODDING)	39.000	M.G.
802-11.11	CERCIS CANADENSIS (REDBUD 2-5FT CNTNR GRWN)	13.000	EACH
802-11.12	CORNUS FLORIDA (FLOWERING DOGWOOD 2-5FT CNTNR GRWN)	14.000	EACH
803-01	SODDING (NEW SOD)	10,687.000	S.Y.
805-01.02	TURF REINFORCEMENT MAT (CLASS II)	246.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	5,810.000	S.Y.
805-12.03	EROSION CONTROL BLANKET (TYPE III)	2,844.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL
790-04.03	POLE 45FT CLASS 3 WOOD	3.000	EACH
790-04.07	POLE 45FT CLASS 2 METAL	1.000	EACH
790-05.06	POLE 50FT CLASS 2 METAL	2.000	EACH
790-06.06	POLE 55 FT CLASS 2 METAL	2.000	EACH
790-22.01	1PH SGL PRIMARY SUPPORT 25KV	1.000	EACH
790-22.10	1PH SUSPENSION ANGLE 25KV	1.000	EACH
790-22.13	1PH DEAD END 25KV	1.000	EACH
790-22.15	1PH DEAD END TAP W/ EXTENSION 25KV	1.000	EACH
790-26.02	3PH CROSSARM DBL LRG COND 25KV	2.000	EACH
790-26.12	3PH CROSSARM DBL SM ANGLE 25KV	1.000	EACH
790-26.25	3PH CROSSARM DDE 25KV	2.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	2.000	EACH
790-26.32	3PH CROSSARM 10FT FBRGLS X-ARM DDE 25KV	1.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	8.000	EACH
790-30.04	SECONDARY ASSEMBLIES MISC	5.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	5.000	EACH
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	3.000	EACH
790-32.03	DOWN GUY - THROUGH BOLT ST PL	2.000	EACH

Contract ID CNW358 - CHEATHAM

Item No.	Description	Quantity	Units
790-32.06	DOWN GUY - INSULATED	4.000	EACH
790-32.23	GUY GUARD	11.000	EACH
790-32.30	OVERHEAD GUY HEAVY CONSTRUCTION - PREFORM	1.000	EACH
790-33.31	SCREW TYPE ANCHOR 23,000LB (F1-5D-P)	11.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	6.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	5,002.000	L.F.
790-61.01	1PH FUSE CUTOUT XARM MOUNT 25KV	4.000	EACH
790-65.06	LIGHTNING ARRESTER POLE MTD 18 KV	4.000	EACH
790-68.10	MISCELLANEOUS ASSEMBLIES	2.000	EACH
790-69.09	GND-ASSY GND ROD WITH ALUMINUM	3.000	EACH
790-69.11	GROUND-GROUND ROD FOR ST POLE	5.000	EACH
790-69.32	ARM PIN	3.000	EACH
790-69.41	EXTENSION LINK - EPOXY -8FT	3.000	EACH
790-98.01	REMOVE WIRE	4,578.000	L.F.
790-98.02	REMOVE POLES	5.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	45.000	EACH

() Item will be bid as lump sum.

Contract ID CNW352 - CLAY

Contract ID: CNW352

Letting Date: December 09, 2022 10:00 AM

Projects: 14S052-M3-004

N/A

Counties: CLAY

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 52 over Trace Creek (L.M. 2.25).

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
209-05	SEDIMENT REMOVAL	2.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	460.000	L.F.
209-09.01	SANDBAGS	6,600.000	BAG
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	685.000	S.Y.
209-65.04	TEMPORARY IN STREAM DIVERSION	110.000	L.F.
303-10.01	MINERAL AGGREGATE (SIZE 57)	20.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	92.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,400.000	S.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	278.000	S.Y.
604-10.05	CONCRETE	82.000	S.F.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	33.000	S.Y.
604-10.54	CONCRETE REPAIRS	76.000	S.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	385.000	S.Y.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	9.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	206.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH

Contract ID CNW352 - CLAY

Item No.	Description	Quantity	Units
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	291.000	L.F.
706-10.26	ROUNDED END ELEMENT	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	250.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	160.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	47.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,713.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	60.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	2,200.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	70.000	L.F.
713-02.27	CONCRETE BARRIER/PARAPET DELINEATOR (BI-DIRECTIONAL)	20.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	6.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	6.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	50.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	200.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	66.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW374 - COFFEE , CUMBERLAND, ETC.

Contract ID: CNW374

Letting Date: December 09, 2022 10:00 AM

Projects: R2IVAR-F3-004

HSIP-I-098-2(20)

Counties: COFFEE, CUMBERLAND, GRUNDY,
HAMILTON, MARION, PUTNAM

District:

DBE Goal Percent:

Description: The installation of longitudinal cable barrier on various Interstate Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	67,780.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	44.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	6.000	EACH
706-80.19	CABLE BARRIER (REMOVAL)	8,860.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW373 - CUMBERLAND

Contract ID: CNW373

Letting Date: December 09, 2022 10:00 AM

Projects: 18003-3245-94

STP-SIP-1(443)

Counties: CUMBERLAND

District:

DBE Goal Percent: 10.00

Description: The construction of a roundabout on U.S. 70 (S.R. 1) at the intersection of S.R. 392 (Milo Lemert Parkway) and S.R. 101 (Peavine Road) (L.M. 17.05 - L.M. 17.40).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (24", RAMP 3 STA. 1301+73)	69.000	L.F.
202-02.51	REMOVE CONCRETE ENDWALL & PIPE FROM EXISTING DRIVEWAY	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	155.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	17,385.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	7,440.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	5,045.000	C.Y.
203-06	WATER	110.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	1,812.000	C.Y.
209-05	SEDIMENT REMOVAL	204.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	595.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	1,295.000	L.F.
209-08.07	ROCK CHECK DAM	20.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	7.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	11.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	4.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	4.000	EACH

Contract ID CNW373 - CUMBERLAND

Item No.	Description	Quantity	Units
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	11.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	15,223.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	80.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,803.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,156.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	672.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	857.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	562.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	31.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	113.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	14.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	488.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	726.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	330.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.120	L.M.
411-12.05	SCORING FOR CENTERLINE RUMBLE (4IN WIDTH- 24IN SPACING)	0.060	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	2,200.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	58.000	C.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	850.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	103.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	55.000	L.F.
611-01.03	MANHOLES, > 8' - 12' DEPTH	1.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH
611-07.31	18IN ENDWALL (SIDE DRAIN)	2.000	EACH
611-07.59	24IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	7.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	4.000	EACH

Contract ID CNW373 - CUMBERLAND

Item No.	Description	Quantity	Units
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	2.000	EACH
611-42.03	CATCH BASINS, TYPE 42, > 8' - 12' DEPTH	2.000	EACH
701-03	CONCRETE MEDIAN PAVEMENT	56.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	150.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,675.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	4.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	1,650.000	L.F.
706-06.03	RADIUS RAIL	25.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,600.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	301.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	283.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	29.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	821.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	725.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,089.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	250.000	L.F.
712-10.02	TEMPORARY TRANSVERSE RUMBLE STRIPS	240.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,650.000	LB.
713-11.21	P POST SLIP BASE	53.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	581.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	6.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	114.000	EACH

Contract ID CNW373 - CUMBERLAND

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	79.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	173.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	65.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	145.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	1.360	L.M.
716-03.09	PLASTIC WORD PAVEMENT MARKING (YIELD))	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	8.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	60.000	S.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	52.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	12.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	1.000	L.M.
716-05.52	PAINTED PAVEMENT MARKING(AREA)	96.000	S.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	97.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	16.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	5.000	L.M.
716-08.33	HYDROBLAST REMOVAL OF PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,466.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,272.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	2,650.000	L.F.

Contract ID CNW373 - CUMBERLAND

Item No.	Description	Quantity	Units
801-01.07	TEMPORARY SEEDING (WITH MULCH)	129.000	UNIT
801-03	WATER (SEEDING & SODDING)	178.000	M.G.
803-01	SODDING (NEW SOD)	14,239.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL

() Item will be bid as lump sum.

Contract ID CNW360 - DAVIDSON

Contract ID: CNW360

Letting Date: December 09, 2022 10:00 AM

Projects: 19005-4168-04
19013-4131-04

NA
N/A

Counties: DAVIDSON

District:

DBE Goal Percent:

Description: The repair of the bridges on I-65 over Arthur Avenue (L.M. 8.80) and on I-40 over I-40, I-65 and the I-65 ramp (L.M. 16.14) in Nashville.

Contract Time: DT - 11/30/2023

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 19-I0065-8.08 R&L)	(1)	LS
203-03	BORROW EXCAVATION (UNCLASSIFIED)	50.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	486.000	L.F.
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	2.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	20.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.010	TON
411-01.10	ACS MIX(PG64-22) GRADING D	48.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	300.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.060	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	5,127.000	S.Y.
602-10.19	JACKING STEEL SPANS	(1)	LS
602-10.34	MISCELLANEOUS STRUCTURAL STEEL REPAIRS	18,195.000	LB.
602-10.51	STRUCTURAL STEEL REPAIR(DESCRIPTION)	4.000	EACH
603-01	PAINT STEEL STRUCTURE	(1)	LS
603-02.20	SPOT PAINTING EXISTING STEEL STRUCTURES	892.000	S.F.
603-05.20	CONTAINMENT & DISPOSAL OF WASTE(LOCATION & DESCRP) (BR. 19-I0065-8.80 R&L)	(1)	LS

Contract ID CNW360 - DAVIDSON

Item No.	Description	Quantity	Units
604-03.74	CLASS X CONCRETE	54.200	C.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	5,276.000	S.Y.
604-10.05	CONCRETE	50.000	S.F.
604-10.09	CONCRETE	75.000	C.Y.
604-10.13	CONCRETE SLAB REMOVAL	(1)	LS
604-10.18	REINFORCING STEEL (REPAIRS)	35,477.000	LB.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	30.000	S.Y.
604-10.41	EXPANSION JOINT REPAIRS (TYPE E)	80.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	185.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	20.000	S.Y.
604-10.54	CONCRETE REPAIRS	242.000	S.F.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	20.000	L.F.
617-01	BRIDGE DECK SEALANT	135.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,535.000	S.Y.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	112.000	L.F.
620-05.02	STANDARD CONCRETE CLASSIC PARAPET RAIL	26.000	L.F.
620-10.01	CONCRETE PARAPET (BRIDGERAIL REPLACEMENT)	600.000	L.F.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	122.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	109.080	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	3.000	EACH
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	2.000	EACH
709-05.06	MACHINED RIP-RAP (CLASS A-1)	83.000	TON
711-02.03	REINFORCED CONCRETE MEDIAN BARRIER (BRIDGES)	125.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,330.000	L.F.
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	840.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	470.000	L.F.

Contract ID CNW360 - DAVIDSON

Item No.	Description	Quantity	Units
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	248.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	24.000	EACH
712-06	SIGNS (CONSTRUCTION)	13,800.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	184.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	3,168.000	HOURL
712-08.12	QUEUE PROTECTION TRUCK	60.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	24.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	14,225.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	15,975.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	7,580.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	22.000	EACH
713-16.20	SIGNS (DESCRIPTION) (COVER OVERHEAD SIGN)	46.000	EACH
714-01.01	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 19-I0040-16.14)	(1)	LS
714-01.01	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO.19-I0065-8.80 R&L)	(1)	LS
714-02.02	ENCASED CONDUIT (2" PVC, SCHEDULE 40)	20.000	L.F.
714-06.07	CABLE (1/C # 2 AWG)	20.000	L.F.
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	54.000	EACH
716-01.14	RAISED PAVEMENT MARKER REMOVAL	47.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	58.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	484.000	L.F.
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	1.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.440	L.M.

Contract ID CNW360 - DAVIDSON

Item No.	Description	Quantity	Units
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	730.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	92.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	70.830	S.Y.
801-03	WATER (SEEDING & SODDING)	12.000	M.G.
803-01	SODDING (NEW SOD)	1,200.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW388 - DAVIDSON , ROBERTSON, ETC.

Contract ID: CNW388

Letting Date: December 09, 2022 10:00 AM

Projects: R3IMSC-F3-002

NH-I-098-3(33)

Counties: DAVIDSON, ROBERTSON, RUTHERFORD,
SUMNER, WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The Nashville SmartWay Intelligent Transportation System (ITS) Maintenance (2023 - 2026).

Contract Time: DT - 12/31/2026

Item No.	Description	Quantity	Units
725-10.75	TDOT SMARTWAY ITS SYSTEM MAINTENANCE (3 YEARS)	(1)	LS
725-10.76	REPAIR MAINTENANCE LABOR	6,000.000	HOUR
725-10.77	SPARE PARTS AND EQUIPMENT REPLACEMENT	2,000,000.000	DOLL
725-10.78	ONE CALL SERVICE	6,000.000	HOUR
725-10.79	SOFTWARE AND NETWORK MAINTENANCE AND SUPPORT	900,000.000	DOLL
725-10.80	SPECIAL MAINTENANCE REPAIR	7,500,000.000	DOLL

() Item will be bid as lump sum.

Contract ID CNW383 - FAYETTE , MADISON, ETC.

Contract ID: CNW383

Letting Date: December 09, 2022 10:00 AM

Projects: R4IVAR-F3-010

HSIP-I-REG4(219)

Counties: FAYETTE, MADISON, SHELBY

District:

DBE Goal Percent:

Description: The installation of longitudinal cable barrier on various Interstate Routes.

Contract Time: DT - 12/31/2023

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	62,806.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	50.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	8.000	DAY
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW387 - FAYETTE & SHELBY

Contract ID: CNW387

Letting Date: December 09, 2022 10:00 AM

Projects: 24I269-F8-002
79I269-F8-002
79I269-M3-003

NH-I-269(35)
NH-I-269(35)
NH-I-269-(35)

Counties: FAYETTE, SHELBY

District:

DBE Goal Percent: 7.50

Description: Resurfacing on I-269 in Shelby County from the Fayette County line near S.R. 193 (L.M. 0.63), crossing in/out of Fayette County to I-40 in Shelby County (L.M. 6.83), including bridge deck repair and thin epoxy overlay.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	198.000	S.Y.
203-06	WATER	26.180	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	29.900	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	3,802.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	92.000	TON
307-03.11	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING CW	7,257.000	TON
403-02.01	TRACKLESS TACK COAT	132.000	TON
403-02.02	HOT APPLIED TACK COAT	47.000	TON
403-05.01	BITUMINOUS MATERIAL (FOG SEAL) SHOULDER	1.200	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,685.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	42.400	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	10,396.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	3,963.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	27.700	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	28,756.000	TON

Contract ID CNW387 - FAYETTE & SHELBY

Item No.	Description	Quantity	Units
502-08.03	SEALING SHOULDER JOINTS	9,637.000	L.F.
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	17,500.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	2,232.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	875.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	67.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,543.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	7.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	4.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	46.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	72.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	7,450.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,399.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,399.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	86.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	19.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	4,578.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	229.000	S.F.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	13,522.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	30.138	L.M.

Contract ID CNW387 - FAYETTE & SHELBY

Item No.	Description	Quantity	Units
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	45,214.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	86.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	1.000	EACH
716-08.19	REMOVAL OF PAVEMENT MARKING (YIELD LINE)	229.000	S.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	47.198	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	13,522.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,544.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	315.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	4.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC)	40.000	L.F.
730-14.02	SAW SLOT	1,000.000	L.F.
730-14.03	LOOP WIRE	3,000.000	L.F.
730-15.09	CABINET (DESCRIPTION) (41" X 25" X 18")	2.000	EACH
604-10.44	EXPANSION JOINT REPAIRS	197.000	L.F.
604-10.53	CONCRETE REPAIRS	50.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	28,600.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW357 - GILES

Contract ID: CNW357

Letting Date: December 09, 2022 10:00 AM

Projects: 28I065-F8-003
28I065-M3-004

NH-I-65-1(78)
NA

Counties: GILES

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-65 from the Alabama state line (L.M. 0.00) to south of U.S. 64 (S.R. 15) (L.M. 13.72) including thin epoxy overlay on the bridge over S.R. 273.

Contract Time: DT - 10/15/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	54.900	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,652.000	TON
307-03.11	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING CW	47,581.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	536.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	3,609.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	31,720.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	54.900	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	41,437.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	140.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	64.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	10.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	10.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
706-01	GUARDRAIL REMOVED	500.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	70.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,368.000	S.F.

Contract ID CNW357 - GILES

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	24.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-02.14	FLEXIBLE DELINEATOR (WHITE)	200.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	200.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	2,126.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,822.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	3,740.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	68.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	5.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	64.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	4,792.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.910	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	64.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	9,900.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC)	20.000	L.F.
730-14.02	SAW SLOT	400.000	L.F.
730-14.03	LOOP WIRE	1,500.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	5.000	S.Y.
604-10.56	CONCRETE OVERLAYED BRIDGE DECK REPAIR (PARTIAL DEPTH)	5.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	7,523.000	S.Y.

Contract ID CNW357 - GILES

() Item will be bid as lump sum.

Contract ID CNW264 - GRAINGER

Contract ID: CNW264

Letting Date: December 09, 2022 10:00 AM

Projects: 29004-4247-04

N/A

Counties: GRAINGER

District:

DBE Goal Percent:

Description: The slope stabilization on U.S. 25E (S.R. 32) near the Pyrite Encapsulation Site at L.M. 7.2.

Contract Time: DT - 5/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (SIZE ,STA.)	19.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,615.000	C.Y.
203-01.07	RD & DRNG EXCV (ACID PRODUCING- OFF SITE DISPOSAL)	3,574.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	3,601.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,800.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	415.000	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	145.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-02.07	18" TEMPORARY SLOPE DRAIN	1,263.000	L.F.
209-03.22	FILTER SOCK (18 INCH)	1,036.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,080.000	L.F.
209-08.07	ROCK CHECK DAM	1.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	860.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	68.000	TON
707-01.11	CHAIN LINK FENCE (6 FOOT)	708.000	L.F.
707-01.12	END & CORNER POST ASSEMBLY(CHAIN-LINK FENCE 6')	4.000	EACH
707-05	WATER GATE	24.000	S.F.

Contract ID CNW264 - GRAINGER

Item No.	Description	Quantity	Units
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (SEE PLANS)	717.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,237.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	2.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	685.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	615.000	TON
710-10.08	18" PERFORATED PLASTIC PIPE	19.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	152.000	S.F.
717-01	MOBILIZATION	(1)	LS
740-06.01	GEOMEMBRANE	499.000	S.Y.
740-07.02	GEOGRID REINFORCEMENT (SOIL SLOPES)	2,315.000	S.Y.
740-10.01	GEOTEXTILE (TYPE I)(SUBSURFACE DRAINAGE)	125.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	2,950.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	668.000	L.F.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	1,313.000	L.F.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	2,193.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1.000	UNIT
801-01.16	BONDED FIBER MATRIX HYDROMULCH (W/PERMANENT SEED)	8.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	14.000	UNIT
801-02.01	CROWN VETCH MIXTURE (WITHOUT MULCH)	24.000	UNIT
801-03	WATER (SEEDING & SODDING)	4.000	M.G.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	870.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	3,626.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW371 - GRUNDY

Contract ID: CNW371

Letting Date: December 09, 2022 10:00 AM

Projects: 31999-3605-04

NA

Counties: GRUNDY

District:

DBE Goal Percent:

Description: The construction of a TDOT maintenance building at 9216 S.R. 56 in Coalmont.

Contract Time: DT - 11/30/2023

Item No.	Description	Quantity	Units
607-65.20	SITE PREPARATION	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (FOUNDATION AND STRUCTURE)	1.000	EACH
680-02.02	BUILDING (DESCRIPTION) (INTERIOR CONSTRUCTION)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW377 - HAYWOOD

Contract ID: CNW377

Letting Date: December 09, 2022 10:00 AM

Projects: 38003-4233-04

N/A

Counties: HAYWOOD

District:

DBE Goal Percent:

Description: The repair of bridges on U.S. 70 (S.R. 1) over branch of Nixon Creek (L.M. 19.60), over branch of Mud Creek (L.M. 22.64), and over Mud Creek (L.M. 24.24).

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 38-SR001-24.24)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,369.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	360.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	543.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	4.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	334.000	TON
411-02.11	ACS MIX(PG70-22) GRADING E RDWY	93.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	4,109.000	S.Y.
603-02.01	REPAINTING EXISTING STEEL STRUCTURES (LOC. & DES.) (38-SR001-22.64)	(1)	LS
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	419.000	S.Y.
604-10.05	CONCRETE	249.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.18	REINFORCING STEEL (REPAIRS)	16,571.000	LB.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	100.000	S.Y.
604-10.42	CONCRETE REPAIRS	1,621.000	C.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	10.000	S.Y.
604-10.51	SCARIFYING	110.000	S.Y.
604-10.54	CONCRETE REPAIRS	427.000	S.F.

Contract ID CNW377 - HAYWOOD

Item No.	Description	Quantity	Units
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	403.000	L.F.
604-12.15	DRILL & GROUT STEEL BARS	794.000	EACH
615-02.02	PRESTRESSED CONCRETE BOX BEAM (17" X 36")	103.000	L.F.
617-01	BRIDGE DECK SEALANT	224.000	S.Y.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	104.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	150.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	12.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	12.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,369.000	L.F.
709-05.08	MACHINED RIP-RAP (CLASS B)	467.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-01.05	FLAGMAN	160.000	HOUR
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	254.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	1,212.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	129.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	61.000	EACH
712-06	SIGNS (CONSTRUCTION)	774.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	21,092.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	96.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNW378 - HENDERSON

Contract ID: CNW378

Letting Date: December 09, 2022 10:00 AM

Projects: 39I040-F8-002
39I040-M3-003

NH-I-40-2(341)
NH-I-40-2(341)

Counties: HENDERSON

District:

DBE Goal Percent: 8.00

Description: The resurfacing on I-40 from west of S.R. 22 (L.M. 12.71) to the bridge over Morris Creek (L.M. 20.31), including bridge deck repair and thin epoxy overlay.

Contract Time: DT - 10/15/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	534.000	S.Y.
203-06	WATER	25.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	30.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	3,464.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	246.000	TON
307-03.11	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING CW	27,917.000	TON
403-02.01	TRACKLESS TACK COAT	153.000	TON
403-02.02	HOT APPLIED TACK COAT	214.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	31.000	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	1,249.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	18,394.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	30.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	46,448.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	33.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	33.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	940.000	L.F.

Contract ID CNW378 - HENDERSON

Item No.	Description	Quantity	Units
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	1,052.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	47.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	1,004.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	374.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,896.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	67.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	35,920.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,072.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,072.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	100.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	475.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	87.200	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	11,430.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	42.500	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,360.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	5.000	S.Y.
604-10.53	CONCRETE REPAIRS	7.000	S.Y.

Contract ID CNW378 - HENDERSON

Item No.	Description	Quantity	Units
604-10.56	CONCRETE OVERLAYED BRIDGE DECK REPAIR (PARTIAL DEPTH)	7.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	6,146.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW362 - HICKMAN

Contract ID: CNW362

Letting Date: December 09, 2022 10:00 AM

Projects: 41001-4154-04

N/A

Counties: HICKMAN

District:

DBE Goal Percent:

Description: The repair of the bridges on I-40 over Sugar Creek (L.M. 2.71).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 41-I0040-02.71 R&L)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	650.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.500	TON
411-03.10	ACS MIX(PG76-22) GRADING D	52.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	771.067	S.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	712.000	S.Y.
604-10.05	CONCRETE	10.000	S.F.
604-10.18	REINFORCING STEEL (REPAIRS)	16,570.000	LB.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	55.000	S.Y.
604-10.42	CONCRETE REPAIRS	1,771.000	C.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	75.000	S.Y.
604-10.54	CONCRETE REPAIRS	6.000	S.F.
604-12.15	DRILL & GROUT STEEL BARS	284.000	EACH
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	570.000	S.Y.
620-05.02	STANDARD CONCRETE CLASSIC PARAPET RAIL	507.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	200.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	5.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	650.000	L.F.

Contract ID CNW362 - HICKMAN

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	990.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	310.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	26.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,000.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	240.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	19,780.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	8,260.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	8,260.000	L.F.
716-01.14	RAISED PAVEMENT MARKER REMOVAL	5.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.100	L.M.
717-01	MOBILIZATION	(1)	LS
725-21.07	PORTABLE SMART WORK ZONE SYSTEM	240.000	DAY

() Item will be bid as lump sum.

Contract ID CNW299 - HUMPHREYS

Contract ID: CNW299

Letting Date: December 09, 2022 10:00 AM

Projects: 43455-3432-04

N/A

Counties: HUMPHREYS

District:

DBE Goal Percent:

Description: The construction of a concrete box beam bridge on Tatum Lane over Blue Creek (L.M. 0.09), including grading, drainage and paving.

Contract Time: DT - 5/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (12", 52+54.47)	24.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,528.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	2,550.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	2,397.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	561.000	C.Y.
203-06	WATER	22.500	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.100	L.M.
209-05	SEDIMENT REMOVAL	61.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	881.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	622.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,773.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	34.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	236.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.600	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	12.800	TON

Contract ID CNW299 - HUMPHREYS

Item No.	Description	Quantity	Units
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.100	TON
411-01.10	ACS MIX(PG64-22) GRADING D	183.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	27.000	TON
607-03.30	18" PIPE CULVERT	28.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	75.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	50.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	548.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	150.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,428.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	162.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	35.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	0.240	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	45.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	49.000	LB.
713-11.21	P POST SLIP BASE	1.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	9.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	9.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	26.000	L.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	1.200	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	581.000	S.Y.

Contract ID CNW299 - HUMPHREYS

Item No.	Description	Quantity	Units
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,080.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,787.000	L.F.
801-01	SEEDING (WITH MULCH)	11.300	UNIT
801-01.02	CROWN VETCH MIXTURE (WITH MULCH)	17.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	17.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	4.300	UNIT
801-03	WATER (SEEDING & SODDING)	5.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	306.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 43-0A276-00.09)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	94.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	20.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	30,293.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	52.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	12,208.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	109.000	C.Y.
604-03.74	CLASS X CONCRETE	22.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	676.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	678.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	12.000	EACH
606-20.03	STEEL PIPE PILES (18-INCH)	460.000	L.F.
606-20.06	PILE TIPS (STEEL PIPE PILES, 18-INCH)	8.000	EACH
615-02.37	PRESTRESSED CONCRETE BOX BEAM (30" X 36")	417.000	L.F.
620-06	CONCRETE RAILING	336.000	L.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	108.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	84.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	38.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW368 - JEFFERSON

Contract ID: CNW368

Letting Date: December 09, 2022 10:00 AM

Projects: 45I040-F8-002

NH-I-40-8(190)

Counties: JEFFERSON

District:

DBE Goal Percent: 7.50

Description: The resurfacing on I-40 from the Sevier County line (L.M. 0.00) to near U.S. 25W (U.S. 70, S.R. 9) (L.M. 5.94).

Contract Time: CD - 200 Days

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	29.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	251.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,591.000	TON
307-03.09	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING C	22,476.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	118.000	TON
403-02.02	HOT APPLIED TACK COAT	286.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	24.000	L.M.
411-03.23	ACS MIX (PG76-22) OGFC	26,303.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	24.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	24,317.000	TON
502-08.01	RESEALING JOINTS (HOT POURED ELASTIC)	10,120.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	131.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	66.000	EACH
712-06	SIGNS (CONSTRUCTION)	5,637.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH

Contract ID CNW368 - JEFFERSON

Item No.	Description	Quantity	Units
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,708.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,708.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	110.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	12,895.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	5.000	EACH
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	33.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,985.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	1,740.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW369 - KNOX

Contract ID: CNW369

Letting Date: December 09, 2022 10:00 AM

Projects: 47I275-M3-003

NA

Counties: KNOX

District:

DBE Goal Percent:

Description: The repair of four (4) bridges on or over I-275 at Baxter Avenue and Heiskell Avenue between L.M. 0.68 and L.M. 2.25.

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
602-10.32	STRUCTURAL STEEL (REPAIRS)	912.000	LB.
604-10.05	CONCRETE	1,412.000	S.F.
604-10.42	CONCRETE REPAIRS	83.000	C.F.
604-10.54	CONCRETE REPAIRS	470.000	S.F.
604-10.58	EPOXY INJECTION (INJECTION)	5.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	111.000	L.F.
604-10.83	COMPOSITE FIBER ENCASEMENT	761.000	S.F.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	70.000	EACH
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,175.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	390.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,780.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	30.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	22,200.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	8.000	EACH
717-01	MOBILIZATION	(1)	LS

Contract ID CNW369 - KNOX

() Item will be bid as lump sum.

Contract ID CNW151 - LAUDERDALE

Contract ID: CNW151

Letting Date: December 09, 2022 10:00 AM

Projects: 49131-3208-94

HSIP/PHSIP-3(133)

Counties: LAUDERDALE

District:

DBE Goal Percent: 9.00

Description: The improvement of the intersection on U.S. 51 (S.R. 3) at Curve Nankipoo Road (L.M. 14.43), including grading, drainage and paving.

Contract Time: DT - 7/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-03.03	REMOVAL OF ASPHALT PAVEMENT	834.000	C.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	18,594.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	18,503.000	C.Y.
203-03.10	SELECT GRANULAR MATERIAL	895.000	TON
203-04	PLACING AND SPREADING TOPSOIL	4,101.000	C.Y.
203-05	UNDERCUTTING	511.000	C.Y.
203-06	WATER	140.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	690.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	4.400	C.Y.
209-05	SEDIMENT REMOVAL	230.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	860.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	4,000.000	L.F.
209-08.07	ROCK CHECK DAM	8.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	14.000	EACH
209-09.01	SANDBAGS	200.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	200.000	S.Y.
209-40.32	CATCH BASIN PROTECTION (TYPE C)	4.000	EACH

Contract ID CNW151 - LAUDERDALE

Item No.	Description	Quantity	Units
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	5,260.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	100.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	200.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	450.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	470.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	322.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,002.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	478.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	13.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	45.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	10.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	2,700.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	88.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	291.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	280.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	400.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	261.000	L.F.
607-03.05	18" CONCRETE PIPE CULVERT(CLASS IV)JACKED- IN-PLACE	110.000	L.F.
607-37.04	30" CORRUGATED METAL PIPE CULVERT	82.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	136.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
611-07.51	15IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	4.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH

Contract ID CNW151 - LAUDERDALE

Item No.	Description	Quantity	Units
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	72.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	100.000	C.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	478.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	500.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	1,090.000	L.F.
707-06.03	REMOVAL AND RESET FENCE (DESCRIPTION) (BARB WIRE)	250.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	600.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	13.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	346.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	250.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	25.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	760.000	L.F.
710-05	LATERAL UNDERDRAIN	96.000	L.F.
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	1.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	3.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	4,600.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	5.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	85.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	230.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	10.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	15.000	EACH
712-06	SIGNS (CONSTRUCTION)	907.000	S.F.

Contract ID CNW151 - LAUDERDALE

Item No.	Description	Quantity	Units
712-07.02	TEMPORARY BARRICADES (TYPE II)	60.000	L.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	120.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	3,600.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	50.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	6,270.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	140.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	324.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,170.000	LB.
713-11.21	P POST SLIP BASE	2.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	50.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	300.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (PROTECTED AREA)	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	120.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	20.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	34.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	710.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	65.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	360.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	31.000	S.F.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	1,100.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	2.920	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.920	L.M.

Contract ID CNW151 - LAUDERDALE

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	731.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,400.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,000.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	384.000	UNIT
801-02.08	TEMPORARY SEEDING (WITHOUT MULCH)	10.000	UNIT
801-03	WATER (SEEDING & SODDING)	288.000	M.G.
802-11.01	ACER NEGUNDO (BOX ELDER 2-5FT CNTNR GRWN)	3.000	EACH
802-11.16	FRAXINUS PENNSYLVANICA (GREEN ASH 2-5FT CNTNR GRWN)	3.000	EACH
802-11.18	LIQUIDAMBER STYRACIFLUA (SWEETGUM 2-5FT CNTNR GRWN)	3.000	EACH
802-11.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR 2-5FT CNTNR GRWN)	3.000	EACH
802-11.44	ULMUS AMERICANA (AMERICAN ELM 2-5FT CNTNR GRWN)	2.000	EACH
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	3.000	EACH
802-12.16	FRAXINUS PENNSYLVANICA (GREEN ASH SEEDLNG B.R.)	3.000	EACH
802-12.18	LIQUIDAMBER STYRACIFLUA (SWEETGUM SEEDLNG B.R.)	3.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	3.000	EACH
802-12.44	ULMUS AMERICANA (AMERICAN ELM SEEDLNG B.R.)	3.000	EACH
803-01	SODDING (NEW SOD)	28,750.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW370 - LOUDON

Contract ID: CNW370

Letting Date: December 09, 2022 10:00 AM

Projects: 53002-3165-44

NH-SIP-I-75-2(45)

Counties: LOUDON

District:

DBE Goal Percent: 5.50

Description: The interchange improvement on I-75 at S.R. 72 in Loudon (L.M. 5.65), including grading, drainage and paving with Portland Cement Concrete.

Contract Time: DT - 6/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,118.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	105.000	C.Y.
203-05	UNDERCUTTING	300.000	C.Y.
203-06	WATER	1.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.120	L.M.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	656.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,732.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	45.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	85.000	TON
313-03	TREATED PERMEABLE BASE	751.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	5.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	48.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	575.000	S.Y.
502-03.21	PARTIAL DEPTH PCC PAVEMENT REPAIR	3.000	S.Y.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	300.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	40.000	TON

Contract ID CNW370 - LOUDON

Item No.	Description	Quantity	Units
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	645.000	L.F.
710-05	LATERAL UNDERDRAIN	125.000	L.F.
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	2.000	EACH
710-06.14	LATERAL UNDERDRAIN ENDWALL (5:1)	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	51.000	EACH
712-06	SIGNS (CONSTRUCTION)	234.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	284.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	280.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	157.000	LB.
713-11.01	"U" SECTION STEEL POSTS	113.000	LB.
713-11.22	U POST SLIP BASE	4.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	63.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	36.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	1.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	41.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	15.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.390	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.310	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	67.000	S.Y.

Contract ID CNW370 - LOUDON

Item No.	Description	Quantity	Units
801-02	SEEDING (WITHOUT MULCH)	22.000	UNIT
801-02.15	FERTILIZER	1.000	TON
801-03	WATER (SEEDING & SODDING)	2.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	618.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW385 - MADISON

Contract ID: CNW385

Letting Date: December 09, 2022 10:00 AM

Projects: 57134-3202-94

NH-SIP-43(41)

Counties: MADISON

District:

DBE Goal Percent: 6.50

Description: The improvement of the intersection on U.S. 45E (S.R. 43) at Green Valley Farms (L.M. 0.53 - L.M. 0.84).

Contract Time: DT - 7/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,630.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	233.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	402.000	C.Y.
203-06	WATER	16.000	M.G.
209-05	SEDIMENT REMOVAL	27.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	610.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	100.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	4.000	EACH
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	1,586.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	314.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	113.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	21.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	85.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	100.000	L.F.

Contract ID CNW385 - MADISON

Item No.	Description	Quantity	Units
411-02.10	ACS MIX(PG70-22) GRADING D	127.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	12.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	77.000	TON
710-05	LATERAL UNDERDRAIN	30.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	100.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	703.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	10,640.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	110.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	735.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	50.000	LB.
713-11.21	P POST SLIP BASE	1.000	EACH
713-11.22	U POST SLIP BASE	22.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	155.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	15.000	EACH
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	55.000	S.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	7.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.125	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.925	L.M.

Contract ID CNW385 - MADISON

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	133.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	570.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	22.000	UNIT
801-03	WATER (SEEDING & SODDING)	28.000	M.G.
803-01	SODDING (NEW SOD)	2,413.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW153 - MARSHALL

Contract ID: CNW153

Letting Date: December 09, 2022 10:00 AM

Projects: 59003-3226-94

BR-STP-11(99)

Counties: MARSHALL

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete Bulb-Tee beam bridge on U.S. 31A (S.R. 11, Nashville Highway) over Rock Creek (L.M. 13.18) in Lewisburg, including grading, drainage and paving.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,180.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	470.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,088.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	88.000	C.Y.
203-06	WATER	44.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	52.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,143.000	L.F.
209-08.07	ROCK CHECK DAM	3.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-08.09	FILTER SOCK CHECK DAM	7.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	668.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,131.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,082.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	274.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	182.000	TON

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	12.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	187.000	TON
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	100.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	70.000	LB.
621-03.02	18" TEMPORARY DRAINAGE PIPE	80.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	325.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	384.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	216.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	6.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	261.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	400.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	21.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	6.000	EACH
712-06	SIGNS (CONSTRUCTION)	421.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	52.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	2,124.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	50.000	L.F.
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	5.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	11.000	EACH

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	11.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.600	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.01	GEO GRID REINFORCEMENT	1,326.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,960.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	500.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	710.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	805.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	10.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	5.000	UNIT
801-03	WATER (SEEDING & SODDING)	8.000	M.G.
802-02.33	CUTTINGS: SAMBUCUS CANADENSIS (18IN-24IN)	1,340.000	EACH
802-12.02	ACER RUBRUM (RED MAPLE SEEDLNG B.R.)	30.000	EACH
802-12.17	JUGLANS NIGRA (BLACK WALNUT SEEDLNG B.R.)	30.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	30.000	EACH
803-01	SODDING (NEW SOD)	529.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	446.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 59-SR11-13.18)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	339.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	41.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	72.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	48.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.1,STA.75+13.00)	(1)	LS

Contract ID CNW153 - MARSHALL

Item No.	Description	Quantity	Units
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.2,STA.76+05.00)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	27.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	63.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	34.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	85,159.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	338.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	46,438.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	235.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	365.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,605.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,533.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	252.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	18.000	EACH
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	1,358.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	324.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	2.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	620.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	148.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	48.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW365 - MCMINN

Contract ID: CNW365

Letting Date: December 09, 2022 10:00 AM

Projects: 54001-3188-04
54017-3214-04

N/A
n/a

Counties: MCMINN

District:

DBE Goal Percent:

Description: The cable barrier and guardrail installation at various locations on I-75 and S.R. 39.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
209-03.21	FILTER SOCK (12 INCH)	533.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	300.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	5.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	1,022.500	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	250.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	725.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
705-06.40	CABLE BARRIER (MASH TL-3)	629.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
706-01	GUARDRAIL REMOVED	53.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	180.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	180.000	EACH
712-06	SIGNS (CONSTRUCTION)	702.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	50.000	HOUR
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
717-01	MOBILIZATION	(1)	LS

Contract ID CNW365 - MCMINN

() Item will be bid as lump sum.

Contract ID CNW364 - MEIGS

Contract ID: CNW364

Letting Date: December 09, 2022 10:00 AM

Projects: 61003-3265-94
61003-3266-04

STP-SIP-58(59)
N/A

Counties: MEIGS

District:

DBE Goal Percent: 9.50

Description: The construction of a roundabout and four approaches on S.R. 58 at the intersection of S.R. 68 (L.M. 26.85), and safety improvements on S.R. 58 near Nebo Road (L.M. 29.20).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (18" ,STA. 23+58.19, S.R. 58)	24.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (18" ,STA. 54+75.52, S.R. 68E)	20.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,378.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	2,102.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	1,155.000	C.Y.
203-06	WATER	40.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	321.000	C.Y.
209-03.21	FILTER SOCK (12 INCH)	170.000	L.F.
209-05	SEDIMENT REMOVAL	170.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	200.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	1,200.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	14.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	4.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	1.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	11.000	EACH

Contract ID CNW364 - MEIGS

Item No.	Description	Quantity	Units
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	1.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	1.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	4,693.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	30.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,121.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	674.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	14.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	53.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.300	TON
407-02.13	REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	580.000	S.Y.
407-20.05	SAW CUTTING ASPHALT PAVEMENT	700.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	481.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	0.190	L.M.
415-01.03	COLD PLANING BITUMINOUS PAVEMENT	145.000	C.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	162.000	C.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	987.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	80.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	4.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	6.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	5.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	1.000	EACH
611-26.01	CATCH BASINS, TYPE 26, 0' - 4' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	2.000	EACH
701-03	CONCRETE MEDIAN PAVEMENT	49.000	C.Y.
702-01	CONCRETE CURB	50.000	C.Y.

Contract ID CNW364 - MEIGS

Item No.	Description	Quantity	Units
702-03	CONCRETE COMBINED CURB & GUTTER	96.000	C.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	451.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	125.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	50.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	450.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	151.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	159.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	190.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	115.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,076.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	195.000	L.F.
712-10.02	TEMPORARY TRANSVERSE RUMBLE STRIPS	480.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	8.100	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	1,769.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	3,304.000	LB.
713-11.21	P POST SLIP BASE	67.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	606.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
713-16.41	RELOCATE SIGN	(1)	LS
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	150.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	38.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	22.000	EACH

Contract ID CNW364 - MEIGS

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	39.000	S.Y.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	155.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	78.000	S.F.
716-05.09	PAINTED PAVEMENT MARKING(STRAIGHT-TURN ARROW)	8.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	2.800	L.M.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	4.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	1.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	634.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	1,300.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	299.000	UNIT
801-03	WATER (SEEDING & SODDING)	141.000	M.G.
803-01	SODDING (NEW SOD)	11,069.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL

() Item will be bid as lump sum.

Contract ID CNW359 - PUTNAM

Contract ID: CNW359

Letting Date: December 09, 2022 10:00 AM

Projects: 711040-F8-003

NH-I-40-6(183)

Counties: PUTNAM

District:

DBE Goal Percent: 7.50

Description: The resurfacing on I-40 from the Smith County line (L.M. 0.00) to east of S.R. 56 (L.M. 6.80).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.600	L.M.
209-70.01	VACUUM TRUCK/SWEEPER FOR ROADWAY DEBRIS	120.000	HOURL
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,800.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,000.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	16.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	15,958.000	S.Y.
403-02.01	TRACKLESS TACK COAT	181.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	6,646.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	26,556.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	26.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	32,849.000	TON
705-04.20	GUARDRAIL DELINEATION ENHANCEMENT	13,000.000	EACH
709-05.06	MACHINED RIP-RAP (CLASS A-1)	75.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	180.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,272.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH

Contract ID CNW359 - PUTNAM

Item No.	Description	Quantity	Units
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	500.000	HOUR
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,033.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,033.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	262.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	2,943.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	450.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	4.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	3,450.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	33.900	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.900	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	3,450.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	759.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW325 - PUTNAM

Contract ID: CNW325

Letting Date: December 09, 2022 10:00 AM

Projects: 71002-3226-04

N/A

71011-3240-04

N/A

71952-3252-04

N/A

Counties: PUTNAM

District:

DBE Goal Percent:

Description: The safety improvements on U.S. 70N (S.R. 24) at Hawkins Crawford Road and Plunk Whitson Road, on S.R. 135 near the I-40 EB/WB ramps, and various intersections along S.R. 135 and S.R. 136 in Cookeville.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (STA. 62+90 RT)	11.000	L.F.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.100	L.M.
209-05	SEDIMENT REMOVAL	1.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	64.000	L.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	40.000	S.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	3.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	450.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	18.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	85.000	L.F.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	30.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	20.000	L.F.

Contract ID CNW325 - PUTNAM

Item No.	Description	Quantity	Units
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	85.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	33.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.010	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.01	SIGNAL HEAD ASSEMBLY (110)	2.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (330)	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-05.04	MODIFY EXISTING ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	548.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	476.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	464.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	1.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC)	16.000	L.F.
730-15.07	CABINET (DESCRIPTION) (NEMA TYPE 3R FLASHING SIGNAL CONTROLLER)	1.000	EACH
730-15.11	MODIFY CABINET (DESCRIPTION) (BATTERY BACKUP INSTALLATION)	10.000	EACH
730-15.11	MODIFY CABINET (DESCRIPTION) (INSTALL PEDESTRIAN EQUIPMENT)	1.000	EACH
730-16.03	CONTROLLER (FLASHING BEACON)	1.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (TYPE A - 10 FOOT)	1.000	EACH
730-25.18	CANTILEVER SIGNAL SUPPORT (1 ARM @ 90')	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSH BUTTON & 15IN SIGN	6.000	EACH
730-35.06	BATTERY BACK-UP AND POWER CONDITIONER	10.000	EACH
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	20.000	L.F.

() Item will be bid as lump sum.

Contract ID CNW361 - ROBERTSON

Contract ID: CNW361

Letting Date: December 09, 2022 10:00 AM

Projects: 74I065-M3-008

NA

Counties: ROBERTSON

District:

DBE Goal Percent:

Description: The installation of an overhead sign structure on I-65 NB at L.M. 16.54.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.03	LANE CLOSURE(NIGHT WORK)	15.000	EACH
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	796.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	150.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	60.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	100.000	HOUR
713-09.20	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (98+/-)	1.000	EACH
713-14	EXTRUDED ALUMINUM PANEL SIGNS	130.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	1.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNW356 - RUTHERFORD

Contract ID: CNW356

Letting Date: December 09, 2022 10:00 AM

Projects: 75013-3255-94

HSIP-99(69)

Counties: RUTHERFORD

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on S.R. 99 at the intersection of S.R. 269 (Jackson Ridge Road) (L.M. 7.74), including installation of a flashing beacon.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	64.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	146.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	60.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	720.000	LB.
713-11.21	P POST SLIP BASE	12.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	8.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	136.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	33.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	33.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	35.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	2.000	EACH
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	360.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	2.000	EACH
716-08.22	REMOVAL OF PAVEMENT MARKING (NOISE STRIP)	240.000	L.F.

Contract ID CNW356 - RUTHERFORD

Item No.	Description	Quantity	Units
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-02.21	SIGNAL HEAD ASSEMBLY (220)	2.000	EACH
730-02.27	SIGNAL HEAD ASSEMBLY (440)	1.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	80.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	100.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	100.000	L.F.
730-15.07	CABINET (DESCRIPTION) (NEMA TYPE 3R FLASHING SIGNAL)	1.000	EACH
730-16.03	CONTROLLER (FLASHING BEACON)	1.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	2.000	EACH
730-26.08	FLASHING WARNING BEACON (DESCRIPTION) (AMBER)	8.000	EACH

() Item will be bid as lump sum.

Contract ID CNW346 - SHELBY

Contract ID: CNW346

Letting Date: December 09, 2022 10:00 AM

Projects: 79044-3509-94

HSIP-2810(10)

Counties: SHELBY

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, signals and paving on Airways Boulevard at the intersection of Ketchum Road in Memphis (L.M. 1.92), including realignment of Ramp A to I-240.

Contract Time: DT - 12/15/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	518.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	455.000	S.Y.
202-08.10	REMOVAL OF CURB (DESCRIPTION) (CURB AND GUTTER)	1,803.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,552.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	303.000	C.Y.
203-06	WATER	16.000	M.G.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	60.000	C.Y.
209-05	SEDIMENT REMOVAL	40.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	909.000	L.F.
209-08.07	ROCK CHECK DAM	6.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	5.000	EACH
209-09.01	SANDBAGS	25.000	BAG
209-09.40	CURB INLET PROTECTION (TYPE 1)	1.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	14.000	EACH
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	200.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	9.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,258.000	TON

Contract ID CNW346 - SHELBY

Item No.	Description	Quantity	Units
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	50.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	50.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	94.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	235.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	190.000	TON
313-03	TREATED PERMEABLE BASE	860.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	10.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	6.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,931.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	799.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	10,013.000	S.Y.
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	860.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	26.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	534.000	EACH
502-04.03	TRANSVERSE TIE-BARS	501.000	EACH
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	820.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	138.000	L.F.
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.62	30IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.65	36IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	4.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	6.000	EACH
611-16.02	CATCH BASINS, TYPE 16, > 4' - 8' DEPTH	3.000	EACH
611-25.02	CATCH BASINS, TYPE 25, > 4' - 8' DEPTH	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	72.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	10,470.000	S.F.
701-02.03	CONCRETE CURB RAMP	1,083.000	S.F.

Contract ID CNW346 - SHELBY

Item No.	Description	Quantity	Units
702-03	CONCRETE COMBINED CURB & GUTTER	121.000	C.Y.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	7.400	C.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	1.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	800.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	3.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (CONTROL ACCESS FENCE)	65.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	50.000	L.F.
707-11.01	PEDESTRIAN CONSTRUCTION BARRIER FENCE	1,000.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	201.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	19.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	29.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	1,854.000	L.F.
710-05	LATERAL UNDERDRAIN	932.000	L.F.
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	1.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	4.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	390.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	346.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	20.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	213.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	92.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,043.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	102.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	8.000	EACH

Contract ID CNW346 - SHELBY

Item No.	Description	Quantity	Units
712-09.01	REMOVABLE PAVEMENT MARKING LINE	503.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	390.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	77.000	L.F.
713-09.01	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 114.20 FT.)	1.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	2.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	170.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK)	64.000	S.F.
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	3.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R1-2, R3-2)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (M3-4, M1-1, M5-6)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (SPEC.)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (W11-2, W16-7P)	1.000	EACH
713-16.24	SIGNS (DESCRIPTION) (R4-4)	2.000	EACH
713-16.25	SIGNS (DESCRIPTION) (R3-7R)	2.000	EACH
713-16.26	SIGNS (DESCRIPTION) (R3-17)	3.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	49.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	458.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	15.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	306.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	416.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.300	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	13.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	5.000	EACH

Contract ID CNW346 - SHELBY

Item No.	Description	Quantity	Units
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	1.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	4.000	EACH
716-04.21	GREEN TEXTURED BIKE LANE	41.000	S.Y.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-05.09	PAINTED PAVEMENT MARKING(STRAIGHT-TURN ARROW)	17.000	EACH
716-05.11	PAINTED PAVEMENT MARKING(STRAIGHT ARROW)	19.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	3.000	L.M.
716-06.01	PAINTED WORD PVMT MARK ()	7.000	EACH
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	15.000	EACH
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	6.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	0.780	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.450	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-01.04	MODIFICATION OF EXISTING TRAFFIC SIGNAL EQUIPMENT	(1)	LS
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	9.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	1.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130 A3 WITH BACKPLATE)	5.000	EACH
730-02.31	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130 A3 POLE MOUNTED)	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	4.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH

Contract ID CNW346 - SHELBY

Item No.	Description	Quantity	Units
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	2,710.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,475.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	310.000	L.F.
730-08.40	INTERCONNECT CABLE - FIBER OPTIC (DESCRIPTION) (6 STRAND SM)	165.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC)	115.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC)	175.000	L.F.
730-12.16	CONDUIT (DESCRIPTION) (2" DIAMETER PVC SCHEDULE 80 JACK AND BORE)	150.000	L.F.
730-12.17	CONDUIT (DESCRIPTION) (3" DIAMETER PVC SCHEDULE 80 JACK AND BORE)	740.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (VIDEO IMAGING AND RADAR SYSTEM)	2.000	EACH
730-13.09	VEHICLE DETECTOR (DESCRIPTION) (VIDEO IMAGING SYSTEM)	2.000	EACH
730-13.10	VEHICLE DETECTOR (DESCRIPTION) (OPTICALLY ACTIVATED PREEMPTION)	4.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (10' TYPE A PEDESTRIAN)	3.000	EACH
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	2.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSH BUTTON & 15IN SIGN	8.000	EACH
730-35.06	BATTERY BACK-UP AND POWER CONDITIONER	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	344.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	856.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	37.000	UNIT
801-03	WATER (SEEDING & SODDING)	45.000	M.G.
803-01	SODDING (NEW SOD)	4,092.000	S.Y.

Contract ID CNW346 - SHELBY

() Item will be bid as lump sum.

Contract ID CNW386 - SULLIVAN

Contract ID: CNW386

Letting Date: December 09, 2022 10:00 AM

Projects: 82956-3293-04

N/A

Counties: SULLIVAN

District:

DBE Goal Percent:

Description: Widening of the I-26 NB exit ramp at U.S. 11E (S.R. 1), safety improvements on U.S. 11E (S.R. 1) at S.R. 36, and construction of an industrial access entrance at S.R. 36 and S.R. 355, in support of Project Smoky.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	441.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,048.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	6.000	C.Y.
209-03.23	FILTER SOCK (24 INCH)	2,420.000	L.F.
209-05	SEDIMENT REMOVAL	38.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	650.000	L.F.
209-08.09	FILTER SOCK CHECK DAM	16.000	EACH
209-09.41	CURB INLET PROTECTION (TYPE 2)	2.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,119.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	2.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	89.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	58.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	100.000	TON
313-03	TREATED PERMEABLE BASE	1,549.000	S.Y.

Contract ID CNW386 - SULLIVAN

Item No.	Description	Quantity	Units
411-01.10	ACS MIX(PG64-22) GRADING D	1.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	170.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	2,049.000	S.Y.
501-01	PORTLAND CEMENT CONCRETE PAVEMENT(REPLACEMENT)	1,549.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	663.000	L.F.
604-10.07	CONCRETE REMOVAL	(1)	LS
604-36	SCARIFYING	592.000	S.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	1,637.000	S.F.
701-02.03	CONCRETE CURB RAMP	759.000	S.F.
702-01	CONCRETE CURB	3.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	50.000	C.Y.
705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,500.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	75.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	10.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	871.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-09.05	REMOVABLE PAVEMENT MARKING (ARROW)	2.000	EACH
712-09.07	REMOVABLE PAVEMENT MARKING (STOP AHEAD)	12.000	EACH
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	5,900.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	303.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	48.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	9.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	7.000	EACH

Contract ID CNW386 - SULLIVAN

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R3-33, RIGHT LANE MUST EXIT, 78"x36")	1.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	48.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	168.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	291.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,650.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	42.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.800	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	169.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	24.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	10.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130A3 WITH BACKPLATE)	4.000	EACH
730-02.31	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (130A3 WITH LOUVERS AND BACKPLATE)	2.000	EACH
730-02.32	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (140A1 WITH BACKPLATE)	2.000	EACH
730-02.33	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (140A4F WITH BACKPLATE)	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	12.000	EACH

Contract ID CNW386 - SULLIVAN

Item No.	Description	Quantity	Units
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	2,912.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,365.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	226.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC)	518.000	L.F.
730-12.08	CONDUIT 2" DIAMETER (RGS)	119.000	L.F.
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	1,592.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (RADAR DETECTION - STOP LINE)	5.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (TYPE A - PEDESTRIAN SIGNALS)	4.000	EACH
730-23.36	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 50')	1.000	EACH
730-23.37	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 65')	2.000	EACH
730-23.38	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (1 ARM @ 80')	1.000	EACH
730-23.80	CANTILEVER SIGNAL SUPPORT (1 ARM @ 40')	1.000	EACH
730-23.88	CANTILEVER SIGNAL SUPPORT (1 ARM @ 45')	3.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSH BUTTON & 15IN SIGN	8.000	EACH
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
801-01	SEEDING (WITH MULCH)	10.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	20.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	8.500	UNIT
801-02.15	FERTILIZER	1.000	TON
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	942.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNW929 - CARTER , JOHNSON, ETC.

Contract ID: CNW929

Letting Date: December 09, 2022 10:00 AM

Projects: R1SVAR-M3-022

NA

R1SVAR-M3-023

N/A

Counties: CARTER, JOHNSON, SULLIVAN, UNICOI,
WASHINGTON

District:

DBE Goal Percent:

Description: The mowing and litter removal on various State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
719-02	REMOVAL AND DISPOSAL OF LITTER	2,189.000	L.M.
806-01	MOWING	7,814.000	ACRE

() Item will be bid as lump sum.

Contract ID CNW714 - CHESTER , HARDEMAN, ETC.

Contract ID: CNW714

Letting Date: December 09, 2022 10:00 AM

Projects: R4SVAR-M3-012

N/A

R4SVAR-M3-013

N/A

Counties: CHESTER, HARDEMAN, HARDIN, MCNAIRY

District:

DBE Goal Percent:

Description: The mowing and litter removal on various State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
719-02	REMOVAL AND DISPOSAL OF LITTER	2,738.000	L.M.
806-01	MOWING	16,569.000	ACRE

() Item will be bid as lump sum.

Contract ID CNW927 - DICKSON , HICKMAN, ETC.

Contract ID: CNW927

Letting Date: December 09, 2022 10:00 AM

Projects: R3SVAR-M3-025

N/A

R3SVAR-M3-026

N/A

Counties: DICKSON, HICKMAN, HUMPHREYS

District:

DBE Goal Percent:

Description: The mowing and litter removal on various State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
719-02	REMOVAL AND DISPOSAL OF LITTER	930.000	L.M.
806-01	MOWING	3,962.000	ACRE

() Item will be bid as lump sum.

Contract ID CNW928 - HOUSTON , MONTGOMERY, ETC.

Contract ID: CNW928

Letting Date: December 09, 2022 10:00 AM

Projects: R3SVAR-M3-027

N/A

R3SVAR-M3-028

N/A

Counties: HOUSTON, MONTGOMERY, STEWART

District:

DBE Goal Percent:

Description: The mowing and litter removal on various State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
717-10.01	INVOLUNTARY WORK SUSPENSION (DESCRIPTION) (BY THE DAY)	6.000	DAY
719-02	REMOVAL AND DISPOSAL OF LITTER	420.000	L.M.
806-01	MOWING	5,534.000	ACRE

() Item will be bid as lump sum.