

Estimated Quantities -- Letting August 18, 2023

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNX909 - JEFFERSON

Contract ID: CNX909

Letting Date: August 18, 2023 10:00 AM

Projects: 45945-3694-14

STP-4500(31)

Counties: JEFFERSON

District:

DBE Goal Percent: 6.00

Description: The stream mitigation for Anderson Branch on the Bush Brothers property.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (18"x24" OVAL CONC., STR-1 STA. 26+64.23)	20.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-1 STA. 27+31.37)	20.000	L.F.
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (36" CMP , STR-1 STA. 32+62.80)	20.000	L.F.
202-02.04	REMOVAL OF PIPE (SIZE ,STA.) (36" CMP, STR-1 STA. 37+73.48)	40.000	L.F.
202-02.05	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-1 STA. 48+03.23)	20.000	L.F.
202-02.06	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-4 STA. 07+05.33)	31.000	L.F.
202-02.07	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP, STR-4 TRIB STA. 00+11.73)	29.000	L.F.
202-02.08	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP, STR-5 STA. 06+76.78)	28.000	L.F.
202-02.09	REMOVAL OF PIPE (SIZE ,STA.) (48" HDPE, STR-5 STA. 14+59.80)	21.000	L.F.
203-01.13	ROAD & DRAINAGE EXCAVATION (STREAM	3,581.000	C.Y.

Contract ID CNX909 - JEFFERSON

Item No.	Description	Quantity	Units
	MITIGATION)		
203-03	BORROW EXCAVATION (UNCLASSIFIED)	6,084.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	1,464.000	C.Y.
203-06	WATER	10.000	M.G.
203-15.03	COMPACTED CLAY	435.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	67.000	C.Y.
209-03.34	STREAM MITIGATION-LOG VANES	215.000	L.F.
209-03.36	STREAM MITIGATION-STEP POOL	41.000	EACH
209-03.37	STREAM MITIGATION CROSS VANE STRUCTURE	88.000	EACH
209-03.38	STREAM MITIGATION -J -HOOK	98.000	EACH
209-03.40	STREAM MITIGATION - LOG RIFFLE	1,310.000	L.F.
209-03.41	STREAM MITIGATION - BOULDER RIFFLE	1,000.000	L.F.
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	1,780.000	L.F.
209-03.54	STREAM MITIGATION - CROSS VANE STRUCTURE W/STEP	58.000	EACH
209-03.62	STREAM MITIGATION - ROOT WAD	29.000	EACH
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	1,780.000	L.F.
209-03.68	STREAM MITIGATION – BOULDER TOE	255.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	132.000	EACH
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	18,840.000	L.F.
209-09.01	SANDBAGS	300.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	30.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	38.000	S.Y.
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (PUMP AROUND)	(1)	LS
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,067.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	100.000	TON
607-03.30	18" PIPE CULVERT	40.000	L.F.
607-09.30	48" PIPE CULVERT	120.000	L.F.
607-11.30	60" PIPE CULVERT	80.000	L.F.

Contract ID CNX909 - JEFFERSON

Item No.	Description	Quantity	Units
621-03.02	18" TEMPORARY DRAINAGE PIPE	180.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	30.000	L.F.
707-03.01	STOCK FENCE	22,250.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	66.000	EACH
707-06.05	REMOVAL OF FENCE (DESCRIPTION) (EXISTING CATTLE FENCE WITHIN EASEMENT BNDRY)	(1)	LS
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,609.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	668.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	284.000	TON
709-05.81	ROCK RIFFLES	(1)	LS
709-11.01	BOULDER RIP-RAP (SIZE) (2.5 FT X 2 FT X 1 FT)	15.000	C.Y.
709-11.02	BOULDER RIP-RAP (SIZE) (3 FT X 2.5 FT X 1 FT)	13.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	80.000	S.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,735.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	282.000	S.Y.
795-02.04	6IN HDPE WATER LINE	800.000	L.F.
795-02.05	8IN HDPE WATER LINE	1,100.000	L.F.
795-13.02	HDPE FITTINGS	170.000	LB.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1,146.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	793.000	UNIT
801-02.15	FERTILIZER	7.000	TON
801-03	WATER (SEEDING & SODDING)	10.000	M.G.
801-09	AGRICULTURAL LIME	19.000	TON
802-02.30	CUTTINGS: SALIX NIGRA (18IN-24IN LENGTH)	2,761.000	EACH
802-02.32	CUTTINGS: CORNUS AMOMUM (18IN-24IN)	2,761.000	EACH
802-02.33	CUTTINGS: SAMBUCUS CANADENSIS (18IN-24IN)	2,761.000	EACH
802-02.37	CUTTINGS: ALNUS SERRULATA (18IN-24IN)	2,761.000	EACH
802-12.14	DIOSPYROS VIRGINIANA (PERSIMMON SEEDLNG)	1,122.000	EACH

Contract ID CNX909 - JEFFERSON

Item No.	Description	Quantity	Units
802-12.17	B.R.) JUGLANS NIGRA (BLACK WALNUT SEEDLNG B.R.)	1,683.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	1,683.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	1,683.000	EACH
802-12.40	SALIX NIGRA (BLACK WILLOW SEEDLNG B.R.)	1,122.000	EACH
802-12.45	CARPINUS CAROLINIANA (AMERICAN HORNBEAM SEEDLING B.R.)	1,683.000	EACH
802-12.46	QUERCUS SHUMARDII (SHUMARD OAK SEEDLING B.R.)	1,122.000	EACH
802-12.53	QUERCUS PAGODA (CHERRYBARK OAK SEEDLING B.R.)	1,122.000	EACH
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	11,375.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX901 - SHELBY

Contract ID: CNX901

Letting Date: August 18, 2023 10:00 AM

Projects: 79947-4111-04

NA

Counties: SHELBY

District:

DBE Goal Percent:

Description: The repair of the bridge on Shady Grove Road over I-240 (L.M. 1.48).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	200.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	146.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	935.000	S.Y.
604-03.01	CLASS A CONCRETE (BRIDGES)	1.000	C.Y.
604-03.60	BRIDGE JOINT SEISMIC MODIFICATION (DESCRIPTION) (LONGITUDINAL)	38.000	EACH
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	300.000	S.Y.
604-10.05	CONCRETE	50.000	S.F.
604-10.09	CONCRETE	66.000	C.Y.
604-10.13	CONCRETE SLAB REMOVAL	(1)	LS
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.18	REINFORCING STEEL (REPAIRS)	15,344.000	LB.
604-10.26	BRACING	12.000	EACH
604-10.42	CONCRETE REPAIRS	300.000	C.F.
604-10.46	EXPANSION JOINT REPAIRS (TYPE G)	81.000	L.F.
604-10.54	CONCRETE REPAIRS	50.000	S.F.
604-10.83	COMPOSITE FIBER ENCASMENT	950.000	S.F.
604-10.90	MISCELLANEOUS BRIDGE ITEMS	(1)	LS
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	96.000	EACH

Contract ID CNX901 - SHELBY

Item No.	Description	Quantity	Units
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	2,178.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	218.000	EACH
712-06	SIGNS (CONSTRUCTION)	991.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	240.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	7.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	5,700.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	5.000	EACH
714-02.02	ENCASED CONDUIT (2" PVC, SCHEDULE 40)	65.000	L.F.
714-06.07	CABLE (1/C # 2 AWG)	195.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.400	L.M.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
803-01	SODDING (NEW SOD)	300.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX292 - ANDERSON , BLOUNT, ETC.

Contract ID: CNX292

Letting Date: August 18, 2023 10:00 AM

Projects: R1BVAR-M3-030

n/a

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER, GREENE,
HAMBLEN, HANCOCK, JEFFERSON,
JOHNSON, KNOX, LOUDON, MONROE,
MORGAN, ROANE, SCOTT, SEVIER,
SULLIVAN, UNICOI, UNION, WASHINGTON

District:

DBE Goal Percent:

Description: The on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	250.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	3,400.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	215.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	40.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	50.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	150.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	300.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	1,600.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	40.000	EACH

Contract ID CNX292 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	2,000.000	L.F.
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	3.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	5.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	20.000	EACH

() Item will be bid as lump sum.

Contract ID CNX315 - BEDFORD

Contract ID: CNX315

Letting Date: August 18, 2023 10:00 AM

Projects: 02ACOU-S3-002

N/A

Counties: BEDFORD

District:

DBE Goal Percent:

Description: The grading, drainage, and paving on a S.I.A. route serving Project Cardinal.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	2,742.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	281.000	C.Y.
203-06	WATER	14.000	M.G.
209-08.08	ENHANCED ROCK CHECK DAM	7.000	EACH
209-09.40	CURB INLET PROTECTION (TYPE 1)	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,688.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	100.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	238.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	363.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	609.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	10.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	20.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,701.000	S.Y.
607-03.30	18" PIPE CULVERT	122.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	243.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	6.000	EACH

Contract ID CNX315 - BEDFORD

Item No.	Description	Quantity	Units
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-09.02	REWORK CATCHBASIN	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	60.000	L.F.
702-03	CONCRETE COMBINED CURB & GUTTER	7.500	C.Y.
703-02	CEMENT CONCRETE DITCH PAVING (REINFORCED)	3.000	C.Y.
706-01	GUARDRAIL REMOVED	105.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	1,316.000	L.F.
710-05	LATERAL UNDERDRAIN	20.000	L.F.
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	75.000	EACH
712-06	SIGNS (CONSTRUCTION)	288.000	S.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	1.000	L.F.
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R2-1)	2.000	EACH
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	39.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	148.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	3,020.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	23.000	UNIT
801-03	WATER (SEEDING & SODDING)	20.000	M.G.
803-01	SODDING (NEW SOD)	1,688.000	S.Y.
791-03.01	<2IN HDPE GAS MAIN	110.000	L.F.
791-03.02	2IN HDPE GAS MAIN	120.000	L.F.
791-03.04	4IN HDPE GAS MAIN	1,000.000	L.F.
791-06.52	4IN PE HOT TAP CONNECTION	2.000	EACH

Contract ID CNX315 - BEDFORD

Item No.	Description	Quantity	Units
791-07.02	4IN PE GAS VALVE ASSEMBLY	6.000	EACH
795-01.06	8IN DIP SLIP JOINT WATER LINE	810.000	L.F.
795-01.08	10IN DIP SLIP JOINT WATER LINE	300.000	L.F.
795-05.65	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	60.000	L.F.
795-05.67	BORE/JACK 20IN STEEL CASING PIPE-UNCON.	150.000	L.F.
795-08.04	6IN GATE VALVE ASSEMBLY	3.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	5.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.08	12IN BUTTERFLY VALVE ASSEMBLY	1.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	1.000	EACH
795-09.14	3/4IN HDPE SERVICE PIPE	200.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	2.000	EACH
795-13.01	DI FITTINGS	750.000	LB.

() Item will be bid as lump sum.

Contract ID CNX313 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNX313

Letting Date: August 18, 2023 10:00 AM

Projects: R3BVAR-M3-038

NA

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HUMPHREYS,
MARSHALL, MAURY, ROBERTSON,
RUTHERFORD, SMITH, SUMNER,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The replacement of flat sheet signs on various Interstate and State Routes.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	50.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	40.000	EACH
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	200.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	125.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	25,000.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	132,000.000	LB.
713-11.21	P POST SLIP BASE	500.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	2,500.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	28,920.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	100.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	100.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PER/KNOCKOUT)	40.000	EACH

() Item will be bid as lump sum.

Contract ID CNX304 - BENTON

Contract ID: CNX304

Letting Date: August 18, 2023 10:00 AM

Projects: 03945-3494-94

HSIP-300(35)

Counties: BENTON

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	564.000	L.F.
713-02.34	DELINEATORS (ALL)	60.000	EACH
713-11.01	"U" SECTION STEEL POSTS	1,954.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,272.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	884.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	975.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	1,426.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	8.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	280.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	60.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	177.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	21.000	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	133.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	35.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX273 - BENTON , CROCKETT, ETC.

Contract ID: CNX273

Letting Date: August 18, 2023 10:00 AM

Projects: R4BVAR-M3-038

NA

Counties: BENTON, CROCKETT, DECATUR, DYER,
FAYETTE, HAYWOOD, HENDERSON,
MADISON, OBION, SHELBY, TIPTON

District:

DBE Goal Percent:

Description: The on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	50.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	2,300.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	60.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	10.000	EACH
705-80.09	DRIVEN SOCKETED LINE POST W/ALL ACCESSORIES	150.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	10.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	10.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	75.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	700.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	20.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	100.000	L.F.

Contract ID CNX273 - BENTON , CROCKETT, ETC.

Item No.	Description	Quantity	Units
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	5.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	35.000	EACH

() Item will be bid as lump sum.

Contract ID CNX308 - BLOUNT

Contract ID: CNX308

Letting Date: August 18, 2023 10:00 AM

Projects: 05005-3249-14

NH-115(65)

Counties: BLOUNT

District:

DBE Goal Percent: 9.50

Description: The grading, drainage, construction of bridges, retaining walls and paving on U.S. 129 (S.R. 115) from proposed interchange at Tyson Boulevard to existing U.S. 129 (S.R. 115) at South Singleton Station Road.

Contract Time: DT - 10/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	7,180.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BOX CULVERT & WINGS, STA. 249+83 LT)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,332,476.000	C.Y.
203-01.13	ROAD & DRAINAGE EXCAVATION (STREAM MITIGATION)	125,571.000	C.Y.
203-02.02	BORROW EXCAVATION (GRADED SOLID ROCK)	136,200.000	C.Y.
203-03.10	SELECT GRANULAR MATERIAL	1,100.000	TON
203-03.51	BORROW EXCAVATION (UNCLASSIFIED)	131,076.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	6,468.000	C.Y.
203-06	WATER	3,547.000	M.G.
203-20.01	CHANNEL SUBSTRATE	3,742.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	1,374.500	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	331.000	C.Y.
209-02.03	8" TEMPORARY SLOPE DRAIN	450.000	L.F.
209-02.04	10" TEMPORARY SLOPE DRAIN	374.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
209-02.05	12" TEMPORARY SLOPE DRAIN	775.000	L.F.
209-03.34	STREAM MITIGATION-LOG VANES	225.000	L.F.
209-03.35	STREAM MITIGATION-LOG DROP STRUCTURE	670.000	L.F.
209-03.36	STREAM MITIGATION-STEP POOL	57.000	EACH
209-03.37	STREAM MITIGATION CROSS VANE STRUCTURE	26.000	EACH
209-03.40	STREAM MITIGATION - LOG RIFFLE	742.000	L.F.
209-03.41	STREAM MITIGATION - BOULDER RIFFLE	354.000	L.F.
209-03.54	STREAM MITIGATION - CROSS VANE STRUCTURE W/STEP	5.000	EACH
209-03.64	STREAM MITIGATION - FELLED TREE (SIZE) (SEE PLANS)	4.000	EACH
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	1,037.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	153.000	EACH
209-05	SEDIMENT REMOVAL	5,711.592	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,761.000	L.F.
209-08.07	ROCK CHECK DAM	582.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	111.000	EACH
209-09.01	SANDBAGS	5,520.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	12.000	EACH
209-09.24	JUTE MESH FABRIC	14,644.000	S.Y.
209-09.43	CURB INLET PROTECTION (TYPE 4)	181.000	EACH
209-10.20	TEMPORARY SEDIMENT TRAP	100.000	C.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	2.000	EACH
209-40.32	CATCH BASIN PROTECTION (TYPE C)	10.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	34.000	EACH
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (PUMP AROUND)	(1)	LS
209-65.03	TEMPORARY DIVERSION CHANNEL	1,654.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	3,198.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	256,303.080	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	328.870	TON

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
303-10.01	MINERAL AGGREGATE (SIZE 57)	3,362.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	3,618.252	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	9,721.261	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	13,341.732	TON
307-01.22	ASP. CONC. MIX(PG76-22) (BPMB-HM) GR. A-S	418.087	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	19,614.149	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	10,924.955	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	614.187	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	986.049	TON
313-03	TREATED PERMEABLE BASE	52,630.185	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	304.165	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	174.485	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	6,938.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,175.491	TON
411-01.10	ACS MIX(PG64-22) GRADING D	5,057.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	6,010.796	TON
411-03.10	ACS MIX(PG76-22) GRADING D	1,416.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	7.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	2,136.487	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	47,340.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	72.346	C.Y.
604-01.20	BOX TUBE SAFETY RAIL	2,550.000	L.F.
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	10,677.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	1,765,402.000	LB.
604-03.07	CLASS A CONCRETE (DESCRIPTION) (BARRIER FOOTING)	24.000	C.Y.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
604-07.01	RETAINING WALL (DESCRIPTION) (RETAINING WALL 1)	1,179.000	S.F.
604-07.02	RETAINING WALL (DESCRIPTION) (RETAINING WALL 2)	2,989.000	S.F.
604-07.03	RETAINING WALL (DESCRIPTION) (RETAINING WALL 3)	8,511.000	S.F.
604-07.04	RETAINING WALL (DESCRIPTION) (RETAINING WALL 4)	11,523.000	S.F.
604-07.05	RETAINING WALL (DESCRIPTION) (RETAINING WALL 5)	4,380.000	S.F.
604-07.06	RETAINING WALL (DESCRIPTION) (RETAINING WALL 6)	3,399.000	S.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	5,747.000	L.F.
607-03.04	18" CONCRETE PIPE CULVERT (CLASS V)	312.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	2,742.000	L.F.
607-05.05	24" CONCRETE PIPE CULVERT(CLASS IV)JACKED-IN-PLACE	46.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	859.000	L.F.
607-06.04	30" CONCRETE PIPE CULVERT (CLASS V)	5.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	494.000	L.F.
607-07.03	36" CONCRETE PIPE CULVERT (CLASS IV)	177.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	254.000	L.F.
607-09.04	48" CONCRETE PIPE CULVERT (CLASS V)	555.000	L.F.
607-10.02	54" CONCRETE PIPE CULVERT (CLASS III)	273.000	L.F.
607-10.04	54" CONCRETE PIPE CULVERT (CLASS V)	164.000	L.F.
607-11.03	60" CONCRETE PIPE CULVERT (CLASS III)	109.000	L.F.
607-13.03	72" CONCRETE PIPE CULVERT (CLASS III)	70.000	L.F.
607-16.10	68"X 43" HORIZONTAL OVAL CONCRETE PIPE CULVERT	30.000	L.F.
607-18.01	CULVERT INSPECTION WITH CAMERA	500.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	154.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	146.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
611-01.03	MANHOLES, > 8' - 12' DEPTH	3.000	EACH
611-01.04	MANHOLES, > 12' - 16' DEPTH	2.000	EACH
611-02.10	JUNCTION BOX, TYPE 1	2.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	2.000	EACH
611-02.13	JUNCTION BOX, TYPE 4	2.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	178.220	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	7,897.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
611-07.32	24IN ENDWALL (SIDE DRAIN)	4.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	6.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	11.000	EACH
611-07.61	30IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.62	30IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.64	36IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.70	48IN ENDWALL (CROSS DRAIN) 4:1	3.000	EACH
611-07.73	18IN ENDWALL (MEDIAN DRAIN)	2.000	EACH
611-10.02	CATCH BASINS, TYPE 10, > 4' - 8' DEPTH	3.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	9.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	26.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	4.000	EACH
611-12.05	CATCH BASINS, TYPE 12, > 16' - 20' DEPTH	1.000	EACH
611-12.06	CATCH BASINS, TYPE 12, > 20' - 24' DEPTH	1.000	EACH
611-12.08	CATCH BASINS, TYPE 12, >(' - ' DEPTH) (28' -32 ' DEPTH)	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	8.000	EACH
611-14.03	CATCH BASINS, TYPE 14, > 8' - 12' DEPTH	5.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	16.000	EACH
611-39.03	CATCH BASINS, TYPE 39, > 8' - 12' DEPTH	1.000	EACH
611-39.04	CATCH BASINS, TYPE 39, > 12' - 16' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	6.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	9.000	EACH
611-42.03	CATCH BASINS, TYPE 42, > 8' - 12' DEPTH	1.000	EACH
611-42.05	CATCH BASINS, TYPE 42, > 16' - 20' DEPTH	1.000	EACH
611-45.02	CATCH BASINS, TYPE 45, > 4' - 8' DEPTH	3.000	EACH
611-45.03	CATCH BASINS, TYPE 45, > 8' - 12' DEPTH	4.000	EACH
611-45.04	CATCH BASINS, TYPE 45, > 12' - 16' DEPTH	1.000	EACH
611-51.02	CATCH BASINS, TYPE 51, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	427.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	529.000	L.F.
621-03.06	42" TEMPORARY DRAINAGE PIPE	366.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	5,102.000	S.F.
701-02.03	CONCRETE CURB RAMP	909.000	S.F.
702-01	CONCRETE CURB	15.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	642.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	99.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	12,197.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	10.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	7.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	5.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	6.000	EACH
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	4.000	EACH
707-03.01	STOCK FENCE	26,818.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	173.000	EACH
707-04	WATER CROSSING	40.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	5,014.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	148.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	3,672.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	12,228.646	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	24,067.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	4,552.352	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	50,978.590	L.F.
710-05	LATERAL UNDERDRAIN	6,006.259	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	32.000	EACH
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	6.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	73.000	EACH
710-06.14	LATERAL UNDERDRAIN ENDWALL (5:1)	7.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	83.000	EACH
711-05.69	36IN SINGLE SLOPE CONCRETE BARRIER WALL	2,328.000	L.F.
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	316.000	L.F.
711-05.77	FLARED S/S CONCRETE MEDIAN BARRIER WALL	1,517.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	4,984.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	20.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	390.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	252.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,358.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	1,892.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
712-09.21	REMOVABLE WET REFLECTIVE PAVEMENT MARKING TAPE	4,000.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	7.400	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	2,356.000	LB.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
713-02.14	FLEXIBLE DELINEATOR (WHITE)	75.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	53.000	EACH
713-02.30	FLEXIBLE TUBULAR DELINEATOR	34.000	EACH
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	5,079.000	LB.
713-09.01	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 61')	1.000	EACH
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,734.000	LB.
713-11.21	P POST SLIP BASE	25.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	298.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	600.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	920.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	56.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	4.000	EACH
713-15.35	METAL BARRICADE (TYPE III)	34.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
713-16.20	SIGNS (DESCRIPTION) (CONSTRUCTION)	4.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	2.000	EACH
714-02.02	ENCASED CONDUIT (2" PVC, SCHEDULE 40)	3,643.000	L.F.
714-03	JACKED OR BORED CONDUIT	903.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	41,186.000	L.F.
714-04.01	CONDUIT (STRUCTURES - 1" RGS)	81.000	L.F.
714-05.04	PULL BOXES (TYPE C)	76.000	EACH
714-06.03	CABLE (1/C # 10 AWG)	243.000	L.F.
714-06.04	CABLE (1/C # 8 AWG)	32,760.000	L.F.
714-06.05	CABLE (1/C # 6 AWG)	252,740.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (ALUMINUM 45' MH OFFSET)	121.000	EACH
714-08.10	LIGHT STANDARDS (DESCRIPTION) (PEDESTRIAN 18' MH)	14.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
714-08.12	LIGHT STANDARDS (DESCRIPTION) (ALUMINUM 35' MH 8' ARM)	52.000	EACH
714-08.28	FOUNDATION FOR LIGHT STANDARDS - ROADWAY (DESCRIPTION) (SEE PLANS)	173.000	EACH
714-09.47	LED LUMINAIRES (DESCRIPTION) (206 WATT - OFFSET)	125.000	EACH
714-09.48	LED LUMINAIRES (DESCRIPTION) (129 WATT - ROADWAY)	54.000	EACH
714-09.49	LED LUMINAIRES (DESCRIPTION) (49 WATT - PEDESTRIAN)	14.000	EACH
714-09.83	LED LUMINAIRES-UNDERPASS (DESCRIPTION) (72 WATT)	4.000	EACH
714-12.01	CONTROL CENTER (NO. 1)	(1)	LS
714-12.02	CONTROL CENTER (NO. 2)	(1)	LS
714-12.03	CONTROL CENTER (NO. 3)	(1)	LS
714-12.04	CONTROL CENTER (NO. 4)	(1)	LS
714-12.05	CONTROL CENTER (NO. 5)	(1)	LS
714-12.06	CONTROL CENTER (NO. 6)	(1)	LS
714-12.07	CONTROL CENTER (NO. 7)	(1)	LS
714-12.08	CONTROL CENTER (NO. 8)	(1)	LS
714-12.09	CONTROL CENTER (_____) (NO. 9)	(1)	LS
714-14.03	MASTARM (DESCRIPTION) (8' FOR SIGNAL)	2.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 01)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 02)	(1)	LS
714-25.03	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 03)	(1)	LS
714-25.04	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 04)	(1)	LS
714-25.05	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 05)	(1)	LS
714-25.06	ELECTRICAL CONNECTION (APPALACHIAN ENERGY COOPERATIVE)	(1)	LS
714-25.07	ELECTRICAL CONNECTION (AMEREICAN ELECTRIC	(1)	LS

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
714-25.08	POWER) ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 08)	(1)	LS
714-25.09	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 09)	1.000	EACH
716-01.11	RAISED PAVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	588.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	276.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	92.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,666.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	233.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	25.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,254.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	670.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	124.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	5.000	EACH
716-03.09	PLASTIC WORD PAVEMENT MARKING () (YIELD)	3.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	90.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	8.000	EACH
716-04.24	PLASTIC PAVEMENT MARKING (FISH-HOOKS WITH 2 ARROWS)	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	6.000	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	22,897.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	12,980.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PAVMT MRKNG (6IN LINE)	6.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PAVMT MRKNG (8IN BARRIER LINE)	4,276.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	2,032.000	L.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	7.000	L.M.
716-13.03	SPRAY THERMO PVMT MRKNG (60 mil) (8IN BARRIER LINE)	2,548.000	L.F.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	37.000	L.F.
717-01	MOBILIZATION	(1)	LS
725-20.44	PULL BOX (TYPE D)	20.000	EACH
725-20.45	PULL BOX (TYPE E)	7.000	EACH
725-22.24	CONDUIT BANK (TYPE 4)	9,095.000	L.F.
725-22.34	CONDUIT BANK BORED (TYPE 4)	4,585.000	L.F.
725-23.01	ITS CABLE MARKER	38.000	EACH
725-24.31	SPARE PARTS	(1)	LS
725-24.55	AS-BUILT PLANS	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	5.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	3.000	EACH
730-02.14	SIGNAL HEAD ASSEMBLY (140 A1 WITH BACKPLATE)	1.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	4.000	EACH
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2 POLE MOUNTED)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	7.000	EACH
730-03.23	INSTALL PULL BOX (FIBER OPTIC-TYPE A)	1.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	320.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	3,685.000	L.F.
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	230.000	L.F.
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	602.000	L.F.
730-13.15	VEHICLE DETECTOR (TWO 360-DEGREE CAMERA)	1.000	EACH
730-15.07	CABINET (DESCRIPTION) (WITH BATTERY BACKUP)	1.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (TYPE A 8 FEET)	1.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	4.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	2.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	1.000	EACH
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	8,067.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	9,367.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	171,417.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	16,125.000	L.F.
797-11.46	CONCRETE CAP	26.337	C.Y.
801-01.06	SEEDING (SPECIAL MIXTURE)	1,680.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	5,412.150	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	395.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	5,412.150	UNIT
801-03	WATER (SEEDING & SODDING)	1,121.930	M.G.
802-02.40	CUTTINGS: SALIX NIGRA (24-48IN LENGTH)	3,218.000	EACH
802-02.42	CUTTINGS: CORNUS AMOMUM (24-48IN)	3,218.000	EACH
802-02.47	CUTTINGS: ALNUS SERRULATA (24-48IN)	3,218.000	EACH
802-11.01	ACER NEGUNDO (BOX ELDER 2-5FT CNTNR GRWN)	1,298.000	EACH
802-11.02	ACER RUBRUM (RED MAPLE 2-5FT CNTNR GRWN)	6,789.000	EACH
802-11.07	BETULA NIGRA (RIVER BIRCH 2-5FT CNTNR GRWN)	1,614.000	EACH
802-11.10	CARYA TOMENTOSA (MOCKERNUT HICKORY 2-5FT CNTNR GRWN)	5,175.000	EACH
802-11.11	CERCIS CANADENSIS (REDBUD 2-5FT CNTNR GRWN)	6,473.000	EACH
802-11.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR 2-5FT CNTNR GRWN)	5,175.000	EACH
802-11.21	NYSSA SYLVATICA (BLCKGUM 2-5FT CNTNR GRWN)	1,614.000	EACH
802-11.26	PLATANUS OCCIDENTALIS (SYCAMORE 2-5FT CNTNR GRWN)	1,298.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
802-11.30	QUERCUS BICOLOR (SWAMP WHITE OAK 2-5FT CNTNR GRWN)	1,298.000	EACH
802-11.37	QUERCUS PALUSTRIS (PIN OAK 2-5FT CNTNR GRWN)	316.000	EACH
802-11.40	SALIX NIGRA (BLACK WILLOW 2-5FT CNTNR GRWN)	316.000	EACH
802-11.44	ULMUS AMERICANA (AMERICAN ELM 2-5FT CNTNR GRWN)	6,473.000	EACH
802-11.59	PRUNUS AMERICANA (AMERICAN PLUM 2-5FT CNTNR GRWN)	1,298.000	EACH
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	916.000	EACH
802-12.02	ACER RUBRUM (RED MAPLE SEEDLNG B.R.)	916.000	EACH
802-12.07	BETULA NIGRA (RIVER BIRCH SEEDLNG B.R.)	916.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	916.000	EACH
802-13.03	CEPHALANTHUS OCCIDENTALIS (BUTTONBUSH 2-5FT CNTNR GRWN)	316.000	EACH
802-13.04	CORNUS AMOMUM (SILKY DOGWOOD 2-5FT CNTNR GRWN)	316.000	EACH
802-13.28	AMORPHA FRUTICOSA (INDIGOBUSH 2-5 FT CNTNR GRWN)	316.000	EACH
803-01	SODDING (NEW SOD)	3,636.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	21,183.000	S.Y.
805-01.03	TURF REINFORCEMENT MAT (CLASS III)	5,055.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	548,691.000	S.Y.
806-02.03	PROJECT MOWING	9.000	CYCL
204-02.01	DRY EXCAVATION (BRIDGES)	3,600.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	230.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	522.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	216.000	L.F.
204-05.01	CORE DRILLING AND SAMPLING	290.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 1 - STA. 47+85.00)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 2 - STA. 49+05.00)	(1)	LS

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
303-01.02	GRANULAR BACKFILL (BRIDGES)	353.000	TON
602-04.01	STEEL STRUCTURES (LOCATION & DESCRIPTION) (WELDED PLATE GIRDER, 68" WEB)	(1)	LS
602-10.60	BEARING DEVICE (DESCRIPTION) (REINFORCED ELASTOMERIC BEARING DEVICE @ ABUTMENTS)	10.000	EACH
604-02.03	EPOXY COATED REINFORCING STEEL	1,878,417.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	4,305.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	1,125,634.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	1,361.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	2,126.000	C.Y.
604-03.32	CLASS DS CONCRETE	3,155.000	C.Y.
604-03.74	CLASS X CONCRETE	728.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	43,225.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	28.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	18,205.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (MODULAR, 8" MOVEMENT)	84.000	L.F.
604-11.02	EXPANSION DEVICE (DESCRIPTION) (STRIP-SEAL, ABUTMENTS)	84.000	L.F.
606-02.03	STEEL PILES (10 INCH)	4,718.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	166.000	EACH
606-03.03	STEEL PILES (12 INCH)	5,566.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	201.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE TYPE 2)	8.000	EACH
615-01.11	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-63)	4,149.000	L.F.
615-01.12	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-72)	8,290.000	L.F.
615-01.32	PRESTRESSED CONCRETE WIDE BULB TEE BEAM (WBT-66)	2,052.000	L.F.
620-05	CONCRETE PARAPET WITH STRUCTURAL TUBING	281.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	7,482.000	L.F.
625-01.11	CAMERA INSPECTION - DRILLED SHAFT	6.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
	(UNDERWATER)		
625-02.01	DRILLED SHAFT-SOIL (DIA.) (8'-6" DIA.)	92.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (8'-0" DIA.)	72.000	V.F.
625-02.14	DRILLED SHAFT-ROCK (DIA.) (8'-6" DIA.)	6.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (8'-6" INSIDE DIAMETER)	98.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	340.000	C.Y.
625-02.43	CONCRETE CORING	182.000	V.F.
625-02.44	DRILLED SHAFT REINFORCING STEEL	85,499.000	LB.
709-04	REINFORCED CONCRETE SLOPE PAVEMENT	769.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	1,082.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	228.000	L.F.
714-01.01	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 1)	(1)	LS
714-01.02	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 2)	(1)	LS
714-01.03	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 3)	(1)	LS
714-01.04	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 4)	(1)	LS
714-01.05	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 5)	(1)	LS
714-01.06	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 6)	(1)	LS
908-21.01	BEARINGS (DESCRIPTION) (AT ABUTMENTS)	8.000	EACH
908-21.02	BEARINGS (DESCRIPTION) (AT BENTS)	24.000	EACH
790-03.02	POLE 40FT CLASS 3 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	1.000	EACH
790-04.07	POLE 45FT CLASS 2 METAL	1.000	EACH
790-05.05	POLE 50FT CLASS 1 METAL	11.000	EACH
790-05.06	POLE 50FT CLASS 2 METAL	1.000	EACH
790-06.05	POLE 55 FT CLASS 1 METAL	7.000	EACH
790-06.07	POLE 55FT CLASS H1 METAL	2.000	EACH

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
790-07.05	POLE 60FT CLASS 1 METAL	4.000	EACH
790-07.07	POLE 60FT CLASS H1 METAL	2.000	EACH
790-09.13	POLE 70FT CLASS 1 METAL	2.000	EACH
790-20.01	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (75FT CLASS 1 METAL)	1.000	EACH
790-20.02	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (35FT CLASS 5 METAL)	1.000	EACH
790-20.03	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (40FT CLASS 4 METAL)	2.000	EACH
790-21.08	1PH DEADEND 15KV	2.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	1.000	EACH
790-21.11	1PH CROSSARM DEADEND 15KV	1.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	8.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	5.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	7.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	8.000	EACH
790-25.30	3PH CROSSARM DBL 10FT LRG COND 15KV	8.000	EACH
790-31.02	SERVICE ASSEMBLY-POLE TYPE	3.000	EACH
790-31.11	SERVICE CONDUCTOR 2 AL TRIPLEX	284.000	L.F.
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	29.000	EACH
790-32.06	DOWN GUY - INSULATED	33.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	8.000	EACH
790-32.23	GUY GUARD	32.000	EACH
790-33.31	SCREW TYPE ANCHOR 23,000LB (F1-5D-P)	20.000	EACH
790-33.32	SCREW TYPE ANCHOR 36,000LB (F1-6T-P)	12.000	EACH
790-36.06	TRANSFER LIGHT	1.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	3.000	EACH
790-36.12	TRANSFER EXISTING 3PH TRANSFORMER/RECLOSER	1.000	EACH
790-40.42	OH COND 336.4 19 AAC TULIP	5,683.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	11,902.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
790-40.49	OH COND 795 37 AAC ARBUTUS	5,142.000	L.F.
790-41.03	UG PRI COND 1/0 AL 15KV	897.000	L.F.
790-41.06	UG PRI COND 4/0 AL 15KV	4,665.000	L.F.
790-42.03	CONDUIT - ROLLED PLASTIC ___IN DIA (2IN)	1,452.000	L.F.
790-42.08	2IN DIA PVC PIPE	1,196.000	L.F.
790-42.09	3IN DIA PVC PIPE	4,768.000	L.F.
790-42.19	4 DUCT BANK @ 36IN-48IN DEPTH	1,396.000	L.F.
790-42.26	___ DUCT BANK @ ___IN-___IN DEPTH (48-52)	95.000	L.F.
790-43.01	LOADBREAK ELBOW 200A 15KV	45.000	EACH
790-43.06	LOADBREAK JUNCTION 4 PT 200A 15KV	21.000	EACH
790-43.08	ELBOW ARRESTER 200A 15KV	21.000	EACH
790-43.10	SPLICE 200A 15KV	21.000	EACH
790-43.34	UG GROUND ROD ASSEMBLY	7.000	EACH
790-43.47	PRIMARY PULLBOX	7.000	EACH
790-43.57	3PH PRIMARY RISER W/ 3IN CONDUIT	3.000	EACH
790-46.03	1PH TRANSFORMER CONV W/XARM MTD FUSE & LA	1.000	EACH
790-60.01	1PH FUSE CUTOUT XARM MOUNT 15KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	3.000	EACH
790-69.11	GROUND-GROUND ROD FOR ST POLE	29.000	EACH
790-69.22	POLE TOP PIN	8.000	EACH
790-69.32	ARM PIN	40.000	EACH
790-69.41	EXTENSION LINK - EPOXY -8FT	8.000	EACH
790-98.01	REMOVE WIRE	35,179.000	L.F.
790-98.02	REMOVE POLES	48.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	382.000	EACH
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-03.02	2IN HDPE GAS MAIN	220.000	L.F.
791-03.05	6IN HDPE GAS MAIN	8,680.000	L.F.
791-04.05	HDD 6IN PE PIPE - UNCONSOLIDATED	2,175.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
791-06.02	CONNECT TO 2IN EX. PE MAIN	5.000	EACH
791-06.04	CONNECT TO 6IN EX. PE MAIN	3.000	EACH
791-07.03	6IN PE GAS VALVE ASSEMBLY	6.000	EACH
793-01.12	POLE 40FT CLASS 4 WOOD	1.000	EACH
793-01.41	ANCHOR 1IN	21.000	EACH
793-11.20	HANDHOLE 30INX48IN	1.000	EACH
793-12.01	DIG SPLICE PIT 80 C.F.	4.000	EACH
793-13.09	2IN SCHEDULE 40 PVC	85.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	850.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	33.000	EACH
793-98.05	RETIRE BURIED FACILITIES IN PLACE	175.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	165.000	L.F.
795-01.06	8IN DIP SLIP JOINT WATER LINE	3,825.000	L.F.
795-01.10	12IN DIP SLIP JOINT WATER LINE	2,177.000	L.F.
795-05.63	BORE/JACK 12IN STEEL CASING PIPE-UNCON.	25.000	L.F.
795-05.65	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	180.000	L.F.
795-05.68	BORE/JACK 24IN STEEL CASING PIPE-UNCON.	425.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	4.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	3.000	EACH
795-06.06	CONNECT TO 10IN WATER LINE	2.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	7.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	2.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	1.000	EACH
795-06.35	CUT AND CAP SERVICE LINE	2.000	EACH
795-06.36	CUT & CAP 10IN WATER LINE	2.000	EACH
795-06.37	CUT AND CAP 12IN WATER LINE	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	11.000	EACH
795-08.08	12IN BUTTERFLY VALVE ASSEMBLY	6.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	250.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
795-10.03	1IN AUTO AIR RELEASE VALVE ASSEMBLY	4.000	EACH
795-10.05	2IN AUTO AIR RELEASE VALVE ASSEMBLY	3.000	EACH
795-10.06	2IN MANUAL AIR RELEASE VALVE ASSEMBLY	2.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	3.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	1,000.000	L.F.
795-12.01	REMOVE FIRE HYDRANT	4.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-12.08	REMOVE WATER METER	9.000	EACH
795-12.11	ASBESTOS REMOVAL	2,480.000	L.F.
795-13.01	DI FITTINGS	15,000.000	LB.
795-14.08	RESTORE ASPHALT	200.000	S.Y.
795-14.09	RESTORE CONCRETE	200.000	S.Y.
795-14.10	RESTORE GRAVEL	200.000	S.Y.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	390.000	L.F.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	4.000	EACH
797-02.10	12IN HDPE FORCE MAIN	363.000	L.F.
797-05.01	8IN DIP GRAVITY SEWER 0FT-6FT DEPTH	490.000	L.F.
797-05.02	8IN DIP GRAVITY SEWER 6FT-12FT DEPTH	1,545.000	L.F.
797-05.03	8IN DIP GRAVITY SEWER 12FT-18FT DEPTH	1,133.000	L.F.
797-05.06	10IN DIP GRAVITY SEWER 6FT-12FT DEPTH	2,296.000	L.F.
797-05.07	10IN DIP GRAVITY SEWER 12FT-18FT DEPTH	828.000	L.F.
797-05.08	10IN DIP GRAVITY SEWER >18FT DEPTH	199.000	L.F.
797-05.10	12IN DIP GRAVITY SEWER 6FT-12FT DEPTH	314.000	L.F.
797-05.64	15IN PVC GRAVITY SEWER 6FT-12FT DEPTH	4,649.000	L.F.
797-05.65	15IN PVC GRAVITY SEWER 12FT-18FT DEPTH	1,425.000	L.F.
797-06.64	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	325.000	L.F.
797-06.66	BORE/JACK 20IN STEEL CASING PIPE-UNCON.	575.000	L.F.
797-06.67	BORE/JACK 24IN STEEL CASING PIPE-UNCON.	215.000	L.F.
797-06.71	BORE/JACK __IN STEEL CASING PIPE-UNCON. (30)	2,425.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
797-06.90	OPEN CUT 16IN STEEL CASING PIPE	125.000	L.F.
797-06.92	OPEN CUT 20IN STEEL CASING PIPE	100.000	L.F.
797-06.94	OPEN CUT 30IN STEEL CASING PIPE	100.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	4.000	EACH
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	5.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	8.000	EACH
797-07.05	48IN MANHOLE 10FT-12FT DEPTH	19.000	EACH
797-07.06	48IN MANHOLE 12FT-14FT DEPTH	12.000	EACH
797-07.07	48IN MANHOLE 14FT-16FT DEPTH	6.000	EACH
797-07.08	48IN MANHOLE 16FT-20FT DEPTH	2.000	EACH
797-07.09	48IN MANHOLE 20FT-24FT DEPTH	1.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	3.000	EACH
797-07.80	REMOVE SEWER MANHOLE	24.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	375.000	L.F.
797-08.08	6IN CLEAN OUT ASSEMBLY	8.000	EACH
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	8.000	EACH
797-10.02	CONNECT 8IN SEWER TO EXIST. MANHOLE	1.000	EACH
797-10.03	CONNECT 10-18IN SEWER TO EXIST. MANHOLE	2.000	EACH
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	4.000	EACH
797-10.10	CONNECT EX.10-18IN SEWER TO NEW MANHOLE	5.000	EACH
797-11.25	RETIREIN PLACE 48IN MANHOLE	13.000	EACH
797-11.31	RETIREIN PLACE EXISTING SEWER 8IN-14IN	2,250.000	L.F.
797-11.32	RETIREIN PLACE EXISTING SEWER 15IN-24IN	2,651.000	L.F.
797-11.35	REMOVE EXISTING SEWER 8IN-14IN	2,550.000	L.F.
797-11.36	REMOVE EXISTING SEWER 15IN-24IN	3,540.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.40	RESTORE ASPHALT	300.000	S.Y.
797-11.42	RESTORE GRAVEL	300.000	S.Y.
798-05.03	FIBER OPTIC CABLE SPLICE	2.000	EACH
798-05.07	3/8IN HIGH STRENGTH STRAND	1,189.000	L.F.

Contract ID CNX308 - BLOUNT

Item No.	Description	Quantity	Units
798-05.08	TRUNK/FEEDER CABLE .565	361.000	L.F.
798-06.13	FIBER OPTIC CABLE (DESCRIPTION) (48F)	1,807.000	L.F.
798-06.48	FIBER STORAGE LOOP	2.000	EACH
798-09.02	REMOVE AERIAL CABLE/TERMINALS	1,452.000	L.F.
798-09.03	REMOVE POLES, GUYS, ANCHORS	16.000	EACH
798-10.10	POWER SUPPLY	1.000	EACH
798-11.31	POWER INSTALLED ANCHOR	2.000	EACH
798-11.41	DOWNGUY - WRAP TYPE	2.000	EACH
798-13.03	STRAND TANGENT ASSEMBLY	5.000	EACH
798-13.04	STRAND ANGLE ASSEMBLY	2.000	EACH
798-13.07	STRAND DOUBLE DEADEND ASSEMBLY	1.000	EACH
798-13.08	STRAND DEADEND ASSEMBLY	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX274 - BLOUNT & KNOX

Contract ID: CNX274

Letting Date: August 18, 2023 10:00 AM

Projects: 98100-3111-44

NH-I-098-1(20)

Counties: BLOUNT, KNOX

District:

DBE Goal Percent: 5.00

Description: The expansion of the Smartway Intelligent Transportation System (ITS) on I-140 from MM 2 in Knox County to U.S. 129 (S.R. 115, Alcoa Highway, Exit 11) in Blount County.

Contract Time: DT - 4/30/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
203-07	FURNISHING & SPREADING TOPSOIL	9.000	C.Y.
209-05	SEDIMENT REMOVAL	90.000	C.Y.
209-09.01	SANDBAGS	54.000	BAG
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	289.000	S.Y.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2.000	TON
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,000.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	5.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	1.000	EACH
711-05.01	REMOVAL & DISPOSAL OF CONCRETE MEDIAN BARRIER	69.500	L.F.
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	60.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	2,500.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	70.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	100.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	70.000	EACH

Contract ID CNX274 - BLOUNT & KNOX

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	850.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	6.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	2.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	7.000	EACH
714-08.11	LIGHT STANDARDS (DESCRIPTION) (35 FT POLE HEIGHT)	1.000	EACH
717-01	MOBILIZATION	(1)	LS
725-20.01	CCTV POLE & FOUNDATION (50FT POLE W/LWRNG DVICE)	1.000	EACH
725-20.02	CCTV POLE & FOUNDATION (80FT POLE W/LWRNG DVICE)	7.000	EACH
725-20.09	MAINTENANCE WORK PAD (CONCRETE PAD)	4.000	EACH
725-20.10	MAINTENANCE WORK PAD (WOOD PLATFORM)	6.000	EACH
725-20.22	STEEL OVERHEAD SIGN STRUCTURE (SPANS 51FT TO 70FT) (SPANS 51 FT TO 70 FT)	1.000	EACH
725-20.43	PULL BOX (TYPE C)	25.000	EACH
725-20.44	PULL BOX (TYPE D)	64.000	EACH
725-20.45	PULL BOX (TYPE E)	11.000	EACH
725-20.46	PULL BOX (STRUCTURE MOUNTED)	3.000	EACH
725-20.55	CABLE (1/C #6 AWG.)	3,830.000	L.F.
725-20.56	CABLE (1/C #4 AWG.)	4,805.000	L.F.
725-20.57	CABLE (1/C #2 AWG.)	7,575.000	L.F.
725-20.71	ELECTRICAL CONNECTION	(1)	LS
725-20.91	CCTV CAMERA SYSTEM (PAN TILT & ZOOM)	8.000	EACH
725-21.02	DYNAMIC MESSAGE SIGN (MULTI-COLOR) (MULTI-COLOR)	1.000	EACH
725-21.11	NETWORK SWITCH (TYPE A)	11.000	EACH
725-21.48	DEMARICATION POINT RISER ASSEMBLY	9.000	EACH
725-21.73	TRANSFORMER (DESCRIPTION) (TYPE C)	8.000	EACH
725-21.85	UNINTERRUPTIBLE POWER SUPPLY	11.000	EACH
725-21.91	RADAR DETECTION SYSTEM	8.000	EACH

Contract ID CNX274 - BLOUNT & KNOX

Item No.	Description	Quantity	Units
725-21.96	RDS COMM CABLE	475.000	L.F.
725-22.22	CONDUIT BANK (TYPE 2)	240.000	L.F.
725-22.24	CONDUIT BANK (TYPE 4)	34,355.000	L.F.
725-22.32	CONDUIT BANK BORED (TYPE 2)	1,295.000	L.F.
725-22.34	CONDUIT BANK BORED (TYPE 4)	6,695.000	L.F.
725-22.42	CONDUIT BANK IN ROCK (TYPE 2)	200.000	L.F.
725-22.44	CONDUIT BANK IN ROCK (TYPE 4)	5,640.000	L.F.
725-22.50	DMS CONDUIT BANK	75.000	L.F.
725-22.64	STRUCTURE CONDUIT BANK (TYPE 4)	2,835.000	L.F.
725-22.71	2IN CONDUIT	3,170.000	L.F.
725-22.72	2IN CONDUIT BORED	195.000	L.F.
725-22.74	2IN CONDUIT W/BANK	1,540.000	L.F.
725-23.01	ITS CABLE MARKER	113.000	EACH
725-23.16	FIBER OPTIC CABLE (144F)	53,150.000	L.F.
725-23.21	FIBER OPTIC DROP CABLE (12 F)	3,220.000	L.F.
725-23.26	FIBER OPTIC CLOSURE (12 F)	6.000	EACH
725-23.27	FIBER OPTIC CLOSURE (DESCRIPTION) (144 F)	6.000	EACH
725-23.28	FIBER OPTIC SPLICE FUSION	758.000	EACH
725-23.31	FIBER OPTIC DROP PANEL (12 F)	11.000	EACH
725-24.02	CABINET (TYPE B)	8.000	EACH
725-24.03	CABINET (TYPE C)	1.000	EACH
725-24.21	PREVENTIVE MAINTENANCE FOR SYSTEM	(1)	LS
725-24.25	UNSCHEDULED MAINTENANCE LABOR	1.000	HOUR
725-24.31	SPARE PARTS	(1)	LS
725-24.41	BURN-IN PERIOD	(1)	LS
725-24.51	SYSTEM INTEGRATION	(1)	LS
725-24.55	AS-BUILT PLANS	(1)	LS
725-24.61	TRAINING	(1)	LS
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	270.000	L.F.
801-01	SEEDING (WITH MULCH)	47.000	UNIT

Contract ID CNX274 - BLOUNT & KNOX

Item No.	Description	Quantity	Units
801-01.02	CROWN VETCH MIXTURE (WITH MULCH)	19.000	UNIT

() Item will be bid as lump sum.

Contract ID CNX312 - BRADLEY , COFFEE, ETC.

Contract ID: CNX312

Letting Date: August 18, 2023 10:00 AM

Projects: R2BVAR-M3-024

NA

Counties: BRADLEY, COFFEE, CUMBERLAND,
GRUNDY, HAMILTON, MARION, PUTNAM,
SEQUATCHIE

District:

DBE Goal Percent:

Description: The on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	500.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	1,900.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	65.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	10.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	20.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	10.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	65.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	400.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	55.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	815.000	L.F.
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH

Contract ID CNX312 - BRADLEY , COFFEE, ETC.

Item No.	Description	Quantity	Units
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	2.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	2.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	20.000	EACH

() Item will be bid as lump sum.

Contract ID CNX275 - CAMPBELL

Contract ID: CNX275

Letting Date: August 18, 2023 10:00 AM

Projects: 071075-M3-012

n/a

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The slope stabilization on I-75 SB near MM 148.9.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,906.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	15,223.000	TON
203-06	WATER	3.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	37.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	18.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.700	L.M.
209-05	SEDIMENT REMOVAL	36.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,687.000	L.F.
209-08.07	ROCK CHECK DAM	2.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
303-10.01	MINERAL AGGREGATE (SIZE 57)	212.000	TON
307-03.09	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING C	999.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
403-02.02	HOT APPLIED TACK COAT	12.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	134.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	1,215.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.700	L.M.

Contract ID CNX275 - CAMPBELL

Item No.	Description	Quantity	Units
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	954.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	37.000	L.F.
607-05.04	24" CONCRETE PIPE CULVERT (CLASS V)	52.000	L.F.
607-05.07	24" CONCRETE PIPE CULVERT CLASS V (JACKED-IN-PLACE)	117.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	148.000	L.F.
611-01.04	MANHOLES, > 12' - 16' DEPTH	1.000	EACH
611-01.05	MANHOLES, > 16' - 20' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	4.500	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	208.000	LB.
621-03.02	18" TEMPORARY DRAINAGE PIPE	16.000	L.F.
705-02.01	SINGLE GUARDRAIL, WITH RUB-RAIL (TYPE 2)	157.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	2.000	EACH
705-04.02	GUARDRAIL TERMINAL (TYPE 12)	1.000	EACH
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	783.000	L.F.
705-06.10	GR TERMINAL TRAILING END (TYPE 13) MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	636.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,385.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	46.000	TON
709-05.07	MACHINED RIP-RAP (CLASS A-2)	136.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	16.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	325.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	107.000	EACH
712-04.10	TEMPORARY FLEXIBLE TUBULAR DELINEATOR	49.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	16.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,032.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH

Contract ID CNX275 - CAMPBELL

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	280.000	EACH
716-01.07	TEMPORARY RAISED PAVEMENT MARKER,YELLOW	178.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	57.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	57.000	EACH
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	3.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.400	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	280.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,741.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,683.000	L.F.
801-01.02	CROWN VETCH MIXTURE (WITH MULCH)	1.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	1.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	2.000	UNIT
801-03	WATER (SEEDING & SODDING)	0.300	M.G.
803-01	SODDING (NEW SOD)	67.000	S.Y.
805-12.03	EROSION CONTROL BLANKET (TYPE III)	203.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX276 - CAMPBELL

Contract ID: CNX276

Letting Date: August 18, 2023 10:00 AM

Projects: 07S009-S3-005

NA

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The signal upgrades on U.S. 25W (S.R.9) at the intersection of Eagle Bluff Road in Jacksboro (L.M. 29.30).

Contract Time: DT - 12/15/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	5.000	EACH
730-02.14	SIGNAL HEAD ASSEMBLY (140 A1 WITH BACKPLATE)	2.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	2.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	766.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	566.000	L.F.
730-13.01	VEHICLE DETECTOR (SHELF MOUNT)	6.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-16.50	CONFLICT MONITOR	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX279 - CARROLL

Contract ID: CNX279

Letting Date: August 18, 2023 10:00 AM

Projects: 09S022-S8-006

N/A

Counties: CARROLL

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 22 from the Henderson County line (L.M. 0.00) to near Weatherford Street (L.M. 4.48).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	50.000	S.Y.
203-06	WATER	11.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	9.600	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	1,375.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	23.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	814.000	TON
403-02.01	TRACKLESS TACK COAT	92.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,258.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	20.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	13,613.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	3.900	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	6.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	17,212.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	11.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	11.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH

Contract ID CNX279 - CARROLL

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,896.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	393.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	592.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	15.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	964.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	103.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	265.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	44.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	347.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	210.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	21.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	21.300	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	300.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	285.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX281 - CARROLL

Contract ID: CNX281

Letting Date: August 18, 2023 10:00 AM

Projects: 09S077-S8-004

n/a

Counties: CARROLL

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 77 from near McLemoresville Road (L.M. 5.80) to the S.R. 22 Bypass (L.M. 13.92).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	125.000	S.Y.
203-06	WATER	15.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	15.300	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C or D)	2,009.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	44.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	15.000	TON
403-02.01	TRACKLESS TACK COAT	43.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	10,525.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.300	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	11.600	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	162.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	1,175.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	1,314.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	25.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	15.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNX281 - CARROLL

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,810.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	510.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	11.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	37.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	288.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	7.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	27.000	L.M.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	37.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	27.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	27.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX277 - CARTER

Contract ID: CNX277

Letting Date: August 18, 2023 10:00 AM

Projects: 10S091-S3-003

NA

Counties: CARTER

District:

DBE Goal Percent:

Description: The signal upgrades on U.S. 321 at the intersection of Hudson Drive in Elizabethton (L.M. 5.31).

Contract Time: DT - 12/15/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-01.01	REMOVE & RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	4.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	5.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	100.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	550.000	L.F.
730-13.06	VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNX272 - CHEATHAM , DAVIDSON, ETC.

Contract ID: CNX272

Letting Date: August 18, 2023 10:00 AM

Projects: R3BVAR-M3-037

NA

Counties: CHEATHAM, DAVIDSON, DICKSON, GILES,
HICKMAN, HUMPHREYS, LAWRENCE,
MARSHALL, MAURY, MONTGOMERY,
ROBERTSON, RUTHERFORD, SMITH,
SUMNER, WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The on-call cable barrier repair on various Interstate and State Routes.

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
705-06.40	CABLE BARRIER (MASH TL-3)	100.000	L.F.
705-06.41	CABLE BARRIER ANCHOR (MASH TL-3)	2.000	EACH
705-80.01	LONGITUDINAL CABLE BARRIER	100.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	3.000	EACH
705-80.04	SOCKETED LINE POST W/ALL ACCESSORIES	2,500.000	EACH
705-80.06	TERMINAL POST W/ALL ACCESSORIES	130.000	EACH
705-80.07	CABLE RELEASE POST (TOP) W/ALL ACCESSORIES	10.000	EACH
705-80.10	LINE POST W/FTNG & ALL ACC.	30.000	EACH
705-80.12	CHECK CABLE TENSION	(1)	LS
705-80.14	END TERMINAL HARDWARE FOR ATTACHING SINGLE CABLE	10.000	EACH
705-80.15	RETENSIONING CABLE BARRIER SECTION AFTER REPAIR	75.000	EACH
705-80.17	LONGITUDINAL CABLE BARRIER TRAINING	1.000	EACH
705-80.19	HARDWARE FOR ATTACHING ALL CABLES TO A SINGLE POST	650.000	EACH
705-80.20	LONGITUDINAL CABLE BARRIER SPLICE (TORPEDO, TURNBUCKLE)	30.000	EACH
705-80.21	LONGITUDINAL CABLE BARRIER CABLE	100.000	L.F.

Contract ID CNX272 - CHEATHAM , DAVIDSON, ETC.

Item No.	Description	Quantity	Units
705-80.22	TERMINAL POST W/FOOTING AND ALL ACCESSORIES	5.000	EACH
705-80.23	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-4	1.000	EACH
705-80.24	CONCRETE MONOLITHIC BLOCK FOR CABLE END TERMINAL FOUNDATION	1.000	EACH
706-80.18	CABLE BARRIER TERMINAL (REMOVAL)	2.000	EACH
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	10.000	DAY
717-01.03	MOBILIZATION (PER CALL-OUT)	105.000	EACH

() Item will be bid as lump sum.

Contract ID CNX309 - COFFEE

Contract ID: CNX309

Letting Date: August 18, 2023 10:00 AM

Projects: 16004-3208-94

BR-STP/HIP-2(260)

Counties: COFFEE

District:

DBE Goal Percent: 8.50

Description: The construction of a welded steel plate girder bridge on U.S. 41 (S.R. 2) over I-24 (L.M. 8.23), including grading, drainage, and paving.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,720.000	HOURL
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (18")	60.000	L.F.
202-08.10	REMOVAL OF CURB (DESCRIPTION) (POST CURB)	637.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	11,321.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	2,961.000	TON
203-04	PLACING AND SPREADING TOPSOIL	950.000	C.Y.
203-05	UNDERCUTTING	8,709.000	C.Y.
209-03.23	FILTER SOCK (24 INCH)	2,350.000	L.F.
209-05	SEDIMENT REMOVAL	158.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	8,922.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	5,155.000	L.F.
209-08.07	ROCK CHECK DAM	32.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	36.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	2.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	3.000	EACH
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	12,216.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,056.160	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,547.000	TON

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,195.000	TON
307-01.20	ASP. CONC. MIX(PG64-22) (BPMB-HM) GR. A-S	908.000	TON
313-03	TREATED PERMEABLE BASE	3,015.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	19.500	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	65.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	11.500	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	355.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	559.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.750	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	140.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	3,015.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	200.000	L.F.
604-10.51	SCARIFYING	63.000	S.Y.
606-24.13	TEMPORARY SHEET PILES	(1)	LS
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	20.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	136.000	L.F.
611-01.03	MANHOLES, > 8' - 12' DEPTH	1.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	935.000	L.F.
705-04.05	GUARDRAIL TERMINAL (TYPE-IN-LINE)	3.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,595.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	1,262.000	L.F.
706-06.03	RADIUS RAIL	236.000	L.F.
707-01.50	CHAIN-LINK FENCE (___ FOOT) (8 FOOT)	235.000	L.F.

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (CHAIN LINK)	235.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	5,500.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	1,307.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	111.810	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	58.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	2,848.340	L.F.
710-05	LATERAL UNDERDRAIN	390.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	5.000	EACH
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	5.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	2.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	7.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	2,900.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	420.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	169.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	116.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,678.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	330.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	8.000	DAY
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	24,640.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,100.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	172.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	461.000	S.F.
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	7.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	8.000	EACH
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	100.000	EACH
716-01.14	RAISED PAVEMENT MARKER REMOVAL	87.000	EACH

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	110.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	30.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	200.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	300.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	42.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	12.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	37,650.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	690.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	30.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	7.000	EACH
716-08.19	REMOVAL OF PAVEMENT MARKING (YIELD LINE)	40.000	S.F.
716-09.03	WET REFLECTIVE PAVEMENT MARKING(6" LINE)	0.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	4.000	L.M.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	600.000	L.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,802.670	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,372.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	12,101.050	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,905.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	307.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	6.000	UNIT
801-03	WATER (SEEDING & SODDING)	124.000	M.G.

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
803-01	SODDING (NEW SOD)	11,138.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BR. NO.16-SR002-08.23)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	512.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	94.000	TON
602-03	STEEL STRUCTURES	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	210,626.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	369.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	64,618.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	268.000	S.Y.
604-03.32	CLASS DS CONCRETE	675.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,087.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,990.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (ABUTMENT NO. 1 6" MOVEMENT)	98.000	L.F.
606-03.03	STEEL PILES (12 INCH)	2,418.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	66.000	EACH
617-02	BRIDGE DECK CRACK SEALING	1,102.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	6.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	1,114.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	268.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	49.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	1,302.000	L.F.
908-21.01	BEARINGS (DESCRIPTION) (EXPANSION BEARING @ ABUTMENT NO. 1)	6.000	EACH
908-21.02	BEARINGS (DESCRIPTION) (FIXED BEARING BENT AND ABUTMENT NO 2)	12.000	EACH
790-04.02	POLE 45FT CLASS 2 WOOD	1.000	EACH
790-04.04	POLE 45FT CLASS 4 WOOD	1.000	EACH
790-07.02	POLE 60FT CLASS 2 WOOD	6.000	EACH

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
790-20.30	TOP EXISTING POLE	5.000	EACH
790-22.15	1PH DEAD END TAP W/ EXTENSION 25KV	1.000	EACH
790-22.17	1PH DDE FEED THROUGH 25KV	1.000	EACH
790-26.14	3PH CROSSARM DBL 10FT SM ANGLE 25KV	1.000	EACH
790-26.15	3PH XARM DBL 10FT LRG COND SM ANGLE 25KV	3.000	EACH
790-26.22	3PH VERTICAL DDE ANGLE LRG COND 25KV	1.000	EACH
790-26.23	3PH VERTICAL DEAD END 25KV	1.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	1.000	EACH
790-26.28	3PH DBL 10FT XARM DDE 25KV	3.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	1.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	42.000	EACH
790-32.23	GUY GUARD	42.000	EACH
790-33.01	EXPANDING TYPE ANCHOR 6,000LB-8,000LB	4.000	EACH
790-33.02	EXPANDING TYPE ANCHOR 10,000LB-12,000LB	9.000	EACH
790-33.15	1IN TRIPLE EYE	11.000	EACH
790-36.05	TRANSFER SECONDARY	2.000	EACH
790-36.09	TRANSFER - 1TR XFMR ASSEMBLY	4.000	EACH
790-36.14	TRANSFER CONDUCTOR	4.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	8.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	1,990.000	L.F.
790-40.05	OH COND 3/0 6/1 ACSR PIGEON	1,825.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	5,475.000	L.F.
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	1.000	EACH
790-49.02	3PH XFMR BNK POLE MTD W/ FUSE/ARRESTERS	1.000	EACH
790-68.06	POLE TOP PROTECTION ASSEMBLY	9.000	EACH
790-68.10	MISCELLANEOUS ASSEMBLIES	11.000	EACH
790-68.11	DEAD END SHOE	1.000	EACH
790-69.08	GROUND-GROUND ROD	8.000	EACH
790-69.22	POLE TOP PIN	3.000	EACH
790-69.31	STICK PIN	4.000	EACH

Contract ID CNX309 - COFFEE

Item No.	Description	Quantity	Units
790-74.10	144 FIBER(MATERIAL ONLY)	2,136.000	L.F.
790-74.25	FIBER SPLICE-12 FIBER RIBBON	24.000	EACH
790-74.31	FIBER TANGENT ASSEMBLY	4.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	4.000	EACH
790-74.33	FIBER DOUBLE DEADEND ASSEMBLY	2.000	EACH
790-74.34	FIBER STORAGE SINGLE LOOP	4.000	EACH
790-98.01	REMOVE WIRE	8,976.000	L.F.
790-98.02	REMOVE POLES	6.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	76.000	EACH
790-98.04	REMOVE FIBER OPTIC CABLE	2,073.000	L.F.
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	155.000	L.F.
793-14.39	6IN SPLIT CONDUIT (FMP)	155.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX247 - COFFEE

Contract ID: CNX247

Letting Date: August 18, 2023 10:00 AM

Projects: 16009-3242-14

STP/NH-55(6)

Counties: COFFEE

District:

DBE Goal Percent: 8.00

Description: The grading, drainage, construction of a concrete box beam bridge, lighting, signals and paving on S.R. 55 from First Avenue (L.M. 1.95) to U.S. 41A (S.R. 16, N. Jackson Street) (L.M. 2.59) in Tullahoma.

Contract Time: DT - 4/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,720.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	36.000	EACH
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (SEE SHEET 2F10)	4,408.000	L.F.
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT 12)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	11,998.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	813.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	4,400.000	C.Y.
203-06	WATER	641.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	2,490.000	C.Y.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	574.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-03.22	FILTER SOCK (18 INCH)	600.000	L.F.
209-05	SEDIMENT REMOVAL	236.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,756.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	10,075.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	6.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-09.40	CURB INLET PROTECTION (TYPE 1)	88.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	23.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	4.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	48.000	EACH
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	38.000	EACH
209-40.45	CATCH BASIN FILTER ASSEMBLY(TYPE 5)	10.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	9.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	1.000	EACH
209-40.49	CATCH BASIN FILTER ASSEMBLY(TYPE 9)	3.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	349.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	18,606.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	34.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	390.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	578.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	3,880.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	2,719.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	38.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	132.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	17.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	800.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	11.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	393.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	1,840.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	231.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	189.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	13,902.000	LB.
604-01.04	1-1/2" STEEL PIPE HANDRAIL	66.000	L.F.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
604-01.20	BOX TUBE SAFETY RAIL	840.000	L.F.
604-03.07	CLASS A CONCRETE (DESCRIPTION) (ADA RAMPS & STAIRS, AND GREENWAY HANDRAIL BASE)	45.000	C.Y.
604-03.08	CLASS A CONCRETE (DESCRIPTION) (CONC. CHANNELS, SLOTTED GRATE DRAIN & WINGWALLS)	17.000	C.Y.
604-10.51	SCARIFYING	7,987.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	2,867.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	1,184.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	263.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	334.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	2,413.000	L.F.
607-16.10	68"X 43" HORIZONTAL OVAL CONCRETE PIPE CULVERT	258.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	48.000	L.F.
611-01.01	MANHOLES, 0' - 4' DEPTH	2.000	EACH
611-01.02	MANHOLES, > 4' - 8' DEPTH	3.000	EACH
611-01.03	MANHOLES, > 8' - 12' DEPTH	1.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	3.000	EACH
611-02.12	JUNCTION BOX, TYPE 3	3.000	EACH
611-05.01	TRENCH DRAINS	66.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	15.300	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	658.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	4.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	14.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	61.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	11.000	EACH
611-12.04	CATCH BASINS, TYPE 12, > 12' - 16' DEPTH	4.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	3.000	EACH
611-14.03	CATCH BASINS, TYPE 14, > 8' - 12' DEPTH	2.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	7.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	3.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
621-05.01	TEMPORARY SHORING	350.000	S.F.
701-01.01	CONCRETE SIDEWALK (4 ")	25,385.000	S.F.
701-02.03	CONCRETE CURB RAMP	4,144.000	S.F.
702-01	CONCRETE CURB	83.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	505.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	153.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
705-20.23	REUSABLE CRASH CUSHION WIDE (MASH TL-3)	2.000	EACH
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	557.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	62.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	23.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	1,600.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,127.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	435.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	24.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	435.000	EACH
712-06	SIGNS (CONSTRUCTION)	652.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	11.000	L.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	470.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	0.420	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	145.300	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	245.000	LB.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,134.000	LB.
713-11.21	P POST SLIP BASE	7.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	215.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	77.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	28.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK)	128.000	S.F.
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	64.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.06	MILE POST SIGN	2.000	EACH
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	6.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
714-03	JACKED OR BORED CONDUIT	1,900.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	7,000.000	L.F.
714-05.04	PULL BOXES (TYPE C)	50.000	EACH
714-06.05	CABLE (1/C # 6 AWG)	8,500.000	L.F.
714-08.01	LIGHT STANDARDS (45' M.H., 15' ARM)	15.000	EACH
714-08.09	LIGHT STANDARDS (DESCRIPTION) (45' M.H., 5' ARM)	1.000	EACH
714-08.10	LIGHT STANDARDS (DESCRIPTION) (40' M.H., 15' ARM)	1.000	EACH
714-08.11	LIGHT STANDARDS (DESCRIPTION) (40' M.H., 10' ARM)	5.000	EACH
714-08.12	LIGHT STANDARDS (DESCRIPTION) (40' M.H., 10' ARM, ON BRIDGE PARAPET)	4.000	EACH
714-08.20	FOUNDATION (ONLY) FOR LIGHT STANDARD	15.000	EACH
714-08.21	FOUNDATION (ONLY) FOR LIGHT STANDARD	1.000	EACH
714-08.22	FOUNDATION (ONLY) FOR LIGHT STANDARD	4.000	EACH
714-09.09	LUMINAIRES (DESCRIPTION) (LED - 160W)	20.000	EACH
714-09.10	LUMINAIRES (DESCRIPTION) (LED - 110W)	7.000	EACH
714-09.11	LUMINAIRES (DESCRIPTION) (LED - 55W)	9.000	EACH
714-09.12	LUMINAIRES (DESCRIPTION) (LED - 105W)	7.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
714-12.01	CONTROL CENTER (NO. 1)	(1)	LS
714-14.01	MASTARM - 15'	9.000	EACH
714-14.03	MASTARM (DESCRIPTION) (10')	2.000	EACH
714-14.04	MASTARM (DESCRIPTION) (5')	2.000	EACH
714-14.05	MASTARM (DESCRIPTION) (TENON MOUNT)	8.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (SEE PLANS)	(1)	LS
714-25.22	INSTALL SVC RISER (DESCRIPTION) (DESCRIPTION)	13.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	97.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	96.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	120.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	547.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	679.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	14.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	624.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	39.000	S.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	5.950	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	107.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	882.000	S.Y.
716-05.22	PAINTED PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	100.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,465.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	252.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	882.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	89.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.850	L.M.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	414.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	8.000	EACH
730-02.14	SIGNAL HEAD ASSEMBLY (140 A1 WITH BACKPLATE)	1.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	7.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	11.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	1,972.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,707.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	615.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	363.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	225.000	L.F.
730-12.14	CONDUIT 3" DIAMETER (JACK AND BORE)	660.000	L.F.
730-13.16	VEHICLE DETECTOR (RADAR/VIDEO)	8.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	5.000	EACH
730-25.01	CANTILEVER SIGNAL SUPPORT (1 ARM @ 50')	2.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	2.000	EACH
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	3.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	1.000	EACH
730-25.70	DECORATIVE SIGNAL BASES (DESCRIPTION) (ALUMINUM CAST SPLIT - BLACK)	8.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	14.000	EACH
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
730-50.20	RECTANGULAR RAPID FLASHING BEACON ASSEMBLY (SOLAR POWERED)	2.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,140.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	603.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,337.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	122.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	11.000	UNIT
801-01.37	NATVE SEED MX ENCAPSULATION & CLEAR ZONE	16.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	16.000	UNIT
801-03	WATER (SEEDING & SODDING)	74.000	M.G.
803-01	SODDING (NEW SOD)	5,808.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	1,422.000	S.Y.
806-02.03	PROJECT MOWING	6.000	CYCL
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (SEE PLANS)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	2,420.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	323.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (SEE PLANS)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	2,278.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	110,252.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	694.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	101,316.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	416.000	S.Y.
604-03.32	CLASS DS CONCRETE	415.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,286.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,836.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	8,672.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	186.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (SEE PLANS)	22.000	EACH
615-02.10	PRESTRESSED CONCRETE BOX BEAM (27" X 48")	2,141.000	L.F.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
617-02	BRIDGE DECK CRACK SEALING	218.000	L.F.
617-05	SEALANT (DESCRIPTION) (SEE PLANS)	2.000	GAL.
620-05	CONCRETE PARAPET WITH STRUCTURAL TUBING	438.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	218.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	60.000	L.F.
714-01.01	STRUCTURAL LIGHTING (BRIDGE NO.) (BRIDGE NO. 1)	(1)	LS
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	2.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	1.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	5.000	EACH
790-21.18	1PH DDE FEED THROUGH 15KV	1.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	15.000	EACH
790-25.17	3PH VERTICAL DEADEND LARGE ANGLE 15KV	2.000	EACH
790-25.18	3PH VERTICAL DEADEND LRG ANG LG COND 15KV	4.000	EACH
790-25.19	3PH VERTICAL DEADEND 15KV	4.000	EACH
790-25.38	3PH 10FT FIBERGLASS CROSSARM DEADEND 15kv	11.000	EACH
790-25.40	3PH 10FT FIBERGLASS DOUBLE DEADEND 15kv	9.000	EACH
790-30.13	SECONDARY CONDUCTOR 2 AL TRIPLEX	145.000	L.F.
790-31.02	SERVICE ASSEMBLY-POLE TYPE	48.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	15.000	EACH
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	73.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	2.000	EACH
790-32.08	OH GUY - THROUGH BOLT TYPE HEAVY DUTY	37.000	EACH
790-32.24	GUY (DESCRIPTION) (INSULATOR)	70.000	EACH
790-33.25	SCREW TYPE ANCHOR 15,000LB	27.000	EACH
790-33.26	SCREW TYPE ANCHOR 28,000LB	30.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	1,660.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,900.000	L.F.
790-40.06	OH COND 4/0 6/1 ACSR PENGUIN	5,000.000	L.F.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
790-40.49	OH COND 795 37 AAC ARBUTUS	14,000.000	L.F.
790-41.03	UG PRI COND 1/0 AL 15KV	270.000	L.F.
790-42.10	4IN DIA PVC PIPE	3.000	L.F.
790-42.17	2 DUCT BANK @ 36IN-48IN DEPTH	20.000	L.F.
790-43.01	LOADBREAK ELBOW 200A 15KV	3.000	EACH
790-43.08	ELBOW ARRESTER 200A 15KV	3.000	EACH
790-43.34	UG GROUND ROD ASSEMBLY	1.000	EACH
790-43.50	SECONDARY RISER W/ 2IN CONDUIT	250.000	EACH
790-43.60	PRIMARY RISER (DESCRIPTION) (3PH PRIMARY RISER W/ 4IN CONDUIT)	1.000	EACH
790-43.62	3PH PRIMARY RISER W/ 4IN CONDUIT	3.000	EACH
790-46.03	1PH TRANSFORMER CONV W/XARM MTD FUSE & LA	10.000	EACH
790-49.02	3PH XFMR BNK POLE MTD W/ FUSE/ARRESTERS	2.000	EACH
790-51.06	3PH TRANSFORMER PAD - CONCRETE	1.000	EACH
790-56.03	150KVA 3PH PAD MT XFMR 15KV 208/120	1.000	EACH
790-58.06	GOAB SWITCH 15KV	1.000	EACH
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	6.000	EACH
790-62.20	3PH OVR-3SP ELECTRONIC RECLOSER 15KV	2.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	6.000	EACH
790-68.01	POLE GROUND ROD TYPE	44.000	EACH
790-68.10	MISCELLANEOUS ASSEMBLIES	8.000	EACH
790-74.19	12-96 FIBER(INSTALLATION ONLY)	3,000.000	L.F.
790-74.31	FIBER TANGENT ASSEMBLY	22.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	33.000	EACH
790-74.34	FIBER STORAGE SINGLE LOOP	3.000	EACH
790-74.37	FIBER SERVICE ATTACHMENT	4.000	EACH
790-98.01	REMOVE WIRE	23,054.000	L.F.
790-98.02	REMOVE POLES	2.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	290.000	EACH
790-98.04	REMOVE FIBER OPTIC CABLE	2,440.000	L.F.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
791-01.03	3IN STEEL GAS MAIN	915.000	L.F.
791-01.04	4IN STEEL GAS MAIN	512.000	L.F.
791-02.02	2IN MDPE GAS MAIN	465.000	L.F.
791-02.04	4IN MDPE GAS MAIN	2,880.000	L.F.
791-04.02	HDD 2IN PE PIPE - UNCONSOLIDATED	75.000	L.F.
791-04.04	HDD 4IN PE PIPE - UNCONSOLIDATED	605.000	L.F.
791-04.21	HDD 3IN STEEL PIPE - UNCONSOLIDATED	310.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	2.000	EACH
791-06.31	CONNECT TO 2IN EX. STL MAIN W/ STOPPLE	1.000	EACH
791-06.32	CONNECT TO 4IN EX. STL MAIN W/ STOPPLE	2.000	EACH
791-06.38	CONNECT TO __IN EX. STL MAIN W/ STOPPLE (3)	2.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	3.000	EACH
791-08.02	3/4IN SERVICE ASSEMBLY	6.000	EACH
791-08.07	3/4IN PE SERVICE PIPE	530.000	L.F.
791-08.08	1IN PE SERVICE PIPE	15.000	L.F.
791-08.17	HDD 3/4IN PE SERVICE PIPE	150.000	L.F.
791-08.40	RECONNECT SERVICE ASSEMBLY	18.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
793-01.02	POLE 30FT CLASS 5 WOOD	1.000	EACH
793-01.07	POLE 35FT CLASS 4 WOOD	2.000	EACH
793-01.11	POLE 40FT CLASS 3 WOOD	5.000	EACH
793-01.20	POLE 50FT CLASS 2 WOOD	1.000	EACH
793-01.23	POLE 55FT CLASS 1 WOOD	1.000	EACH
793-01.24	POLE 55FT CLASS 2 WOOD	14.000	EACH
793-01.28	POLE 60FT CLASS 2 WOOD	4.000	EACH
793-01.30	POLE 65FT CLASS 1 WOOD	1.000	EACH
793-01.41	ANCHOR 1IN	22.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	131.000	L.F.

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	37.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	47.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	32.000	EACH
795-01.04	6IN DIP SLIP JOINT WATER LINE	2,300.000	L.F.
795-01.06	8IN DIP SLIP JOINT WATER LINE	40.000	L.F.
795-01.07	10IN DIP RESTRAINED JOINT WATER LINE	400.000	L.F.
795-01.08	10IN DIP SLIP JOINT WATER LINE	2,500.000	L.F.
795-02.07	12IN HDPE WATER LINE	475.000	L.F.
795-03.02	2IN PVC WATER LINE	10.000	L.F.
795-03.04	4IN PVC WATER LINE	10.000	L.F.
795-03.05	6IN PVC WATER LINE	10.000	L.F.
795-05.10	HDD 20IN HDPE CASING PIPE-UNCON	225.000	L.F.
795-05.14	HDD __IN HDPE CASING PIPE-UNCON (2)	800.000	L.F.
795-05.24	HDD 20IN HDPE CASING PIPE-ROCK	200.000	L.F.
795-05.63	BORE/JACK 12IN STEEL CASING PIPE-UNCON.	310.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	2.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	9.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	1.000	EACH
795-06.06	CONNECT TO 10IN WATER LINE	2.000	EACH
795-06.30	CUT/CAP EXISTING LINES (ALL SIZES)	14.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-08.03	4IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	12.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	6.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	25.000	EACH
795-09.37	3/4IN SERVICE PIPE	1,000.000	L.F.
795-09.38	1N SERVICE PIPE	10.000	L.F.
795-09.51	RECONNECT SERVICE ASSEMBLY	2.000	EACH
795-10.05	2IN AUTO AIR RELEASE VALVE ASSEMBLY	2.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
795-11.02	FIRE HYDRANT ASSEMBLY	6.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	7,800.000	L.F.
795-13.01	DI FITTINGS	10,000.000	LB.
795-14.03	CLASS C CONCRETE	15.000	C.Y.
795-14.08	RESTORE ASPHALT	65.000	S.Y.
795-14.10	RESTORE GRAVEL	20.000	S.Y.
795-15.04	18IN STEEL CASING PIPE OPEN CUT METHOD	90.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	65.000	L.F.
797-05.52	8IN PVC GRAVITY SEWER 6FT-12FT DEPTH	795.000	L.F.
797-05.55	10IN PVC GRAVITY SEWER 0FT-6FT DEPTH	20.000	L.F.
797-05.56	10IN PVC GRAVITY SEWER 6FT-12FT DEPTH	660.000	L.F.
797-05.57	10IN PVC GRAVITY SEWER 12FT-18FT DEPTH	170.000	L.F.
797-05.68	18IN PVC GRAVITY SEWER 6FT-12FT DEPTH	115.000	L.F.
797-06.65	BORE/JACK 18IN STEEL CASING PIPE-UNCON.	30.000	L.F.
797-06.91	OPEN CUT 18IN STEEL CASING PIPE	70.000	L.F.
797-06.93	OPEN CUT 24IN STEEL CASING PIPE	87.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	1.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	5.000	EACH
797-07.05	48IN MANHOLE 10FT-12FT DEPTH	2.000	EACH
797-07.06	48IN MANHOLE 12FT-14FT DEPTH	3.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	2.000	EACH
797-07.60	ADJUST EXISTING MANHOLE	6.000	EACH
797-07.75	TRAFFIC RATED FRAMES AND COVERS	9.000	EACH
797-07.80	REMOVE SEWER MANHOLE	1.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	300.000	L.F.
797-08.08	6IN CLEAN OUT ASSEMBLY	9.000	EACH
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	9.000	EACH
797-10.02	CONNECT 8IN SEWER TO EXIST. MANHOLE	1.000	EACH
797-10.03	CONNECT 10-18IN SEWER TO EXIST. MANHOLE	1.000	EACH
797-10.08	CONNECT EX. 6IN SEWER TO NEW MANHOLE	1.000	EACH

Contract ID CNX247 - COFFEE

Item No.	Description	Quantity	Units
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	1.000	EACH
797-10.10	CONNECT EX.10-18IN SEWER TO NEW MANHOLE	2.000	EACH
797-11.25	RETIREIN PLACE 48IN MANHOLE	6.000	EACH
797-11.31	RETIREIN PLACE EXISTING SEWER 8IN-14IN	1,225.000	L.F.
797-11.32	RETIREIN PLACE EXISTING SEWER 15IN-24IN	90.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.40	RESTORE ASPHALT	50.000	S.Y.
797-11.50	FRAME AND COVER (WATERTIGHT) (WATERTIGHT)	2.000	EACH
797-40.01	CONCRETE ENCASEMENT	40.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX283 - CROCKETT

Contract ID: CNX283

Letting Date: August 18, 2023 10:00 AM

Projects: 17S020-S8-003

N/A

Counties: CROCKETT

District:

DBE Goal Percent:

Description: The resurfacing with hot in-place recycling on U.S. 412 (S.R. 20) from Birmingham/Lyons Road (L.M. 8.23) to U.S. 70 (U.S. 79, S.R. 76) (L.M. 17.64).

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	534.000	S.Y.
203-06	WATER	20.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	37.500	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	5,342.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	185.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	62.000	TON
311-03.04	HOT IN PLACE RECYCLING OF ASPHALT PAVEMENT (2.00IN)	276,030.000	S.Y.
311-03.10	ASPHALT REJUVENATING AGENT	110,420.000	GAL.
403-02.01	TRACKLESS TACK COAT	185.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	14,300.000	TON
411-03.26	ACS MIX(PG70-22) THIN LIFT E ASPHALT	5,400.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	16.820	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	14.550	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	2,380.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	21.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	21.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNX283 - CROCKETT

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	350.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	80.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	80.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,384.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,650.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,650.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	480.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	45.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,750.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	2.360	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	42.000	S.F.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	12,500.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	42.345	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	42.345	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	75.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX310 - DEKALB

Contract ID: CNX310

Letting Date: August 18, 2023 10:00 AM

Projects: 21945-3493-94

HSIP-2100(29)

Counties: DEKALB

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	55.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	219.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	2,082.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	300.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	728.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	6,415.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	862.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	933.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	93.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	789.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	61.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	564.000	L.F.
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	2.000	EACH
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	48.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	47.840	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	3,500.000	L.F.
717-01	MOBILIZATION	(1)	LS

Contract ID CNX310 - DEKALB

() Item will be bid as lump sum.

Contract ID CNX284 - DYER

Contract ID: CNX284

Letting Date: August 18, 2023 10:00 AM

Projects: 23S104-S8-003

N/A

Counties: DYER

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 104 from near Viar Road (L.M. 20.07) to the Gibson County line (L.M. 29.02).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,838.000	S.Y.
203-06	WATER	27.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	17.900	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	3,596.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	846.000	TON
403-02.01	TRACKLESS TACK COAT	68.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	12,734.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	9.130	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	12.574	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,119.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	17.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	11.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,066.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	592.000	EACH

Contract ID CNX284 - DYER

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	592.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	264.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,025.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	30.564	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.564	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX286 - DYER

Contract ID: CNX286

Letting Date: August 18, 2023 10:00 AM

Projects: 23S181-S8-002

N/A

Counties: DYER

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 181 from S.R. 104 (L.M. 11.48) to the Lake County line (L.M. 21.90).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	6,419.000	S.Y.
203-06	WATER	53.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	20.840	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	7,104.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	2,215.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	14,906.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	23,614.000	TON
403-02.01	TRACKLESS TACK COAT	137.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	16.680	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	349.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	2,883.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	13,258.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	5.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,738.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	690.000	EACH

Contract ID CNX286 - DYER

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	690.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	120.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	24.630	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	13.440	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	24.630	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX287 - FAYETTE

Contract ID: CNX287

Letting Date: August 18, 2023 10:00 AM

Projects: 24S196-S8-004

N/A

Counties: FAYETTE

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 196 from S.R. 193 (L.M. 11.91) to U.S. 64 (S.R. 15) (L.M. 16.99).

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	534.000	S.Y.
203-06	WATER	8.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.059	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	1,023.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	246.000	TON
403-02.01	TRACKLESS TACK COAT	38.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	6,916.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	6.325	L.M.
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.832	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	7.250	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	6,851.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	8.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	778.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	310.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE	310.000	EACH

Contract ID CNX287 - FAYETTE

Item No.	Description	Quantity	Units
716-02.04	MARKER PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	20.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	66.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	230.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	18.412	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	18.412	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX288 - HARDIN

Contract ID: CNX288

Letting Date: August 18, 2023 10:00 AM

Projects: 36945-3499-94

HSIP-3600(40)

Counties: HARDIN

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	18.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	6.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	18.840	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	990.000	L.F.
713-02.34	DELINEATORS (ALL)	21.000	EACH
713-11.01	"U" SECTION STEEL POSTS	1,782.800	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	3,845.400	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,069.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	760.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	1,537.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	24.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	11.110	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	173.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.040	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	11.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	43.330	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX135 - HUMPHREYS

Contract ID: CNX135

Letting Date: August 18, 2023 10:00 AM

Projects: 43LCOU-F3-004

BRZ-4300(36)

Counties: HUMPHREYS

District:

DBE Goal Percent: 8.50

Description: The construction of a concrete box beam bridge on Tumbling Creek Road over Tumbling Creek (L.M. 2.02), including grading, drainage and paving.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	307.000	C.Y.
203-02.02	BORROW EXCAVATION (GRADED SOLID ROCK)	127.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	13.000	C.Y.
209-05	SEDIMENT REMOVAL	16.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,084.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	8.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	340.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	276.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	11.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE A)	45.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	66.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	4.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	43.000	TON
620-05.10	CONCRETE PARAPET CURVED WALL (<=TO 40MPH)	10.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	237.500	L.F.

Contract ID CNX135 - HUMPHREYS

Item No.	Description	Quantity	Units
705-06.10	GR TERMINAL TRAILING END (TYPE 13) MASH TL-3	3.000	EACH
705-06.26	THREE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	571.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	154.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	96.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	318.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	205.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	100.000	L.F.
801-01	SEEDING (WITH MULCH)	2.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	4.000	UNIT
801-03	WATER (SEEDING & SODDING)	1.000	M.G.
803-01	SODDING (NEW SOD)	50.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	150.000	S.Y.
806-02.03	PROJECT MOWING	2.000	CYCL
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 43-0A239-02.02)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	362.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	451.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	378.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	150.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO 1, STA. 105+75.75)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO 2, STA. 106+36.58)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	177.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	38,899.000	LB.

Contract ID CNX135 - HUMPHREYS

Item No.	Description	Quantity	Units
604-03.01	CLASS A CONCRETE (BRIDGES)	248.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	36,133.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	108.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	709.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	145.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	8.000	EACH
615-02.37	PRESTRESSED CONCRETE BOX BEAM (30" X 36")	435.000	L.F.
620-06	CONCRETE RAILING	325.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	79.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	40.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX282 - JOHNSON

Contract ID: CNX282

Letting Date: August 18, 2023 10:00 AM

Projects: 46946-3410-94

HSIP-4600(29)

Counties: JOHNSON

District:

DBE Goal Percent: 2.00

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	25.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	834.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	3,133.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	6,773.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	702.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	1,314.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	78.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	52.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	170.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	87.200	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	2,590.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX302 - LAKE

Contract ID: CNX302

Letting Date: August 18, 2023 10:00 AM

Projects: 48945-3424-94

HSIP-4800(16)

Counties: LAKE

District:

DBE Goal Percent: 2.00

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	550.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	8.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	651.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	5,922.000	LB.
713-11.22	U POST SLIP BASE	151.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	291.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	823.000	S.F.
713-15.35	METAL BARRICADE (TYPE III)	1.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	100.000	EACH
713-16.05	RAILROAD CROSS-BUCK SIGN & SUPPORT	2.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	54.000	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	382.000	L.F.
716-05.10	PAINTED PAVEMENT MARKING (RXR)	2.000	EACH
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	1,555.000	L.F.
716-06.01	PAINTED WORD PVMT MARK ()	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX290 - LAUDERDALE

Contract ID: CNX290

Letting Date: August 18, 2023 10:00 AM

Projects: 49005-8229-04
49S003-S8-005

N/A
N/A

Counties: LAUDERDALE

District:

DBE Goal Percent:

Description: The resurfacing with hot in-place recycling on U.S. 51 (S.R. 3) from the Tipton County line to S.R. 19 (L.M. 0.00 to 8.85) and resurfacing on S.R. 19 from U.S. 51 (S.R. 3) to near Eastland Avenue (L.M. 19.09 to 21.99).

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	175.000	S.Y.
203-06	WATER	41.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	39.700	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	5,454.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	362.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	9.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	3.000	TON
311-03.04	HOT IN PLACE RECYCLING OF ASPHALT PAVEMENT (2.00IN)	255,794.000	S.Y.
311-03.10	ASPHALT REJUVENATING AGENT	102,318.000	GAL.
403-02.01	TRACKLESS TACK COAT	167.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,765.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	8.900	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	1,024.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	13,180.000	TON
411-03.24	ACS MIX(PG64-22) THIN LIFT E ASPHALT	1,353.000	TON

Contract ID CNX290 - LAUDERDALE

Item No.	Description	Quantity	Units
411-03.26	ACS MIX(PG70-22) THIN LIFT E ASPHALT	4,877.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	16.400	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	18.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,159.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	16,481.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	27.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	3.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	12.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	15.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	70.000	EACH
712-06	SIGNS (CONSTRUCTION)	4,658.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	300.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	1,216.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	349.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,268.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	425.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	984.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	64.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	2,457.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	1.170	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	11.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	8.000	EACH

Contract ID CNX290 - LAUDERDALE

Item No.	Description	Quantity	Units
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	1.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	18.000	S.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	207.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	50.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	50.800	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,130.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	915.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	50.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.01	SHIELDED DETECTOR CABLE	50.000	L.F.
730-14.02	SAW SLOT	3,164.000	L.F.
730-14.03	LOOP WIRE	8,148.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX289 - LAUDERDALE

Contract ID: CNX289

Letting Date: August 18, 2023 10:00 AM

Projects: 49S003-S8-006

N/A

Counties: LAUDERDALE

District:

DBE Goal Percent:

Description: The resurfacing with hot in-place recycling on U.S. 51 (S.R. 3) from near S.R. 88 (L.M. 20.18) to the Dyer County line (L.M. 25.00).

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	25.000	S.Y.
203-06	WATER	19.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	19.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	2,547.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	9.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	3.000	TON
311-03.04	HOT IN PLACE RECYCLING OF ASPHALT PAVEMENT (2.00IN)	140,194.000	S.Y.
311-03.10	ASPHALT REJUVENATING AGENT	56,078.000	GAL.
403-02.01	TRACKLESS TACK COAT	66.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	805.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	6,857.000	TON
411-03.26	ACS MIX(PG70-22) THIN LIFT E ASPHALT	1,929.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	9.600	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	7.600	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	19,652.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	5.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH

Contract ID CNX289 - LAUDERDALE

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	80.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,276.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	64.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	637.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	77.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	650.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	274.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	160.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	126.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	74.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	22.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	22.800	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,530.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	762.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX099 - LINCOLN

Contract ID: CNX099

Letting Date: August 18, 2023 10:00 AM

Projects: 52002-4244-04

N/A

Counties: LINCOLN

District:

DBE Goal Percent:

Description: The repair of the bridges on U.S. 231 (S.R. 10) over the Elk River (L.M. 10.57).

Contract Time: CD - 30 Days

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 52-SR010-10.57 LT. & RT.)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	500.000	L.F.
601-10.11	TREATED TIMBER (SIDEWALK PLANKS AND CURBS)	6.400	MBFM
602-10.10	ANCHOR BOLTS	66.000	EACH
602-10.32	STRUCTURAL STEEL (REPAIRS)	7,868.000	LB.
604-10.05	CONCRETE	10.000	S.F.
604-10.18	REINFORCING STEEL (REPAIRS)	31,780.000	LB.
604-10.42	CONCRETE REPAIRS	1,133.925	C.F.
604-10.54	CONCRETE REPAIRS	20.000	S.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	500.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	1,028.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	227.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	38.000	EACH
712-06	SIGNS (CONSTRUCTION)	378.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	7,947.000	L.F.

Contract ID CNX099 - LINCOLN

Item No.	Description	Quantity	Units
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	950.000	L.F.
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	25.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX285 - LOUDON

Contract ID: CNX285

Letting Date: August 18, 2023 10:00 AM

Projects: 53I075-M3-003

n/a

Counties: LOUDON

District:

DBE Goal Percent:

Description: The repair of the bridges on I-75 over Hotchkiss Valley Road (L.M. 12.92).

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
201-05.31	VEGETATION REMOVAL	(1)	LS
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
411-01.10	ACS MIX(PG64-22) GRADING D	183.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	2,566.000	S.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	1,733.000	S.Y.
604-10.05	CONCRETE	36.000	S.F.
604-10.42	CONCRETE REPAIRS	6.000	C.F.
604-10.54	CONCRETE REPAIRS	36.000	S.F.
604-10.55	CONCRETE (FOUNDATION REPAIRS)	6.000	C.Y.
604-10.58	EPOXY INJECTION (INJECTION)	10.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	92.000	L.F.
604-10.69	PRESTRESSING STRAND SPLICE	1.000	EACH
622-01	PNEUMATICALLY PLACED CONCRETE	22.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	430.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	111.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	14.000	EACH
712-06	SIGNS (CONSTRUCTION)	841.000	S.F.

Contract ID CNX285 - LOUDON

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	264.000	HOUR
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,700.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (VERTICAL CLEARANCE)	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX307 - MADISON

Contract ID: CNX307

Letting Date: August 18, 2023 10:00 AM

Projects: 57201-3151-44

NH-I-40-1(354)

Counties: MADISON

District:

DBE Goal Percent: 6.00

Description: The expansion of the Smartway Intelligent Transportation System (ITS) on I-40 near Jackson (L.M. 7.55 to L.M. 9.28 and L.M. 12.30 to L.M. 15.22).

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
203-07	FURNISHING & SPREADING TOPSOIL	5.000	C.Y.
209-05	SEDIMENT REMOVAL	50.000	C.Y.
209-09.01	SANDBAGS	36.000	BAG
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	278.000	S.Y.
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,285.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,000.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	75.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	20.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	75.000	EACH
712-06	SIGNS (CONSTRUCTION)	576.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	2.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	2.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
717-01	MOBILIZATION	(1)	LS

Contract ID CNX307 - MADISON

Item No.	Description	Quantity	Units
725-20.02	CCTV POLE & FOUNDATION (80FT POLE W/LWRNG DVICE)	4.000	EACH
725-20.23	STEEL OVERHEAD SIGN STRUCTURE (SPANS 71FT TO 90FT) (SPANS 71FT TO 90FT)	1.000	EACH
725-20.43	PULL BOX (TYPE C)	13.000	EACH
725-20.44	PULL BOX (TYPE D)	25.000	EACH
725-20.45	PULL BOX (TYPE E)	5.000	EACH
725-20.46	PULL BOX (STRUCTURE MOUNTED)	2.000	EACH
725-20.55	CABLE (1/C #6 AWG.)	3,185.000	L.F.
725-20.56	CABLE (1/C #4 AWG.)	2,190.000	L.F.
725-20.57	CABLE (1/C #2 AWG.)	4,665.000	L.F.
725-20.71	ELECTRICAL CONNECTION	(1)	LS
725-20.91	CCTV CAMERA SYSTEM (PAN TILT & ZOOM)	4.000	EACH
725-21.02	DYNAMIC MESSAGE SIGN (MULTI-COLOR) (MULTI-COLOR)	1.000	EACH
725-21.11	NETWORK SWITCH (TYPE A)	5.000	EACH
725-21.48	DEMARICATION POINT RISER ASSEMBLY	5.000	EACH
725-21.85	UNINTERRUPTIBLE POWER SUPPLY	5.000	EACH
725-21.91	RADAR DETECTION SYSTEM	4.000	EACH
725-21.96	RDS COMM CABLE	200.000	L.F.
725-22.22	CONDUIT BANK (TYPE 2)	825.000	L.F.
725-22.24	CONDUIT BANK (TYPE 4)	5,545.000	L.F.
725-22.32	CONDUIT BANK BORED (TYPE 2)	75.000	L.F.
725-22.34	CONDUIT BANK BORED (TYPE 4)	3,560.000	L.F.
725-22.50	DMS CONDUIT BANK	75.000	L.F.
725-22.64	STRUCTURE CONDUIT BANK (TYPE 4)	215.000	L.F.
725-22.71	2IN CONDUIT	450.000	L.F.
725-22.72	2IN CONDUIT BORED	2,210.000	L.F.
725-22.74	2IN CONDUIT W/BANK	525.000	L.F.
725-22.75	2IN CONDUIT BORED W/BANK	190.000	L.F.
725-23.01	ITS CABLE MARKER	35.000	EACH

Contract ID CNX307 - MADISON

Item No.	Description	Quantity	Units
725-23.02	FIBER OPTIC TESTING	(1)	LS
725-23.16	FIBER OPTIC CABLE (144F)	29,005.000	L.F.
725-23.21	FIBER OPTIC DROP CABLE (12 F)	1,525.000	L.F.
725-23.26	FIBER OPTIC CLOSURE (12 F)	5.000	EACH
725-23.27	FIBER OPTIC CLOSURE (DESCRIPTION) (144F)	2.000	EACH
725-23.28	FIBER OPTIC SPLICE FUSION	308.000	EACH
725-23.31	FIBER OPTIC DROP PANEL (12 F)	5.000	EACH
725-24.02	CABINET (TYPE B)	4.000	EACH
725-24.03	CABINET (TYPE C)	1.000	EACH
725-24.21	PREVENTIVE MAINTENANCE FOR SYSTEM	(1)	LS
725-24.41	BURN-IN PERIOD	(1)	LS
725-24.51	SYSTEM INTEGRATION	(1)	LS
725-24.55	AS-BUILT PLANS	(1)	LS
725-24.61	TRAINING	(1)	LS
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	180.000	L.F.
801-01	SEEDING (WITH MULCH)	42.000	UNIT
801-03	WATER (SEEDING & SODDING)	5.000	M.G.

() Item will be bid as lump sum.

Contract ID CNX101 - MONTGOMERY

Contract ID: CNX101

Letting Date: August 18, 2023 10:00 AM

Projects: 63023-4241-04

N/A

Counties: MONTGOMERY

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 149 over Yellow Creek (L.M. 1.53).

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 63-SR149-1.53)	(1)	LS
204-06.01	FLOWABLE FILL (GENERAL)	5.200	C.Y.
204-11	BRIDGE EXCAVATION (UNCLASSIFIED)	324.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	360.000	L.F.
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE)	561.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	25.800	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	16.900	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.300	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	0.800	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	228.100	TON
411-01.10	ACS MIX(PG64-22) GRADING D	212.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	3,040.000	S.Y.
604-03.04	PAVEMENT @ BRIDGE ENDS	251.000	S.Y.
604-03.74	CLASS X CONCRETE	332.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	609.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,305.000	S.Y.
604-10.05	CONCRETE	5.000	S.F.
604-10.18	REINFORCING STEEL (REPAIRS)	121,074.738	LB.
604-10.54	CONCRETE REPAIRS	19.000	S.F.

Contract ID CNX101 - MONTGOMERY

Item No.	Description	Quantity	Units
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	538.000	L.F.
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	360.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	560.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	15.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	21.000	EACH
712-06	SIGNS (CONSTRUCTION)	396.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	9,720.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.800	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,045.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	418.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX296 - OBION

Contract ID: CNX296

Letting Date: August 18, 2023 10:00 AM

Projects: 66945-3469-94

HSIP-6600(25)

Counties: OBION

District:

DBE Goal Percent: 2.00

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 4/30/2024

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	580.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	8.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,015.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	940.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,480.000	LB.
713-11.21	P POST SLIP BASE	134.000	EACH
713-11.22	U POST SLIP BASE	30.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	679.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	715.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	75.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	325.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	57.300	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	3,765.000	L.F.
717-01	MOBILIZATION	(1)	LS
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (D)	70.000	TON

() Item will be bid as lump sum.

Contract ID CNX303 - SHELBY

Contract ID: CNX303

Letting Date: August 18, 2023 10:00 AM

Projects: 79060-3503-94

HSIP-2823(4)

Counties: SHELBY

District:

DBE Goal Percent: 9.50

Description: The construction of a roundabout on New Allen Road at Ridgemont Road (L.M. 6.19), including construction of a concrete box bridge.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,215.000	C.Y.
203-06	WATER	98.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	594.000	C.Y.
209-05	SEDIMENT REMOVAL	153.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	286.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.01	SANDBAGS	900.000	BAG
209-09.41	CURB INLET PROTECTION (TYPE 2)	3.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	1,500.000	S.Y.
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	4.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	16.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	6,135.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (DESCRIPTION)	161.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	8.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	278.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM)	1,495.000	TON

Contract ID CNX303 - SHELBY

Item No.	Description	Quantity	Units
	GRADING B-M2		
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,427.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	935.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	14.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	53.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	31.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	548.000	TON
415-01.03	COLD PLANING BITUMINOUS PAVEMENT	19.000	C.Y.
606-24.12	TEMPORARY SHEET PILES	30,000.000	S.F.
607-03.30	18" PIPE CULVERT	679.000	L.F.
607-05.30	24" PIPE CULVERT	160.000	L.F.
607-06.30	30" PIPE CULVERT	200.000	L.F.
607-39.01	15" PIPE CULVERT (SIDE DRAIN)	36.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-14.01	CATCH BASINS, TYPE 14, 0' - 4' DEPTH	2.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	12.000	EACH
611-14.03	CATCH BASINS, TYPE 14, > 8' - 12' DEPTH	2.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	2.000	EACH
611-42.03	CATCH BASINS, TYPE 42, > 8' - 12' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	120.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	60.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	11,005.000	S.F.
701-02	CONCRETE DRIVEWAY	9,942.000	S.F.
701-02.03	CONCRETE CURB RAMP	2,152.000	S.F.
702-01	CONCRETE CURB	98.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	189.000	C.Y.
703-02	CEMENT CONCRETE DITCH PAVING (REINFORCED)	46.000	C.Y.

Contract ID CNX303 - SHELBY

Item No.	Description	Quantity	Units
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	625.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,000.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	45.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,600.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	497.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	497.000	EACH
712-06	SIGNS (CONSTRUCTION)	378.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	140.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	10,400.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	10,400.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	852.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,006.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	403.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	500.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	1.250	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	6.000	L.F.
716-04.03	PLASTIC PAVEMENT MARKING (4" DOTTED LINE)	186.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	390.000	S.F.
716-04.17	PLASTIC PAVEMENT MARKING (YIELD SYMBOL)	84.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	549.000	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	28,379.000	L.F.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	672.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	124.000	L.F.

Contract ID CNX303 - SHELBY

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	108.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,924.000	L.F.
801-03	WATER (SEEDING & SODDING)	90.000	M.G.
803-01	SODDING (NEW SOD)	9,002.000	S.Y.
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	8,505.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	710.000	C.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	7,919.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	58.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	6,983.000	LB.
607-50.12	PRECAST CONCRETE BOX CULVERT (SIZE) (2 @ 16' x 12')	928.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX121 - SHELBY

Contract ID: CNX121

Letting Date: August 18, 2023 10:00 AM

Projects: 79052-4230-04

NA

Counties: SHELBY

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 177 over the Wolf River (L.M. 4.68).

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	400.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	189.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	80.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,200.000	S.Y.
604-05.32	BRIDGE DECK GRINDING AND GROOVING	8,960.000	S.Y.
604-10.05	CONCRETE	75.000	S.F.
604-10.07	CONCRETE REMOVAL	(1)	LS
604-10.12	CONCRETE SLAB REPAIRS	294.000	C.Y.
604-10.18	REINFORCING STEEL (REPAIRS)	47,890.000	LB.
604-10.20	HYDRODEMOLITION	8,674.000	S.Y.
604-10.26	BRACING	1.000	EACH
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	176.000	S.Y.
604-10.42	CONCRETE REPAIRS	375.000	C.F.
604-10.43	PENETRATING WATER REPELLENT CONCRETE SEAL	1,369.000	S.Y.
604-10.45	EXPANSION JOINT REPAIRS (TYPE F)	232.000	L.F.
604-10.46	EXPANSION JOINT REPAIRS (TYPE G)	232.000	L.F.
604-10.54	CONCRETE REPAIRS	75.000	S.F.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	161.000	L.F.
604-10.67	CONCRETE REPAIRS (DESCRIPTION) (SAW	3,208.000	L.F.

Contract ID CNX121 - SHELBY

Item No.	Description	Quantity	Units
	CUTTING)		
604-10.83	COMPOSITE FIBER ENCASMENT	606.000	S.F.
606-03.03	STEEL PILES (12 INCH)	960.000	L.F.
619-01	BRIDGE DECK OVERLAY (PMC)	8,421.000	S.Y.
619-01.35	BRIDGE DECK OVERLAY (PMC)	36.000	C.Y.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	89.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	13.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	1.000	EACH
705-10.30	GUARDRAIL ATTACHMENT TO SLOPE FACE ENDPOST	26.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	300.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	970.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	107.000	EACH
712-06	SIGNS (CONSTRUCTION)	730.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	150.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	3,460.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	1.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.500	L.M.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	6.000	M.G.
803-01	SODDING (NEW SOD)	600.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX298 - SHELBY

Contract ID: CNX298

Letting Date: August 18, 2023 10:00 AM

Projects: 79I040-S8-014

N/A

Counties: SHELBY

District:

DBE Goal Percent:

Description: The resurfacing on I-40 from near the Wolf River (L.M. 14.73) to near Sycamore View Road (L.M. 16.13).

Contract Time: DT - 8/30/2024

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	134.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	23.000	S.Y.
203-06	WATER	2.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	2.800	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	212.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	11.000	TON
403-02.01	TRACKLESS TACK COAT	68.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	18.600	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	12,194.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	5.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,079.000	TON
701-01.01	CONCRETE SIDEWALK (4 ")	1,215.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	1,456.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	500.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	518.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	184.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,343.000	S.F.

Contract ID CNX298 - SHELBY

Item No.	Description	Quantity	Units
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-07.02	TEMPORARY BARRICADES (TYPE II)	60.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	20.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,046.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,046.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	46.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,022.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	238.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	10.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	1.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	10.800	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	4.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	10.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	4,214.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	567.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	1,027.000	L.F.

Contract ID CNX298 - SHELBY

Item No.	Description	Quantity	Units
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	1,343.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	857.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.21	INSTALL PULL BOX (TYPE B)	1.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	10.000	L.F.
730-14.02	SAW SLOT	224.000	L.F.
730-14.03	LOOP WIRE	498.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX299 - SHELBY

Contract ID: CNX299

Letting Date: August 18, 2023 10:00 AM

Projects: 79S014-M3-007

N/A

Counties: SHELBY

District:

DBE Goal Percent:

Description: The repair of the bridge on U.S. 61 (S.R. 14) over I-55 (L.M. 7.46).

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (Bridge No. 79-I55-7.46)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	250.000	L.F.
604-02.03	EPOXY COATED REINFORCING STEEL	2,925.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	19.000	C.Y.
604-03.60	BRIDGE JOINT SEISMIC MODIFICATION (DESCRIPTION) (DESCRIPTION)	2.000	EACH
604-10.05	CONCRETE	17.000	S.F.
604-10.54	CONCRETE REPAIRS	14.000	S.F.
604-10.83	COMPOSITE FIBER ENCASMENT	160.000	S.F.
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	58.000	L.F.
620-06	CONCRETE RAILING	75.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	250.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	120.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	45.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,066.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	160.000	L.F.

Contract ID CNX299 - SHELBY

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.14	PORTABLE QUEUE WARNING SYSTEM	28.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	3,100.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.150	L.M.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	5.500	M.G.
803-01	SODDING (NEW SOD)	550.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX311 - VAN BUREN

Contract ID: CNX311

Letting Date: August 18, 2023 10:00 AM

Projects: 88945-3453-94

HSIP-8800(14)

Counties: VAN BUREN

District:

DBE Goal Percent: 6.50

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	350.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	20.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	136.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	594.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	624.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,785.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	297.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	614.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	61.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	733.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	130.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	172.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	28.000	S.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	96.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	44.560	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	660.000	L.F.

Contract ID CNX311 - VAN BUREN

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
406-04.02	HIGH FRICTION SURFACE TREATMENT	1,625.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX297 - WEAKLEY

Contract ID: CNX297

Letting Date: August 18, 2023 10:00 AM

Projects: 92002-3233-94

PHSIP-22(94)

Counties: WEAKLEY

District:

DBE Goal Percent: 8.00

Description: The miscellaneous safety improvements on S.R. 22 from near Dresden Elementary School to near S.R. 54 (L.M. 12.38 - L.M. 13.10), and on Linden Street from near Southfield Lane to S.R. 22 in Dresden.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	38.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (DESCRIPTION)	70.000	L.F.
604-01.01	CLASS A CONCRETE (ROADWAY)	8.000	C.Y.
701-01.02	CONCRETE SIDEWALK (6 ")	340.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	200.000	S.F.
702-01	CONCRETE CURB	4.250	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	2.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	84.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	894.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,062.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	34.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	356.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	32.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	286.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	65.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	70.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH

Contract ID CNX297 - WEAKLEY

Item No.	Description	Quantity	Units
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	72.000	S.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	70.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (DESCRIPTION)	4.000	EACH
716-10.30	TRUNCATED DOME DETECTABLE WARNING MAT	32.000	S.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	1.250	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.08	SCHOOL SPEED LIMIT FLASHING SIGNAL INSTALLED	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNX301 - WILSON

Contract ID: CNX301

Letting Date: August 18, 2023 10:00 AM

Projects: 95013-3222-14

STP-141(16)

Counties: WILSON

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, construction of concrete box bridges and paving on S.R. 141 (Hartsville Pike) from north of Lovers Lane (L.M. 8.71) to U.S. 70 (S.R. 26) (L.M. 10.50).

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	4,500.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (SIZE VARIES , STA. VARIES)	359.000	L.F.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CATCH BASIN, STA. VARIES)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRICK MONUMENTS, STA. 437+00 AND STA. 437+50)	(1)	LS
202-04.03	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (SMALL WOODEN BILLBOARD, STA. 431+30)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	44,293.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	48,623.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	94,907.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	7,522.000	C.Y.
203-05	UNDERCUTTING	28,189.000	C.Y.
203-06	WATER	714.000	M.G.
204-06.01	FLOWABLE FILL (GENERAL)	223.000	C.Y.
209-02.03	8" TEMPORARY SLOPE DRAIN	15.000	L.F.
209-02.05	12" TEMPORARY SLOPE DRAIN	399.000	L.F.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
209-02.06	15" TEMPORARY SLOPE DRAIN	45.000	L.F.
209-02.07	18" TEMPORARY SLOPE DRAIN	4,343.000	L.F.
209-03.21	FILTER SOCK (12 INCH)	1,336.000	L.F.
209-05	SEDIMENT REMOVAL	1,375.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	868.000	L.F.
209-08.07	ROCK CHECK DAM	62.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	72.000	EACH
209-09.40	CURB INLET PROTECTION (TYPE 1)	16.000	EACH
209-09.41	CURB INLET PROTECTION (TYPE 2)	185.000	EACH
209-10.20	TEMPORARY SEDIMENT TRAP	563.000	C.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	8.000	EACH
209-40.31	CATCH BASIN PROTECTION (TYPE B)	6.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	6.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	68,041.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	973.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	11,671.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	14,893.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	11,759.000	TON
307-01.20	ASP. CONC. MIX(PG64-22) (BPMB-HM) GR. A-S	10,075.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	149.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	527.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	37.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,144.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	584.000	TON
607-02.02	15" CONCRETE PIPE CULVERT(CLASS III)	39.000	L.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	8,636.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	2,660.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	220.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	388.000	L.F.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
607-39.01	15" PIPE CULVERT (SIDE DRAIN)	29.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	460.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	42.000	L.F.
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	86.000	L.F.
607-39.05	36" PIPE CULVERT (SIDE DRAIN)	160.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-01.03	MANHOLES, > 8' - 12' DEPTH	1.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	6.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	9.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.66	42IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.67	42IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-09.02	REWORK CATCHBASIN	2.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	68.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	3.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	27.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	1.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	2.000	EACH
611-40.02	CATCH BASINS, TYPE 40, > 4' - 8' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	5.000	EACH
621-03.01	15" TEMPORARY DRAINAGE PIPE	250.000	L.F.
621-03.02	18" TEMPORARY DRAINAGE PIPE	650.000	L.F.
621-03.07	48" TEMPORARY DRAINAGE PIPE	152.000	L.F.
621-03.10	66" TEMPORARY DRAINAGE PIPE	163.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	114,670.000	S.F.
701-02	CONCRETE DRIVEWAY	16,749.000	S.F.
701-02.03	CONCRETE CURB RAMP	3,028.000	S.F.
701-03	CONCRETE MEDIAN PAVEMENT	9.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	1,498.000	C.Y.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
705-08.11	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	11.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	650.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1,575.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	1,307.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,741.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	15,725.000	L.F.
710-05	LATERAL UNDERDRAIN	948.000	L.F.
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	79.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	9,470.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	112.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	131.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,163.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	315.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.05	REMOVABLE PAVEMENT MARKING (ARROW)	7.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	0.200	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	91.000	LB.
713-11.01	"U" SECTION STEEL POSTS	2,926.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	143.000	LB.
713-11.21	P POST SLIP BASE	4.000	EACH
713-11.22	U POST SLIP BASE	87.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	420.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	373.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK)	142.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
713-16.07	END OF ROADWAY SIGN AND SUPPORT	4.000	EACH
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	11,315.000	L.F.
714-03.03	DIRECT BURIAL CONDUIT (DESCRIPTION) (2" PVC, SCHEDULE 80)	950.000	L.F.
714-06.06	CABLE (1/C # 4 AWG)	38,050.000	L.F.
714-06.09	CABLE (DESCRIPTION) (#6 SOLID COPPER SOFT DRAWN)	150.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (MOUNTING HEIGHT 25' ALUMINUM)	1.000	EACH
714-08.11	LIGHT STANDARDS (DESCRIPTION) (MOUNTING HEIGHT 30' ALUMINUM)	41.000	EACH
714-08.20	FOUNDATION (ONLY) FOR LIGHT STANDARD	1.000	EACH
714-08.21	FOUNDATION (ONLY) FOR LIGHT STANDARD	41.000	EACH
714-09.09	LUMINAIRES (DESCRIPTION) (50 WATT LED)	4.000	EACH
714-09.10	LUMINAIRES (DESCRIPTION) (50 WATT LED ON UTILITY POLE BY OTHERS)	1.000	EACH
714-09.11	LUMINAIRES (DESCRIPTION) (50 WATT LED ON SIGNAL POLE BY OTHERS)	1.000	EACH
714-09.12	LUMINAIRES (DESCRIPTION) (120 WATT LED)	38.000	EACH
714-09.13	LUMINAIRES (DESCRIPTION) (120 WATT LED ON UTILITY POLE BY OTHERS)	6.000	EACH
714-09.14	LUMINAIRES (DESCRIPTION) (120 WATT LED ON SIGNAL POLE BY OTHERS)	3.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (PSA)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (PSB)	(1)	LS
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	732.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	241.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	268.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	904.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	515.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,035.000	L.F.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	384.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	742.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.200	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	7.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,050.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	105.000	S.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	35.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	12.600	L.M.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	92.000	S.Y.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	63,995.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	92.000	S.Y.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	1.000	EACH
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,130.000	L.F.
716-08.23	REMOVAL OF PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-08.24	REMOVAL OF PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	12.900	L.M.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	11.000	EACH
730-02.14	SIGNAL HEAD ASSEMBLY (140 A1 WITH BACKPLATE)	2.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	12.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	3.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	2,335.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,930.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	285.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	270.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	150.000	L.F.
730-12.08	CONDUIT 2" DIAMETER (RGS)	60.000	L.F.
730-12.09	CONDUIT 3" DIAMETER (RGS)	350.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	340.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	95.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (RADAR - STOP LINE)	7.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	5.000	EACH
730-15.30	CABINET (FOUR PHASE POLE MOUNTED)	1.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	3.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	7.000	EACH
730-23.88	CANTILEVER SIGNAL SUPPORT (1 ARM @ 45')	1.000	EACH
730-24.94	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 70')	1.000	EACH
730-25.03	CANTILEVER SIGNAL SUPPORT (2 @ 50' & 55')	1.000	EACH
730-25.08	CANTILEVER SIGNAL SUPPORT (2 @ 55' & 55')	1.000	EACH
730-25.10	CANTILEVER SIGNAL SUPPORT (2 @ 55' & 65')	1.000	EACH
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	14.000	EACH
730-50.25	PEDESTRIAN HYBRID BEACON ASSEMBLY	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	3,854.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	17,000.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	63,271.000	L.F.
791-05.73	12IN STEEL CASING	283.000	L.F.
801-01	SEEDING (WITH MULCH)	86.200	UNIT
801-03	WATER (SEEDING & SODDING)	51.000	M.G.
802-01.10	TREES (DESCRIPTION) (JUNIPERUS VIRGINIANA 'CANAERTII' (EAST. RED CEDAR, 2-5 CNT GRWN)	206.000	EACH
803-01	SODDING (NEW SOD)	49,832.000	S.Y.
805-01.02	TURF REINFORCEMENT MAT (CLASS II)	180.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	13,895.000	S.Y.
806-02.03	PROJECT MOWING	9.000	CYCL
204-08	FOUNDATION FILL MATERIAL	191.000	C.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	286.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	64,154.000	LB.
790-02.01	POLE 35FT CLASS 2 WOOD	5.000	EACH
790-03.01	POLE 40FT CLASS 2 WOOD	4.000	EACH
790-04.02	POLE 45FT CLASS 2 WOOD	2.000	EACH
790-04.04	POLE 45FT CLASS 4 WOOD	3.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	18.000	EACH
790-05.08	POLE 50FT CLASS H2 METAL	1.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	2.000	EACH
790-06.08	POLE 55FT CLASS H2 METAL	18.000	EACH
790-07.06	POLE 60FT CLASS 2 METAL	4.000	EACH
790-08.04	POLE 65FT CLASS H2 METAL	2.000	EACH
790-20.90	METAL TAG INSTALLATION	43.000	EACH
790-22.01	1PH SGL PRIMARY SUPPORT 25KV	1.000	EACH
790-22.07	1PH DBL PTS ANGLE 25KV	1.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
790-22.13	1PH DEAD END 25KV	3.000	EACH
790-22.15	1PH DEAD END TAP W/ EXTENSION 25KV	7.000	EACH
790-26.02	3PH CROSSARM DBL LRG COND 25KV	1.000	EACH
790-26.03	3PH CROSSARM SGL LRG COND 25KV	10.000	EACH
790-26.04	3PH CROSSARM SGL LRG COND ON ST POLE 25KV	10.000	EACH
790-26.11	3PH VERTICAL TANGENT SM ANGLE 25KV	1.000	EACH
790-26.15	3PH XARM DBL 10FT LRG COND SM ANGLE 25KV	10.000	EACH
790-26.16	3PH XARM FBRGLS LRG COND MED ANGLE 25KV	5.000	EACH
790-26.20	3PH VERTICAL ANGLE LRG COND 25KV	4.000	EACH
790-26.22	3PH VERTICAL DDE ANGLE LRG COND 25KV	1.000	EACH
790-26.24	3PH VERTICAL DEAD END LRG COND 25KV	7.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	2.000	EACH
790-26.27	3PH CROSSARM DBL DDE 25KV	1.000	EACH
790-26.28	3PH DBL 10FT XARM DDE 25KV	1.000	EACH
790-30.01	SECONDARY ASSEMBLIES SMALL ANGLE	2.000	EACH
790-30.02	SECONDARY ASSEMBLIES LRG ANGLE	2.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	17.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	24.000	EACH
790-32.06	DOWN GUY - INSULATED	4.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	17.000	EACH
790-32.19	DN GUY HVY CONST - 1 PREFORM	78.000	EACH
790-33.17	ROCK ANCHOR EXPANDING TYPE	5.000	EACH
790-33.19	ROCK ANCHOR TRIPLE EYE 53IN EXPANDING	6.000	EACH
790-33.21	ANCHOR TWIN EYE POWER INSTALLED	45.000	EACH
790-36.13	TRANSFER STREET LIGHT	13.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	2,814.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	1,518.000	L.F.
790-40.05	OH COND 3/0 6/1 ACSR PIGEON	15,955.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	150.000	L.F.
790-40.49	OH COND 795 37 AAC ARBUTUS	47,715.000	L.F.

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
790-41.46	UG SEC COND 1/0 AL TPLX	663.000	L.F.
790-41.49	UG SEC COND 4/0 AL TPLX	358.000	L.F.
790-42.13	CONDUIT - POLE MTD - 3IN SCH 80 PVC	23.000	L.F.
790-42.16	1 DUCT @ 36IN-48IN DEPTH	50.000	L.F.
790-43.26	SPLICE 200A 25KV	1.000	EACH
790-43.27	OUTDOOR TERMINATOR URD 25KV	1.000	EACH
790-43.46	SECONDARY PULLBOX LARGE	16.000	EACH
790-43.47	PRIMARY PULLBOX	1.000	EACH
790-46.01	1PH TRANSFORMER	8.000	EACH
790-59.03	CUTOUT KNIFE SWITCH-SNGL LOADBREAK 25KV	2.000	EACH
790-59.05	GOLB SWITCH 25KV	2.000	EACH
790-61.01	1PH FUSE CUTOUT XARM MOUNT 25KV	36.000	EACH
790-61.10	3PH SECTLR OR RECL W/ BYPASS SW 25KV	2.000	EACH
790-61.11	3PH SECTLR OR RECL W/ BYP SW ELECTC 25KV	2.000	EACH
790-65.05	LIGHTNING ARRESTER ARM MTD 18 KV	36.000	EACH
790-65.07	LIGHTNING ARRESTOR 18KV INTERMEDIATE	1.000	EACH
790-68.12	LARGE BRACES	1.000	EACH
790-68.13	SGL PHASE MOUNTING BRACKET - FIBERGLASS	11.000	EACH
790-69.06	HARDWARE FOR SGL PH CONV TRANS	22.000	EACH
790-69.08	GROUND-GROUND ROD	23.000	EACH
790-69.12	GROUND ASSEMBLY GROUND PLATE TYPE	25.000	EACH
790-69.22	POLE TOP PIN	1.000	EACH
790-69.26	EXTENSION LINK - EPOXY -1FT	9.000	EACH
790-69.27	EXTENSION LINK - EPOXY -4FT	4.000	EACH
790-69.28	EXTENSION LINK - EPOXY -6FT	24.000	EACH
790-69.32	ARM PIN	4.000	EACH
790-71.17	HOR LN POSTS NO OHGW 69KV MAX	1.000	EACH
790-98.01	REMOVE WIRE	39,419.000	L.F.
790-98.02	REMOVE POLES	36.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	378.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
791-01.11	6IN PVC CASING OPEN CUT	810.000	L.F.
791-02.01	<2IN MDPE GAS MAIN	200.000	L.F.
791-02.02	2IN MDPE GAS MAIN	1,800.000	L.F.
791-02.04	4IN MDPE GAS MAIN	10,650.000	L.F.
791-04.01	HDD <2IN PE PIPE - UNCONSOLIDATED	2,200.000	L.F.
791-04.02	HDD 2IN PE PIPE - UNCONSOLIDATED	50.000	L.F.
791-04.04	HDD 4IN PE PIPE - UNCONSOLIDATED	100.000	L.F.
791-05.40	BORE/JACK 6IN - PVC CASING PIPE	295.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	6.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	2.000	EACH
791-06.09	CONNECT TO __IN EX. PE MAIN (3)	2.000	EACH
791-06.31	CONNECT TO 2IN EX. STL MAIN W/ STOPPLE	4.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	6.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	24.000	EACH
791-08.06	1/2IN PE SERVICE PIPE	40.000	L.F.
791-08.07	3/4IN PE SERVICE PIPE	3,300.000	L.F.
791-08.16	HDD 1/2IN PE SERVICE PIPE	40.000	L.F.
791-08.17	HDD 3/4IN PE SERVICE PIPE	200.000	L.F.
791-08.40	RECONNECT SERVICE ASSEMBLY	74.000	EACH
791-09.05	RESTORE ASPHALT	5.000	S.Y.
791-11.01	CLASS A CONCRETE	2.000	C.Y.
793-01.08	POLE 35FT CLASS 5 WOOD	1.000	EACH
793-01.12	POLE 40FT CLASS 4 WOOD	5.000	EACH
793-01.39	ANCHOR 5/8IN	9.000	EACH
793-01.40	ANCHOR 3/4IN	13.000	EACH
793-01.41	ANCHOR 1IN	26.000	EACH
793-01.99	INSTALL POLE NUMBER	40.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	18.000	EACH
793-02.92	OVERHEAD GUY WIRE (DESCRIPTION) (10M)	5.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
793-02.99	INSTALL GUY GUARD	20.000	EACH
793-03.40	INSTALL STRAND BOND	40.000	EACH
793-03.41	AERIAL CABLE (DESCRIPTION) (288, Fiber, 6M Strand)	8,550.000	L.F.
793-03.41	AERIAL CABLE (DESCRIPTION) (288, Fiber, Maintenance Loop)	1,700.000	L.F.
793-03.41	AERIAL CABLE (DESCRIPTION) (48, Fiber, E-Lash)	2,900.000	L.F.
793-03.41	AERIAL CABLE (DESCRIPTION) (48, Fiber, Maintenance Loop)	550.000	L.F.
793-04.07	AERIAL SPLICE CLOSURE (8)	3.000	EACH
793-04.07	AERIAL SPLICE CLOSURE (9T)	7.000	EACH
793-07.23	FIBER OPTIC MAINTENANCE LOOP	17.000	EACH
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	700.000	EACH
793-11.50	REARRANGE EXISTING SPLICE CASE	1.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	2,064.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	438.000	L.F.
793-13.22	3 DUCT FORMATION @ 36IN DEPTH	396.000	L.F.
793-14.19	4IN SCH 80 ORANGE FLEXPIPE	1,040.000	L.F.
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	1,040.000	L.F.
793-98.01	REMOVE AERIAL CABLE AND WIRE	9,500.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	49.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	11.000	EACH
793-98.09	REMOVE DOWN GUY	15.000	EACH
795-01.06	8IN DIP SLIP JOINT WATER LINE	550.000	L.F.
795-01.08	10IN DIP SLIP JOINT WATER LINE	5,775.000	L.F.
795-01.14	16IN DIP SLIP JOINT WATER LINE	3,100.000	L.F.
795-03.05	6IN PVC WATER LINE	1,750.000	L.F.
795-05.68	BORE/JACK 24IN STEEL CASING PIPE-UNCON.	45.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	5.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	2.000	EACH
795-06.09	CONNECT TO 16IN WATER LINE	2.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
795-07.21	16IN X 16IN TAPPING SLEEVE AND VALVE	6.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	14.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	3.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	8.000	EACH
795-08.13	16IN BUTTERFLY VALVE ASSEMBLY	2.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	50.000	EACH
795-09.51	RECONNECT SERVICE ASSEMBLY	25.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	3,000.000	L.F.
795-09.64	2IN PEXa SERVICE PIPE	1,750.000	L.F.
795-10.03	1IN AUTO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	16.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	7,300.000	L.F.
795-13.01	DI FITTINGS	17,000.000	LB.
795-14.03	CLASS C CONCRETE	30.000	C.Y.
795-14.08	RESTORE ASPHALT	5.000	S.Y.
795-15.02	12IN STEEL CASING PIPE OPEN CUT METHOD	125.000	L.F.
795-15.04	18IN STEEL CASING PIPE OPEN CUT METHOD	280.000	L.F.
795-15.07	24IN STEEL CASING PIPE OPEN CUT METHOD	440.000	L.F.
797-03.06	4IN PVC FORCE MAIN	1,475.000	L.F.
797-05.55	10IN PVC GRAVITY SEWER 0FT-6FT DEPTH	475.000	L.F.
797-05.56	10IN PVC GRAVITY SEWER 6FT-12FT DEPTH	100.000	L.F.
797-06.87	OPEN CUT 8IN STEEL CASING PIPE	230.000	L.F.
797-06.91	OPEN CUT 18IN STEEL CASING PIPE	185.000	L.F.
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	2.000	EACH
797-07.60	ADJUST EXISTING MANHOLE	5.000	EACH
797-08.01	DI FITTINGS	400.000	LB.
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	40.000	L.F.
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	1.000	EACH
797-09.18	3/4IN COMBO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
797-09.44	CUT AND CAP 8IN GRAVITY	2.000	EACH

Contract ID CNX301 - WILSON

Item No.	Description	Quantity	Units
797-10.03	CONNECT 10-18IN SEWER TO EXIST. MANHOLE	1.000	EACH
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	2.000	EACH
797-10.16	CONNECT TO 4IN FORCE MAIN	4.000	EACH
797-11.15	48IN MH ADJUSTMENT INCREASE HEIGHT	15.000	V.F.
797-11.25	REIREIN PLACE 48IN MANHOLE	1.000	EACH
797-11.31	REIREIN PLACE EXISTING SEWER 8IN-14IN	380.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.40	RESTORE ASPHALT	12.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX910 - RUTHERFORD , SUMNER, ETC.

Contract ID: CNX910

Letting Date: August 18, 2023 10:00 AM

Projects: R3SVAR-M3-054

N/A

R3SVAR-M3-055

N/A

Counties: RUTHERFORD, SUMNER, WILSON

District:

DBE Goal Percent:

Description: The mowing and litter removal on various State Routes.

Contract Time: DT - 3/31/2024

Item No.	Description	Quantity	Units
717-10.01	INVOLUNTARY WORK SUSPENSION (DESCRIPTION)(BY THE DAY)	3.000	DAY
719-02	REMOVAL AND DISPOSAL OF LITTER	258.000	L.M.
806-01	MOWING	4,315.000	ACRE

() Item will be bid as lump sum.