

Estimated Quantities -- Letting December 06, 2024

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNY905 - GRAINGER

Contract ID: CNY905

Letting Date: December 06, 2024 10:00 AM

Projects: 29007-3221-94

BR-STP-131(50)

Counties: GRAINGER

District:

DBE Goal Percent: 8.50

Description: The construction of a concrete box bridge on S.R. 131 over Williams Creek (L.M. 7.73), including grading, drainage, and paving.

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (EXISTING SIDE DRAIN AT STA. 102+85.79)	53.000	L.F.
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING 2-48" CMP PIPES, STA. 104+64)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 3)	(1)	LS
202-06.02	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 4 / 8004)	(1)	LS
202-06.03	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 6)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,544.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	741.000	C.Y.
203-06	WATER	30.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	196.000	C.Y.
209-03.31	STREAM MITIGATION-COCONUT FIBER ROLLS	307.000	L.F.
209-05	SEDIMENT REMOVAL	114.000	C.Y.

Contract ID CNY905 - GRAINGER

Item No.	Description	Quantity	Units
209-06.02	12" DIA COIR LOG (DESCRIPTION) (LOW FLOW CHANNEL)	163.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	990.000	L.F.
209-08.07	ROCK CHECK DAM	4.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	12.000	EACH
209-09.01	SANDBAGS	820.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	1.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	32.000	S.Y.
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	1.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	85.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,187.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	219.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	55.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	720.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	596.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	8.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	390.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	13.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	45.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	7,917.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	70.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	136.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	1.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	45.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	5.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-03.07	48" TEMPORARY DRAINAGE PIPE	62.000	L.F.
701-02	CONCRETE DRIVEWAY	36.000	S.F.

Contract ID CNY905 - GRAINGER

Item No.	Description	Quantity	Units
702-01	CONCRETE CURB	3.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	125.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	412.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	7.000	EACH
706-01	GUARDRAIL REMOVED	407.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	302.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	20.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	434.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	480.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	3,253.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	54.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	214.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	30.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	50.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	6,656.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	3,957.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (STOP, R1-1, 36"X36")	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	18.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	18.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	16.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.

Contract ID CNY905 - GRAINGER

Item No.	Description	Quantity	Units
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.100	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,657.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,544.000	L.F.
801-01	SEEDING (WITH MULCH)	3.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	67.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	44.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	31.000	UNIT
801-03	WATER (SEEDING & SODDING)	20.000	M.G.
803-01	SODDING (NEW SOD)	1,258.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	3,379.000	S.Y.
202-04.51	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BOX BRIDGE, STA. 109+88.84)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	440.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	157.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	33,737.000	LB.
790-02.04	POLE 35FT CLASS 5 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	2.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	2.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	2.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	2.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	3.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	2.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	10.000	EACH
790-30.13	SECONDARY CONDUCTOR 2 AL TRIPLEX	97.000	L.F.
790-30.14	SECONDARY CONDUCTOR 1/0 AL TRIPLEX	166.000	L.F.
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	10.000	EACH

Contract ID CNY905 - GRAINGER

Item No.	Description	Quantity	Units
790-33.20	ANCHOR TRIPLE EYE POWER INSTALLED	7.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	1.000	EACH
790-36.13	TRANSFER STREET LIGHT	1.000	EACH
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,324.000	L.F.
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	2.000	EACH
790-60.02	1PH FUSE CUTOFF BRKT MOUNT 15KV	2.000	EACH
790-68.01	POLE GROUND ROD TYPE	3.000	EACH
790-98.01	REMOVE WIRE	3,256.000	L.F.
790-98.02	REMOVE POLES	4.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	31.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
793-01.18	POLE 45FT CLASS 4 WOOD	4.000	EACH
793-01.40	ANCHOR 3/4IN	71.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	350.000	EACH
793-03.01	25 PAIR GROUP AERIAL SPLICE	1,200.000	EACH
793-03.03	10M STRAND	2,500.000	L.F.
793-03.12	50 PAIR CABLE	2,500.000	L.F.
793-03.14	100 PAIR CABLE	2,500.000	L.F.
793-03.18	400 PAIR CABLE	2,500.000	L.F.
793-03.41	AERIAL CABLE (DESCRIPTION) (1100 PAIR COPPER 22 GAUGE)	296.000	L.F.
793-04.01	RELASH/DELASH CABLE	500.000	L.F.
793-04.02	2 PAIR AERIAL DROP	30.000	L.F.
793-04.06	READY ACCESS CLOSURE	20.000	EACH
793-04.07	AERIAL SPLICE CLOSURE	10.000	EACH
793-04.25	HOT SPLICE EXISTING CABLES	1,200.000	EACH
793-07.05	96 FIBER(MATERIAL ONLY)	2,500.000	L.F.
793-07.16	12-96 FIBER(INSTALLATION ONLY)	192.000	L.F.
793-07.23	FIBER OPTIC MAINTENANCE LOOP	4.000	EACH
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	192.000	EACH

Contract ID CNY905 - GRAINGER

Item No.	Description	Quantity	Units
793-07.41	HOT SPLICE EXISTING FIBER CABLES	48.000	EACH
793-11.13	BURIED RISER GUARD	6.000	EACH
793-12.02	REARRANGEMENT EXISTING CABLE	3.000	EACH
793-14.24	LOAD COIL	2.000	EACH
793-15.01	TRANSFER CABLE ATTACHMENT	8.000	EACH
793-98.01	REMOVE AERIAL CABLE AND WIRE	8,500.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	6.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	16.000	EACH
795-03.35	8IN C900 PVC WATER LINE	400.000	L.F.
795-06.05	CONNECT TO 8IN WATER LINE	1.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	1.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	2.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	30.000	L.F.
795-10.31	2IN BLOW-OFF ASSEMBLY	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNY906 - HUMPHREYS

Contract ID: CNY906**Letting Date:** December 06, 2024 10:00 AM**Projects:** 43029-3409-94

BRZ-910(10)

Counties: HUMPHREYS**District:****DBE Goal Percent:** 8.50**Description:** The construction of a welded steel plate girder bridge on Bakerville Road over the Duck River (L.M. 15.71), including grading, drainage, and paving.**Contract Time:** DT - 8/31/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,200.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,797.000	C.Y.
203-01.77	ROAD AND DRAINAGE EXCAVATION (UNCLASS)	160.000	C.Y.
203-01.79	EXCAVATION/BACKFILL	390.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	30,700.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	9,110.000	C.Y.
203-06	WATER	75.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	190.000	C.Y.
203-10.01	EMBANKMENT (SOLID ROCK)	390.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-02.04	10" TEMPORARY SLOPE DRAIN	85.000	L.F.
209-03.30	STREAM MITIGATION (RIVER ROCK)	100.000	TON
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	60.000	L.F.
209-05	SEDIMENT REMOVAL	50.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (BANK STABILIZATION)	500.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,900.000	L.F.
209-08.07	ROCK CHECK DAM	3.000	EACH

Contract ID CNY906 - HUMPHREYS

Item No.	Description	Quantity	Units
209-08.08	ENHANCED ROCK CHECK DAM	3.000	EACH
209-08.09	FILTER SOCK CHECK DAM	3.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,517.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	19.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	1,400.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	691.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	453.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	7.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	21.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	4.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	266.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	1.000	L.M.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	56.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	48.000	L.F.
611-01.07	MANHOLES, > 24' - 28' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	3.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	138.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,700.000	L.F.
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	6.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	653.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,780.000	TON
710-04	FILTER CLOTH UNDERDRAIN (WITH PIPE)	360.000	L.F.
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	306.000	L.F.

Contract ID CNY906 - HUMPHREYS

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.36	REMOVE AND RELOCATE PORTABLE BARRIER RAIL	200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	160.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	20.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	383.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	20.000	L.F.
712-09.09	REMOVABLE PAVEMENT MARKING (4" line)	4,600.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	0.500	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	106.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	131.000	LB.
713-11.21	P POST SLIP BASE	4.000	EACH
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	62.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	32.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	0.250	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVT MRKNG (6IN LINE)	1.400	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.01	GEO GRID REINFORCEMENT	135.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	2,200.000	S.Y.
740-10.01	GEOTEXTILE (TYPE I)(SUBSURFACE DRAINAGE)	80.000	S.Y.

Contract ID CNY906 - HUMPHREYS

Item No.	Description	Quantity	Units
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	240.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,875.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,000.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	5.000	UNIT
801-03	WATER (SEEDING & SODDING)	190.000	M.G.
801-08	FERTILIZER (SUPPLEMENTAL APPLICATION)	0.300	TON
802-13.10	SAMBUCUS CANADENSIS (ELDERBERRY 2-5FT CNTNR GRWN)	360.000	EACH
802-16.01	SALIX NIGRA (BLACK WILLOW 3FT LIVE STAKES)	360.000	EACH
802-16.03	CEPHALANTHUS OCCIDENTALIS (BUTTONBUSH 3FT LIVE STAKES)	360.000	EACH
802-16.04	CORNUS AMOMUM (SILKY DOGWOOD 3FT LIVE STAKES)	360.000	EACH
803-01	SODDING (NEW SOD)	10,300.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	115.000	S.Y.
920-10.04	(DESCRIPTION) (OSPREY NEST PLATFORM)	1.000	EACH
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 43-0910-15.71)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	264.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	307.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	38.000	TON
602-04.01	STEEL STRUCTURES (LOCATION & DESCRIPTION) (BR. ID NO. 430A3160001, STA. 322+40.00)	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	212,591.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	283.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	77,414.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	140.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	718.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	2,380.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,400.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (ABUTMENT 2)	30.000	L.F.

Contract ID CNY906 - HUMPHREYS

Item No.	Description	Quantity	Units
606-03.03	STEEL PILES (12 INCH)	633.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	16.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE INLET-TYPE 1)	24.000	EACH
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	1,709.000	L.F.
625-01.10	CAMERA INSPECTION - DRILLED SHAFT (DRY)	2.000	EACH
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	4.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (5'-0" DIA.)	122.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (5'-0"/4'-6" DIA.)	56.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (5'-0" INSIDE DIAMETER)	157.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	251.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	66,378.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	115.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	46.000	L.F.
908-21.01	BEARINGS (DESCRIPTION) (ABUTMENT 2)	3.000	EACH
793-11.20	HANDHOLE 30INX48IN	2.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	3,755.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	1,727.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	194.000	L.F.
793-14.09	BRIDGE CONDUIT HANGER SYSTEM	(1)	LS
793-14.19	4IN SCH 80 ORANGE FLEXPipe	279.000	L.F.
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	279.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY279 - ANDERSON

Contract ID: CNY279**Letting Date:** December 06, 2024 10:00 AM**Projects:** 01004-3247-94**BR-STP/HIP-61(45)****Counties:** ANDERSON**District:****DBE Goal Percent:** 9.00**Description:** The construction of a concrete I-beam bridge on S.R. 61 over Brushy Creek (L.M. 3.98), including grading, drainage, and paving.**Contract Time:** DT - 9/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,680.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.56	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (TRACTS 11 & 12, SEPTIC)	(1)	LS
202-01.57	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (TRACT 15 CONC. DRIVEWAY)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACTS NO. 11 and 12)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,819.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	8,664.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	12,903.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,676.000	C.Y.
203-06	WATER	129.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	40.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-05	SEDIMENT REMOVAL	130.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,572.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	2,807.000	L.F.
209-08.07	ROCK CHECK DAM	42.000	EACH

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
209-08.08	ENHANCED ROCK CHECK DAM	35.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-10.01	TEMPORARY DEWATERING STRUCTURE	298.000	C.Y.
209-65.04	TEMPORARY IN STREAM DIVERSION	367.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	8,258.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	134.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	1,087.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,040.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	856.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	11.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	38.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	267.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	582.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	63.000	TON
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	136.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	79.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	421.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	38.000	L.F.
607-39.10	66" PIPE CULVERT (SIDE DRAIN)	47.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	6.640	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	662.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	19.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	4.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	60.000	L.F.

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
621-03.05	36" TEMPORARY DRAINAGE PIPE	615.000	L.F.
701-02	CONCRETE DRIVEWAY	830.000	S.F.
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,499.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.32	GR TERMINAL (GATING) (TYPE 21) MASH TL2	2.000	EACH
706-01	GUARDRAIL REMOVED	285.000	L.F.
706-06.03	RADIUS RAIL	280.000	L.F.
706-10.26	ROUNDED END ELEMENT	8.000	EACH
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	37.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	207.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	415.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	1,219.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	19.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	630.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	380.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	12.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	51.000	EACH
712-06	SIGNS (CONSTRUCTION)	274.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	96.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.09	REMOVABLE PAVEMENT MARKING (4" line)	2,320.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	24.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R1-1)	2.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R5-2)	2.000	EACH

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
713-16.22	SIGNS (DESCRIPTION) (W1-7)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (W2-7R)	1.000	EACH
713-16.24	SIGNS (DESCRIPTION) (W3-1)	2.000	EACH
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	860.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	35.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	35.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	38.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	5.900	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	160.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,572.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	322.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	7,154.000	L.F.
801-01	SEEDING (WITH MULCH)	2.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	218.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	23.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	49.000	UNIT
801-03	WATER (SEEDING & SODDING)	43.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	6,233.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BR. ID. 01SR0610003)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	165.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	241.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	90.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 1 ,STA. 13+83.67)	(1)	LS

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 2, STA. 14+54.33)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	189.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	81.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	54.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	89,156.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	350.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	61,432.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	204.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	219.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,052.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	954.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	486.000	L.F.
606-17.03	STEEL PIPE PILES (12-INCH)	440.000	L.F.
615-01.03	PRESTRESSED CONCRETE I-BEAM (TYPE III)	1,063.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	185.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	1.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	427.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	136.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	30.000	L.F.
793-01.41	ANCHOR 1IN	12.000	EACH
793-11.58	REMOVE HANDHOLE	2.000	EACH
793-98.04	REMOVE POLES ALL SIZES	18.000	EACH
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	129.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	109.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	101.000	L.F.
795-03.05	6IN PVC WATER LINE	1,014.000	L.F.
795-03.06	8IN PVC WATER LINE	109.000	L.F.
795-03.07	10IN PVC WATER LINE	263.000	L.F.
795-03.08	12IN PVC WATER LINE	1,272.000	L.F.

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
795-05.14	HDD __IN HDPE CASING PIPE-UNCON (1-1/2)	333.000	L.F.
795-05.63	BORE/JACK 12IN STEEL CASING PIPE-UNCON.	40.000	L.F.
795-05.65	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	46.000	L.F.
795-05.90	HDD 6IN HDPE CARRIER PIPE-UNCON	200.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	1.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	1.000	EACH
795-06.06	CONNECT TO 10IN WATER LINE	1.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	1.000	EACH
795-06.30	CUT/CAP EXISTING LINES (ALL SIZES)	4.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.06	8IN X 8IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.10	10IN X 10IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.15	12IN X 12IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	1.000	EACH
795-09.14	3/4IN HDPE SERVICE PIPE	985.000	L.F.
795-11.01	BLOW-OFF ASSEMBLY	3.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	3,325.000	L.F.
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-12.03	PIPE GROUTING	(1)	LS
795-13.01	DI FITTINGS	1,000.000	LB.
795-14.08	RESTORE ASPHALT	100.000	S.Y.
795-15.02	12IN STEEL CASING PIPE OPEN CUT METHOD	72.000	L.F.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	55.000	L.F.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	12.000	EACH
795-16.25	RELOCATE/RECONNECT 6IN WATER METER ASSEMBLY	2.000	EACH
795-30.09	1-1/2IN HDPE CASING OPEN CUT	350.000	L.F.
797-02.04	2IN HDPE FORCE MAIN	440.000	L.F.

Contract ID CNY279 - ANDERSON

Item No.	Description	Quantity	Units
797-03.06	4IN PVC FORCE MAIN	1,880.000	L.F.
797-06.03	HDD 6IN HDPE CARRIER PIPE-UNCON	61.000	L.F.
797-06.61	BORE/JACK 10IN STEEL CASING PIPE-UNCON.	40.000	L.F.
797-06.88	OPEN CUT 10IN STEEL CASING PIPE	10.000	L.F.
797-08.01	DI FITTINGS	400.000	LB.
797-08.60	2IN GATE VALVE ASSEMBLY	1.000	EACH
797-09.06	4IN PLUG VALVE ASSEMBLY	4.000	EACH
797-09.41	CUT AND CAP 2IN FORCE MAIN	1.000	EACH
797-09.43	CUT AND CAP 4IN FORCE MAIN	4.000	EACH
797-10.14	CONNECT TO 2IN FORCE MAIN	1.000	EACH
797-10.16	CONNECT TO 4IN FORCE MAIN	5.000	EACH
797-11.30	RETIREIN PLACE EXISTING SEWER <8IN	2,350.000	L.F.
797-11.40	RESTORE ASPHALT	20.000	S.Y.
797-12.12	6IN HDPE CASING OPEN CUT	64.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY265 - ANDERSON , BLOUNT, ETC.

Contract ID: CNY265**Letting Date:** December 06, 2024 10:00 AM**Projects:** R1BVAR-M3-052

N/A

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER,
HAMBLE, HANCOCK, HAWKINS,
JEFFERSON, JOHNSON, KNOX, LOUDON,
MONROE, MORGAN, ROANE, SCOTT,
SEVIER, SULLIVAN, UNICOI, UNION,
WASHINGTON**District:****DBE Goal Percent:****Description:** The random on-call concrete pavement repair on various Interstate and State Routes.**Contract Time:** DT - 3/31/2026

Item No.	Description	Quantity	Units
502-02	HOLES	5.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	50.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	7,500.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	3,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	600.000	EACH
502-08	PRE-ROLLING	50.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	1,300.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	1,800.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	250.000	L.F.
502-10	CEMENT-FLY ASH GROUT	50.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	400.000	S.Y.
503-60	RETROFIT DOWEL BAR	25.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	8.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	6.000	EACH

Contract ID CNY265 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	250.000	EACH
712-06	SIGNS (CONSTRUCTION)	450.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	4.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	4,500.000	L.F.
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	5.000	EACH

() Item will be bid as lump sum.

Contract ID CNY212 - ANDERSON , BLOUNT, ETC.

Contract ID: CNY212

Letting Date: December 06, 2024 10:00 AM

Projects: R1BVAR-M3-048

N/A

Counties: ANDERSON, BLOUNT, CAMPBELL, COCKE,
JEFFERSON, KNOX, LOUDON, MONROE,
ROANE, SEVIER

District:

DBE Goal Percent:

Description: The sweeping on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
719-01	SWEEPING	14,585.000	L.M.

() Item will be bid as lump sum.

Contract ID CNY231 - ANDERSON , BLOUNT, ETC.

Contract ID: CNY231

Letting Date: December 06, 2024 10:00 AM

Projects: R1BVAR-M3-049

N/A

Counties: ANDERSON, BLOUNT, CAMPBELL, COCKE,
GRAINGER, JEFFERSON, KNOX, LOUDON,
MONROE, ROANE, SEVIER

District:

DBE Goal Percent:

Description: The drain cleaning on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
611-07.11	CLEAN DRAIN(WITH GRATE)	1,230.000	EACH
611-07.12	CLEAN DRAIN(WALL DRAIN)	100.000	EACH
611-07.13	PIPE CLEANING (<18IN DIA.)	750.000	L.F.
611-07.14	PIPE CLEANING (>OR=18IN DIA.)	2,400.000	L.F.
611-07.20	HEAVY DRAIN CLEANING	100.000	EACH
712-01.02	LANE CLOSURE	50.000	EACH
712-01.12	LANE CLOSURE (CALLOUT)	10.000	EACH

() Item will be bid as lump sum.

Contract ID CNY282 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNY282**Letting Date:** December 06, 2024 10:00 AM**Projects:** R3BVAR-M3-058

n/a

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON**District:****DBE Goal Percent:****Description:** The random on-call concrete pavement repair on various Interstate and State Routes.**Contract Time:** DT - 3/31/2026

Item No.	Description	Quantity	Units
502-02	HOLES	10.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	50.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	11,500.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	4,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	735.000	EACH
502-08	PRE-ROLLING	8.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	8,000.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	2,500.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	200.000	L.F.
502-10	CEMENT-FLY ASH GROUT	40.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	425.000	S.Y.
503-60	RETROFIT DOWEL BAR	50.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	10.000	EACH

Contract ID CNY282 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
712-01.03	LANE CLOSURE(NIGHT WORK)	9.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	160.000	EACH
712-06	SIGNS (CONSTRUCTION)	560.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	20.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	3,100.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	8.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNY280 - BENTON

Contract ID: CNY280**Letting Date:** December 06, 2024 10:00 AM**Projects:** 03S069-F3-003
03S069-F8-003

NH/HSIP-69(113)

NH/HSIP-69(113)

Counties: BENTON**District:****DBE Goal Percent:** 5.00**Description:** The resurfacing (either microsurface or thin mix overlay) on U.S. 641 (S.R. 69) from the Decatur County line (L.M. 0.00) to James Walker Road (L.M. 10.92).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
203-06	WATER	22.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.900	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	2,890.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	134,535.000	S.Y.
411-04	CRACK SEALANT	15,288.000	LB.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	231.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	1,910.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	20.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	20.000	EACH
706-01	GUARDRAIL REMOVED	1,010.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,440.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	2,484.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	90.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	2,574.000	EACH

Contract ID CNY280 - BENTON

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	3,570.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	32.000	EACH
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.400	L.M.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	40.700	L.M.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	3,570.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	442.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	32.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	40.700	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	40.700	L.M.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	44.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	7,548.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	70.000	TON
712-06	SIGNS (CONSTRUCTION)	128.000	S.F.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	28.000	TON
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	341.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	2,842.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	50.000	TON
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	40.700	L.M.

() Item will be bid as lump sum.

Contract ID CNY266 - BENTON , CARROLL, ETC.

Contract ID: CNY266**Letting Date:** December 06, 2024 10:00 AM**Projects:** R4BVAR-M3-062

N/A

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
DECATUR, DYER, FAYETTE, GIBSON,
HARDEMAN, HARDIN, HAYWOOD,
HENDERSON, HENRY, LAKE, LAUDERDALE,
MADISON, MCNAIRY, OBION, SHELBY,
TIPTON, WEAKLEY**District:****DBE Goal Percent:****Description:** The random on-call concrete pavement repair on various Interstate and State Routes.**Contract Time:** DT - 3/31/2026

Item No.	Description	Quantity	Units
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	30.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	11,500.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	2,500.000	EACH
502-04.03	TRANSVERSE TIE-BARS	700.000	EACH
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	4,100.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	3,400.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	250.000	L.F.
503-01	GRINDING CONCRETE PAVEMENT	500.000	S.Y.
503-60	RETROFIT DOWEL BAR	15.000	EACH
706-10.74	CONCRETE BARRIER WALL REPAIR	5.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	365.000	EACH
712-06	SIGNS (CONSTRUCTION)	800.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	150.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH

Contract ID CNY266 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	15.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	15.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	800.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	300.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNY270 - BENTON & DECATUR

Contract ID: CNY270**Letting Date:** December 06, 2024 10:00 AM**Projects:** 20I040-S3-003

N/A

Counties: BENTON, DECATUR**District:****DBE Goal Percent:****Description:** The grading, drainage, and paving on I-40 at the U.S. 641 (S.R. 69) interchange (L.M. 5.62) (Exit 126), including lighting and signals.**Contract Time:** DT - 6/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (TR. 18 & 20)	529.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	81,494.000	C.Y.
203-03.01	BORROW EXCAVATION (SELECT MATERIAL)	5,671.700	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	5,813.000	C.Y.
203-06	WATER	390.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	4,627.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	15.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-05	SEDIMENT REMOVAL	402.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,340.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	740.000	L.F.
209-08.07	ROCK CHECK DAM	8.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	36.000	EACH
209-08.09	FILTER SOCK CHECK DAM	143.000	EACH
209-09.01	SANDBAGS	120.000	BAG
209-09.04	SEDIMENT FILTER BAG(15' X 10')	6.000	EACH
209-09.41	CURB INLET PROTECTION (TYPE 2)	10.000	EACH

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	100.000	S.Y.
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	100.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	17.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	280.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	23,080.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	47.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	60.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	415.000	TON
307-01.22	ASP. CONC. MIX(PG76-22) (BPMB-HM) GR. A-S	1,026.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,577.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	742.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	1,740.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,295.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	3,767.000	TON
313-03	TREATED PERMEABLE BASE	9,540.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	38.800	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	134.800	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	16,900.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	112.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	419.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	764.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	354.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	2,508.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.700	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	0.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,245.000	TON

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	9,540.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	100.000	L.F.
604-01.20	BOX TUBE SAFETY RAIL	616.000	L.F.
604-03.07	CLASS A CONCRETE (DESCRIPTION) (MEDIAN BARRIER)	20.000	C.Y.
607-02.02	15" CONCRETE PIPE CULVERT (CLASS III)	22.000	L.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	659.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	8.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	88.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	68.000	L.F.
611-02.10	JUNCTION BOX, TYPE 1	4.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH
611-02.12	JUNCTION BOX, TYPE 3	2.000	EACH
611-02.13	JUNCTION BOX, TYPE 4	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	20.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	750.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	2.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.59	24IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.65	36IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.67	42IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.68	42IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.70	48IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	3.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	1.000	EACH
621-03.01	15" TEMPORARY DRAINAGE PIPE	100.000	L.F.
621-03.02	18" TEMPORARY DRAINAGE PIPE	100.000	L.F.
701-03	CONCRETE MEDIAN PAVEMENT	56.000	C.Y.

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
702-01	CONCRETE CURB	30.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	24.000	C.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,875.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	4.000	EACH
705-06.15	SHORT-RADIUS GUARDRAIL SYSTEM (16 FT RADIUS) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	3,550.000	L.F.
707-03.01	STOCK FENCE	3,700.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	34.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (ROW)	3,471.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	3,830.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	30.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	520.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	45.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	331.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	8,530.000	L.F.
710-05	LATERAL UNDERDRAIN	761.000	L.F.
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	2.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	40.000	EACH
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	188.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	9,200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	9.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	260.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	460.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	24.000	EACH

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	874.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	300.000	HOURL
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,290.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	8,935.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	2.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	507.000	LB.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	684.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	23.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	96.000	L.F.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	4,113.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	375.000	LB.
713-11.01	"U" SECTION STEEL POSTS	102.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,034.000	LB.
713-11.21	P POST SLIP BASE	5.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	169.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	728.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	1,504.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	4.000	EACH
714-03	JACKED OR BORED CONDUIT	250.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	8,000.000	L.F.
714-05.04	PULL BOXES (TYPE C)	19.000	EACH
714-06.03	CABLE (1/C # 10 AWG)	31,650.000	L.F.
714-06.05	CABLE (1/C # 6 AWG)	8,250.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (40' M.H.)	27.000	EACH

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
714-08.11	LIGHT STANDARDS (DESCRIPTION) (HIGH MAST - 100' M.H.)	6.000	EACH
714-08.27	FOUNDATION FOR LIGHT STANDARDS - HIGH MAST (DESCRIPTION) (100' M.H.)	6.000	EACH
714-08.28	FOUNDATION FOR LIGHT STANDARDS - ROADWAY (DESCRIPTION) (40' STANDARD)	27.000	EACH
714-08.32	REMOVAL OF LIGHT STANDARD & FOUNDATION	4.000	EACH
714-09.47	LED LUMINAIRES (DESCRIPTION) (126 WATT)	27.000	EACH
714-09.48	LED LUMINAIRES (DESCRIPTION) (72 WATT)	4.000	EACH
714-09.64	LED LUMINAIRES-HIGH MAST (DESCRIPTION) (6 LUMINAIRES @ 60 DEGREES, 300 WATT)	6.000	EACH
714-12.01	CONTROL CENTER (NO. 1)	(1)	LS
714-12.02	CONTROL CENTER (NO. 2)	(1)	LS
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 1)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (CONTROL CENTER NO. 2)	(1)	LS
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	385.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	94.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	154.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	179.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	220.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	40.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	745.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	196.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,065.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	36.000	S.F.

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	10.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	33,669.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	1.950	L.M.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	8.590	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	8.300	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	2,445.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	5,878.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	10.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	2.000	EACH
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2 POLE MOUNTED)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	6.000	EACH
730-03.23	INSTALL PULL BOX (FIBER OPTIC-TYPE A)	5.000	EACH
730-03.51	FIBER OPTIC CABLE (12F)	650.000	L.F.
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,100.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	175.000	L.F.
730-12.16	CONDUIT (DESCRIPTION) (2" STRUCTURE CONDUIT WITH HANGER ASSEMBLY)	627.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	800.000	L.F.
730-12.42	CURB MARKER (DESCRIPTION) (FIBER OPTIC)	12.000	EACH
730-13.02	VEHICLE DETECTOR (VIDEO)	4.000	EACH
730-13.16	VEHICLE DETECTOR (RADAR/VIDEO)	2.000	EACH

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-24.91	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 55')	1.000	EACH
730-24.93	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 65')	1.000	EACH
730-25.01	CANTILEVER SIGNAL SUPPORT (1 ARM @ 50')	1.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,511.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	9,267.600	S.Y.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	1,460.000	L.F.
801-01	SEEDING (WITH MULCH)	557.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	557.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	10.000	UNIT
801-01.65	TEMPORARY MULCH	50.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	10.000	UNIT
801-03	WATER (SEEDING & SODDING)	683.000	M.G.
803-01	SODDING (NEW SOD)	62,640.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	107.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	150.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	317.000	S.Y.
805-12.03	EROSION CONTROL BLANKET (TYPE III)	87.000	S.Y.
805-12.04	EROSION CONTROL BLANKET (TYPE IV)	213.000	S.Y.
793-10.01	BURIED CABLE @ 24IN DEPTH	10.000	L.F.
793-10.02	BURIED CABLE @ 36IN DEPTH	163.000	L.F.
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	195.000	L.F.
793-11.04	6IN PEDESTAL	1.000	EACH
793-11.19	MARKER POST	1.000	EACH
793-16.22	GROUND BED	1.000	EACH
793-98.06	REMOVE PEDESTALS	1.000	EACH
403-02.01	TRACKLESS TACK COAT	61.100	TON
403-02.02	HOT APPLIED TACK COAT	37.000	TON

Contract ID CNY270 - BENTON & DECATUR

Item No.	Description	Quantity	Units
403-02.01	TRACKLESS TACK COAT	100.300	TON

() Item will be bid as lump sum.

Contract ID CNY295 - BLEDSOE , BRADLEY, ETC.

Contract ID: CNY295**Letting Date:** December 06, 2024 10:00 AM**Projects:** R2BVAR-M3-039

n/a

Counties: BLEDSOE, BRADLEY, CANNON, CLAY,
COFFEE, CUMBERLAND, DEKALB,
FENTRESS, FRANKLIN, GRUNDY,
HAMILTON, JACKSON, MARION, MCMINN,
MEIGS, OVERTON, PICKETT, POLK,
PUTNAM, RHEA, SEQUATCHIE, VAN BUREN,
WARREN, WHITE**District:****DBE Goal Percent:****Description:** The random on-call concrete pavement repair on various Interstate and State Routes.**Contract Time:** DT - 3/31/2026

Item No.	Description	Quantity	Units
502-02	HOLES	5.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	50.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	10,200.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	4,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	1,600.000	EACH
502-08	PRE-ROLLING	5.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	5,000.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	1,500.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	200.000	L.F.
502-10	CEMENT-FLY ASH GROUT	50.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	500.000	S.Y.
503-60	RETROFIT DOWEL BAR	25.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	6.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	5.000	EACH

Contract ID CNY295 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	230.000	EACH
712-06	SIGNS (CONSTRUCTION)	625.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	6.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	1,250.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	3.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	6.000	EACH

() Item will be bid as lump sum.

Contract ID CNY210 - BRADLEY , GRUNDY, ETC.

Contract ID: CNY210

Letting Date: December 06, 2024 10:00 AM

Projects: R2BVAR-M3-037

N/A

Counties: BRADLEY, GRUNDY, HAMILTON, MARION,
PUTNAM, SEQUATCHIE, WHITE

District:

DBE Goal Percent:

Description: The sweeping on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
719-01	SWEEPING	7,040.000	L.M.

() Item will be bid as lump sum.

Contract ID CNY226 - BRADLEY , GRUNDY, ETC.

Contract ID: CNY226

Letting Date: December 06, 2024 10:00 AM

Projects: R2BVAR-M3-038

N/A

Counties: BRADLEY, GRUNDY, HAMILTON, MARION,
PUTNAM, SEQUATCHIE, WHITE

District:

DBE Goal Percent:

Description: The drain cleaning on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
611-07.10	CLEAN DRAIN (TRENCH DRAIN)	3,750.000	L.F.
611-07.11	CLEAN DRAIN(WITH GRATE)	560.000	EACH
611-07.12	CLEAN DRAIN(WALL DRAIN)	110.000	EACH
611-07.13	PIPE CLEANING (<18IN DIA.)	9,000.000	L.F.
611-07.14	PIPE CLEANING (>OR=18IN DIA.)	400.000	L.F.
611-07.20	HEAVY DRAIN CLEANING	100.000	EACH
712-01.02	LANE CLOSURE	50.000	EACH
712-01.12	LANE CLOSURE (CALLOUT)	10.000	EACH

() Item will be bid as lump sum.

Contract ID CNY293 - CAMPBELL**Contract ID:** CNY293**Letting Date:** December 06, 2024 10:00 AM**Projects:** 07I075-F8-017

NH-I-75-3(201)

Counties: CAMPBELL**District:****DBE Goal Percent:** 6.50**Description:** The resurfacing on I-75 from near Rarity Mountain Road (L.M. 24.52) to the Kentucky State line (L.M. 31.64).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	764.000	TON
307-03.09	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING C	22,138.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	129.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	254.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	25,026.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	29.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	28,759.000	TON
502-08.01	RESEALING JOINTS (HOT POURED ELASTIC)	4,889.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	401.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	200.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,680.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	2.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH

Contract ID CNY293 - CAMPBELL

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,314.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,314.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	18.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	84.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,924.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	6.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	29.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	39.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	39.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	5,736.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	7,201.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	1,358.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	573.000	L.F.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	300.000	TON
403-02.02	HOT APPLIED TACK COAT	275.000	TON

() Item will be bid as lump sum.

Contract ID CNY304 - CAMPBELL

Contract ID: CNY304**Letting Date:** December 06, 2024 10:00 AM**Projects:** 07002-3248-04

N/A

Counties: CAMPBELL**District:****DBE Goal Percent:****Description:** The traffic signal modernization on U.S. 25W (S.R. 9) from near S.R. 297 (South Main Street) (L.M. 0.21) to near Kentucky Street (L.M. 0.37) in Jellico.**Contract Time:** DT - 10/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	115.000	S.Y.
202-08.10	REMOVAL OF CURB (DESCRIPTION) (SEE PLANS)	90.000	L.F.
209-05	SEDIMENT REMOVAL	100.000	C.Y.
209-09.43	CURB INLET PROTECTION (TYPE 4)	8.000	EACH
701-01.10	CONCRETE SIDEWALK (DESCRIPTION)	780.000	S.F.
701-02.03	CONCRETE CURB RAMP	240.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	56.000	S.F.
702-01.02	CONCRETE CURB	40.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	205.500	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.21	SIGNS (DESCRIPTION) (24"X12" ALUMINUM FLAT SHEET, W16-7P)	2.000	EACH
713-16.22	SIGNS (DESCRIPTION) (24"X12" ALUMINUM FLAT SHEET, W16-9P)	2.000	EACH
713-16.24	SIGNS (DESCRIPTION) (36"X36" ALUMINUM FLAT SHEET, R1-5b)	2.000	EACH
713-16.25	SIGNS (DESCRIPTION) (30"X30" ALUMINUM FLAT	4.000	EACH

Contract ID CNY304 - CAMPBELL

Item No.	Description	Quantity	Units
	SHEET, W11-2)		
713-16.26	SIGNS (DESCRIPTION) (30"X30" ALUMINUM FLAT SHEET, R10-15)	4.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	38.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	25.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	30.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	38.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	8.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	3.000	EACH
730-05.06	ELECTRICAL SERVICE CONNECTION (PHB) (PHB)	1.000	EACH
730-08.01	SIGNAL CABLE - 3 CONDUCTOR	130.000	L.F.
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	1,270.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	360.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	3.000	EACH
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	190.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	3.000	EACH
730-15.07	CABINET (DESCRIPTION) (PEDESTRIAN HYBRID BEACON)	1.000	EACH
730-15.11	MODIFY CABINET (DESCRIPTION) (SEE PLANS)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-16.14	CONTROLLER (DESCRIPTION) (PEDESTRIAN HYBRID BEACON)	1.000	EACH
730-23.02	STEEL STRAIN POLE (DESCRIPTION) (PED POLE W/LUMINAIRE)	1.000	EACH
730-23.88	CANTILEVER SIGNAL SUPPORT (1 ARM @ 45')	1.000	EACH
730-26.05	COUNTDOWN PEDESTRIAN SIGNAL	8.000	EACH
730-26.06	PEDESTRIAN PUSHBUTTON POST	4.000	EACH
730-26.09	PEDESTRIAN PUSHBUTTON WITH 15IN SIGN	8.000	EACH
730-26.12	PEDESTRIAN PUSHBUTTON HORIZONTAL EXTENSION	1.000	EACH
730-50.25	PEDESTRIAN HYBRID BEACON ASSEMBLY	2.000	EACH

Contract ID CNY304 - CAMPBELL

Item No.	Description	Quantity	Units
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	60.000	L.F.
793-97.01	RESTORE ASPHALT	7.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY300 - CARROLL

Contract ID: CNY300**Letting Date:** December 06, 2024 10:00 AM**Projects:** 09S001-F3-002

STP/HSIP-1(493)

09S001-F8-002

STP/HSIP-1(493)

09S001-M3-002

STP/HSIP-1(493)

Counties: CARROLL**District:****DBE Goal Percent:** 4.50**Description:** The resurfacing with hot in-place recycling on U.S. 70 (S.R. 1) from near the Rutherford Fork Obion River (L.M. 11.00) to S.R. 22 (L.M. 19.68), including bridge expansion joint repairs and thin epoxy overlay.**Contract Time:** DT - 10/31/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,523.000	S.Y.
203-06	WATER	37.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	16.800	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	4,900.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	350.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	112.000	TON
311-03.04	HOT IN PLACE RECYCLING OF ASPHALT PAVEMENT (2.00IN)	120,818.000	S.Y.
311-03.10	ASPHALT REJUVENATING AGENT	60,410.000	GAL.
403-02.01	TRACKLESS TACK COAT	161.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	1,509.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	7,422.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	10.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	1,184.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	25.000	EACH

Contract ID CNY300 - CARROLL

Item No.	Description	Quantity	Units
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	25.000	EACH
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	25.000	EACH
706-01	GUARDRAIL REMOVED	1,260.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	80.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,664.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	575.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	575.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	325.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	52.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	101.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	5.000	S.F.
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	1,500.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	33.700	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.700	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,300.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	188.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	68.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,588.000	S.Y.

Contract ID CNY300 - CARROLL

() Item will be bid as lump sum.

Contract ID CNY213 - CARTER , SULLIVAN, ETC.

Contract ID: CNY213

Letting Date: December 06, 2024 10:00 AM

Projects: R1BVAR-M3-047

N/A

Counties: CARTER, SULLIVAN, UNICOI, WASHINGTON

District:

DBE Goal Percent:

Description: The sweeping on various Interstate and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
719-01	SWEEPING	987.000	L.M.

() Item will be bid as lump sum.

Contract ID CNY273 - CHEATHAM & ROBERTSON

Contract ID: CNY273**Letting Date:** December 06, 2024 10:00 AM**Projects:** 11I024-F8-002

NH-I-24-9(102)

Counties: CHEATHAM, ROBERTSON**District:****DBE Goal Percent:** 9.00**Description:** The resurfacing on I-24 from the Robertson County line (L.M. 0.00, Cheatham County Seq. 1), crossing through Robertson County to the Davidson County line (L.M. 3.63, Cheatham County Seq. 2).**Contract Time:** DT - 11/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	26.200	L.M.
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	400.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	110.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	5,505.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	16,502.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	25.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	20,464.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	400.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,079.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	2.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH

Contract ID CNY273 - CHEATHAM & ROBERTSON

Item No.	Description	Quantity	Units
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,263.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,263.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	129.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	35.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,508.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	24.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	6.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	29.800	L.M.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	1.500	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	1.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	29.800	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,805.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	3,283.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.02	SAW SLOT	400.000	L.F.
730-14.03	LOOP WIRE	1,200.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY303 - COCKE , GREENE, ETC.

Contract ID: CNY303**Letting Date:** December 06, 2024 10:00 AM**Projects:** 15946-3436-94

HSIP-1500(56)

30946-3487-94

HSIP-3000(59)

73014-3222-94

HSIP-61(49)

78S035-F3-002

HSIP-35(79)

Counties: COCKE, GREENE, ROANE, SEVIER**District:****DBE Goal Percent:** 10.00**Description:** The miscellaneous safety improvements on U.S. 411/U.S. 441 (S.R. 35), S.R. 61, and various local roads.**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	8.000	EACH
705-02.20	SINGLE GUARDRAIL (TYPE 2) LONG POST (6 FT-9 FT)	1.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	8.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	900.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,638.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
706-01	GUARDRAIL REMOVED	538.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.11	REMOVAL OF EXISTING DELINEATORS	5.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	5.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	10.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	2,772.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	6,040.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	17,210.000	LB.
713-11.21	P POST SLIP BASE	4.000	EACH

Contract ID CNY303 - COCKE , GREENE, ETC.

Item No.	Description	Quantity	Units
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	2,034.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	2,923.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	264.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	4.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	650.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	124.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,093.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	22.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	3.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	670.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	6.000	EACH
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	138.100	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	4,110.000	L.F.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	6.900	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY267 - COFFEE

Contract ID: CNY267**Letting Date:** December 06, 2024 10:00 AM**Projects:** 16S055-F3-004
16S055-F8-004NH/HSIP-55(32)
NH/HSIP-55(32)**Counties:** COFFEE**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on S.R. 55 from U.S. 41 (S.R. 2) (L.M. 13.79) to north of Interstate Drive (L.M. 15.32).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	3.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	250.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	750.000	TON
403-02.01	TRACKLESS TACK COAT	31.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	6.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	4,279.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,512.000	TON
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	33.000	EACH
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	74.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	92.000	EACH
712-06	SIGNS (CONSTRUCTION)	420.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	104.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	166.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS	90.000	EACH

Contract ID CNY267 - COFFEE

Item No.	Description	Quantity	Units
	(BI-DIR)(2 COLOR)		
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	432.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	55.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	86.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	221.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	20.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	211.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	631.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	99.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.600	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	4.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	159.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	15.000	S.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	7.200	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	221.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	7.200	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	1,010.000	L.F.
730-14.03	LOOP WIRE	3,030.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY287 - DAVIDSON

Contract ID: CNY287**Letting Date:** December 06, 2024 10:00 AM**Projects:** 19I040-F8-003
19I040-M3-020

NH-I-40-3(175)

NH-I-40-3(175)

Counties: DAVIDSON**District:****DBE Goal Percent:** 9.50**Description:** The resurfacing on I-40 from 46th Avenue (L.M. 13.33) to near Jefferson Street (L.M. 16.44), including bridge expansion joint repair and thin epoxy overlay.**Contract Time:** DT - 11/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	802.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	311.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	97.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	2,553.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	28.000	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	12,322.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	10.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	14,357.000	TON
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	16,564.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	286.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	180.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,300.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	8.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH

Contract ID CNY287 - DAVIDSON

Item No.	Description	Quantity	Units
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,452.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,452.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,460.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	30.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,798.000	L.F.
716-03.09	PLASTIC WORD PAVEMENT MARKING () (NORTH)	2.000	EACH
716-03.10	PLASTIC WORD PAVEMENT MARKING () (SOUTH)	2.000	EACH
716-03.11	PLASTIC WORD PAVEMENT MARKING () (EAST)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	8.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	16.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	27.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	16.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	2,112.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.300	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.100	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	29.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	15.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN	9,742.000	L.F.

Contract ID CNY287 - DAVIDSON

Item No.	Description	Quantity	Units
	DOTTED LINE)		
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	7,200.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	5,090.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	9,597.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	382.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	30.000	S.Y.
604-10.53	CONCRETE REPAIRS	10.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	3,479.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY284 - DAVIDSON

Contract ID: CNY284**Letting Date:** December 06, 2024 10:00 AM**Projects:** 19I065-F8-002
19I065-M3-004

NH-I-65-3(132)

NH-I-65-3(132)

Counties: DAVIDSON**District:****DBE Goal Percent:** 9.50**Description:** The resurfacing on I-65 from I-40 (L.M. 8.44) to near the Cumberland River bridge (L.M. 11.91), including thin epoxy overlay at L.M. 8.55.**Contract Time:** DT - 11/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	855.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	298.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	90.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,031.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	10,098.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	11.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	13,861.000	TON
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	9,026.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	250.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,413.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	8.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	175.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	4.000	EACH

Contract ID CNY284 - DAVIDSON

Item No.	Description	Quantity	Units
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	10.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W4-2R 48"X48")	1.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	112.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,579.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,579.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	150.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	14.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	140.000	L.F.
716-03.09	PLASTIC WORD PAVEMENT MARKING () (EAST)	3.000	EACH
716-03.10	PLASTIC WORD PAVEMENT MARKING () (WEST)	3.000	EACH
716-03.11	PLASTIC WORD PAVEMENT MARKING () (SOUTH)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	7.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	225.000	L.F.
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	7.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	18.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,835.000	L.F.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.100	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	11.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	18.000	L.M.

Contract ID CNY284 - DAVIDSON

Item No.	Description	Quantity	Units
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	5,050.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	2,262.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	7,134.000	L.F.
716-15.10	PREFORMED PERMANENT TAPE (6IN LINE)	1,835.000	L.F.
716-15.11	PREFORMED PERMANENT TAPE (8IN LINE)	8,240.000	L.F.
716-15.20	PREFORMED PERMANENT TAPE (24IN BARRIER LINE)	3,400.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	30.000	L.F.
730-14.02	SAW SLOT	400.000	L.F.
730-14.03	LOOP WIRE	1,700.000	L.F.
730-15.07	CABINET (DESCRIPTION) (CYCLE STATION #315)	2.000	EACH
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,624.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY208 - DAVIDSON , MONTGOMERY, ETC.

Contract ID: CNY208

Letting Date: December 06, 2024 10:00 AM

Projects: R3SVAR-M3-067

N/A

Counties: DAVIDSON, MONTGOMERY, SUMNER,
WILLIAMSON

District:

DBE Goal Percent:

Description: The sweeping on various and State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
719-01	SWEEPING	4,580.000	L.M.

() Item will be bid as lump sum.

Contract ID CNY222 - DAVIDSON , SUMNER, ETC.

Contract ID: CNY222

Letting Date: December 06, 2024 10:00 AM

Projects: R3SVAR-M3-068

N/A

Counties: DAVIDSON, SUMNER, WILLIAMSON

District:

DBE Goal Percent:

Description: The drain cleaning on various State Routes.

Contract Time: DT - 2/28/2026

Item No.	Description	Quantity	Units
611-07.10	CLEAN DRAIN (TRENCH DRAIN)	1,000.000	L.F.
611-07.11	CLEAN DRAIN(WITH GRATE)	750.000	EACH
611-07.12	CLEAN DRAIN(WALL DRAIN)	300.000	EACH
611-07.13	PIPE CLEANING (<18IN DIA.)	100.000	L.F.
611-07.14	PIPE CLEANING (>OR=18IN DIA.)	100.000	L.F.
611-07.20	HEAVY DRAIN CLEANING	50.000	EACH
712-01.02	LANE CLOSURE	20.000	EACH
712-01.12	LANE CLOSURE (CALLOUT)	10.000	EACH

() Item will be bid as lump sum.

Contract ID CNY151 - DECATUR

Contract ID: CNY151**Letting Date:** December 06, 2024 10:00 AM**Projects:** 20S020-F3-002
20S020-F8-002NH/HSIP-20(87)
NH/HSIP-20(87)**Counties:** DECATUR**District:****DBE Goal Percent:** 6.00**Description:** The resurfacing on U.S. 412 (S.R. 20) from S.R. 69 (L.M. 3.59) to the Perry County line (L.M. 9.14).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	467.000	S.Y.
203-06	WATER	13.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.900	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	1,698.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	235.000	TON
307-02.09	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING CAM	6,316.000	TON
403-02.01	TRACKLESS TACK COAT	94.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	4,584.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.400	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	6.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,217.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	500.000	LB.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	7.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	7.000	EACH
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	6.000	EACH

Contract ID CNY151 - DECATUR

Item No.	Description	Quantity	Units
706-01	GUARDRAIL REMOVED	350.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,108.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	530.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	24.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	289.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	75.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	353.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	490.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	783.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	185.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,900.000	L.F.
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	1.000	EACH
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	80.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	38.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	19.300	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY281 - DYER**Contract ID:** CNY281**Letting Date:** December 06, 2024 10:00 AM**Projects:** 23S078-F3-002
23S078-F8-002

STP/HSIP-78(31)

STP/HSIP-78(31)

Counties: DYER**District:****DBE Goal Percent:** 6.50**Description:** The resurfacing on S.R. 78 from near U.S. 51 (S.R. 3) (L.M. 1.51) to S.R. 103 (L.M. 9.52).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	200.000	S.Y.
203-06	WATER	18.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	17.100	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	2,289.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	92.000	TON
403-02.01	TRACKLESS TACK COAT	121.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	30.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	13,933.000	TON
411-04.10	ACS MIX(PG82-22) GRADING D	3,179.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	6.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	18,464.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	5,250.000	LB.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	8.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
706-01	GUARDRAIL REMOVED	550.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	85.000	EACH

Contract ID CNY281 - DYER

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	2,558.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
713-16.04	CHANGEABLE MESSAGE SIGN UNIT (DESCRIPT) (PORTABLE)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	506.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	228.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	62.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	795.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	355.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,956.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	836.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	31.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	510.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	3.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	204.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	100.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	34.100	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVT MRKNG (6IN LINE)	34.100	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY305 - FAYETTE

Contract ID: CNY305**Letting Date:** December 06, 2024 10:00 AM**Projects:** 24S194-F3-003

STP/HSIP-194(16)

24S194-F8-003

STP/HSIP-194(16)

24S194-M3-005

STP/HSIP-194(16)

Counties: FAYETTE**District:****DBE Goal Percent:** 4.00**Description:** The microsurfacing on S.R. 194 from North Railroad Street (L.M. 0.53) to S.R. 193 (L.M. 9.02), including bridge expansion joint repairs.**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
203-06	WATER	17.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	17.000	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	15.000	TON
403-05.01	BITUMINOUS MATERIAL (FOG SEAL) SHOULDER	0.800	TON
411-04	CRACK SEALANT	12,300.000	LB.
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	195.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	1,625.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	6.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	6.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	6.000	EACH
706-01	GUARDRAIL REMOVED	300.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	536.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	54.000	L.F.
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (W10-1 36")	2.000	EACH
713-16.51	REMOVE AND REPLACE SIGN (DESCRIPTION) (W10-4 36"X36")	2.000	EACH

Contract ID CNY305 - FAYETTE

Item No.	Description	Quantity	Units
713-16.52	REMOVE AND REPLACE SIGN (DESCRIPTION) (R1-1 36"X36")	5.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	562.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	562.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	306.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	30.100	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	14.300	L.M.
716-09.88	CONTRAST PAVEMENT MARKING 8"	1.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.100	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	150.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	468.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY225 - FAYETTE & SHELBY

Contract ID: CNY225**Letting Date:** December 06, 2024 10:00 AM**Projects:** R4BVAR-M3-057

N/A

Counties: FAYETTE, SHELBY**District:****DBE Goal Percent:****Description:** The drain cleaning on various Interstate and State Routes.**Contract Time:** DT - 2/28/2026

Item No.	Description	Quantity	Units
611-07.11	CLEAN DRAIN(WITH GRATE)	1,430.000	EACH
611-07.12	CLEAN DRAIN(WALL DRAIN)	600.000	EACH
611-07.13	PIPE CLEANING (<18IN DIA.)	500.000	L.F.
611-07.14	PIPE CLEANING (>OR=18IN DIA.)	500.000	L.F.
611-07.20	HEAVY DRAIN CLEANING	100.000	EACH
712-01.02	LANE CLOSURE	50.000	EACH
712-01.12	LANE CLOSURE (CALLOUT)	10.000	EACH

() Item will be bid as lump sum.

Contract ID CNY283 - GIBSON

Contract ID: CNY283**Letting Date:** December 06, 2024 10:00 AM**Projects:** 27S420-F3-002
27S420-F8-002STP/HSIP-420(11)
STP/HSIP-420(11)**Counties:** GIBSON**District:****DBE Goal Percent:** 5.50**Description:** The resurfacing on S.R. 420 from U.S. 45W (S.R. 5) (L.M. 0.00) to S.R. 186 (L.M. 4.57).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	3,516.000	S.Y.
203-06	WATER	27.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	9.200	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	3,589.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,213.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	398.000	TON
403-02.01	TRACKLESS TACK COAT	13.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	2,794.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	7.300	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	77.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	858.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	61.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	840.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	302.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	302.000	EACH

Contract ID CNY283 - GIBSON

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	169.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	20.100	L.M.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	82.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	15.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	15.100	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY228 - GRAINGER

Contract ID: CNY228**Letting Date:** December 06, 2024 10:00 AM**Projects:** 29002-3244-94

HSIP-1(444)

Counties: GRAINGER**District:****DBE Goal Percent:** 8.00**Description:** The miscellaneous safety improvements including signals on U.S. 11W (S.R. 1) at the intersection of Phyllis Drive and Main Street in Bean Station (L.M. 30.30 - L.M. 30.70).**Contract Time:** DT - 10/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,091.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	400.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	99.000	C.Y.
209-05	SEDIMENT REMOVAL	24.000	C.Y.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	8.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	339.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	8.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	72.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	85.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	193.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	675.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.200	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	0.200	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	12,122.000	S.Y.
604-01.20	BOX TUBE SAFETY RAIL	170.000	L.F.

Contract ID CNY228 - GRAINGER

Item No.	Description	Quantity	Units
604-07.01	RETAINING WALL (DESCRIPTION) (CONCRETE RET. WALL FROM STA. 36+00 TO 37+00)	533.000	S.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	14.000	L.F.
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	1.000	EACH
622-02.01	STEEL MESH & PLATES	144.000	S.F.
701-01.02	CONCRETE SIDEWALK (6 ")	4,802.000	S.F.
701-02.03	CONCRETE CURB RAMP	790.000	S.F.
702-01	CONCRETE CURB	1.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	90.000	C.Y.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	45.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	75.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	10.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	126.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	5,000.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	126.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	4.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	51.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	90.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.08	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.100" THICK)	5.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	58.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	65.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	9.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	135.000	L.F.

Contract ID CNY228 - GRAINGER

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	7.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	244.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.030	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	979.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	665.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	9.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	8.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (140A3F WITH BACKPLATE)	1.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	8.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	2,659.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,738.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	388.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	435.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	4.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	3.000	EACH
730-23.80	CANTILEVER SIGNAL SUPPORT (1 ARM @ 40')	1.000	EACH

Contract ID CNY228 - GRAINGER

Item No.	Description	Quantity	Units
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH
730-26.06	PEDESTRIAN PUSHBUTTON POST	2.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	8.000	EACH
730-50.11	WARNING SIGN FLASHING ASSEMBLY (HARD- WIRED)	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	108.000	S.Y.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	5,000.000	L.F.
801-01	SEEDING (WITH MULCH)	42.000	UNIT
803-01	SODDING (NEW SOD)	191.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY296 - GRUNDY & SEQUATCHIE

Contract ID: CNY296**Letting Date:** December 06, 2024 10:00 AM**Projects:** 31LCOU-F3-002
77LCOU-F3-002

HSIP-3100(25)

HSIP-7700(24)

Counties: GRUNDY, SEQUATCHIE**District:****DBE Goal Percent:** 10.00**Description:** The miscellaneous safety improvements including high friction surface treatment (HFST) on various local roads.**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	54.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	14,090.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	475.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	54.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.20	ROADSIDE OBSTACLE DELINEATION	99.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,536.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	680.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	2,678.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,586.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	701.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	1,036.500	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	143.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,021.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	179.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	470.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	14.000	EACH

Contract ID CNY296 - GRUNDY & SEQUATCHIE

Item No.	Description	Quantity	Units
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	3.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	2.000	EACH
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	144.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	69.760	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	4,125.000	L.F.
717-01	MOBILIZATION	(1)	LS
406-04.02	HIGH FRICTION SURFACE TREATMENT	3,670.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY308 - HAMBLEN

Contract ID: CNY308**Letting Date:** December 06, 2024 10:00 AM**Projects:** 32S034-F3-003
32S034-F8-003STP/HSIP-34(132)
STP/HSIP-34(132)**Counties:** HAMBLEN**District:****DBE Goal Percent:** 7.00**Description:** The resurfacing on U.S. 11E (S.R. 34) from near Depot Street (L.M. 15.24) to the Hawkins County line (L.M. 21.00).**Contract Time:** DT - 6/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.000	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	70.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	4,470.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	10.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	540.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,299.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	381.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	381.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-03.04	PLASTIC WORD PAVEMENT MARKING (SCHOOL)	2.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	3,106.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	10.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	23.000	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED	120.000	L.F.

Contract ID CNY308 - HAMBLEN

Item No.	Description	Quantity	Units
717-01	LINE) MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY276 - HICKMAN

Contract ID: CNY276**Letting Date:** December 06, 2024 10:00 AM**Projects:** 41S230-F3-006
41S230-F8-006STP/HSIP-230(19)
STP/HSIP-230(19)**Counties:** HICKMAN**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on S.R. 230 from S.R. 50 (L.M. 0.00) to S.R. 100 (L.M. 9.31).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
203-06	WATER	18.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	18.300	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,420.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	54.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	8,396.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,119.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,592.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	603.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	285.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	34.700	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	2,112.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVT MRKNG (6IN LINE)	34.700	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY301 - HICKMAN

Contract ID: CNY301**Letting Date:** December 06, 2024 10:00 AM**Projects:** 41S050-F3-004

HSIP-50(81)

41S050-F3-005

STP/HSIP-50(84)

41S050-F8-005

STP/HSIP-50(84)

Counties: HICKMAN**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on S.R. 50 from Collins Lane (L.M. 25.25) to the Maury County line (L.M. 31.66), and miscellaneous safety improvements from the Highway 50 West Loop (L.M. 12.01) to Orton Circle (L.M. 14.45).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	926.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	392.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	200.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	52.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,846.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	12.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,121.000	TON
705-04.05	GUARDRAIL TERMINAL (TYPE-IN-LINE)	1.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	4,210.000	L.F.
706-06.03	RADIUS RAIL	580.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,106.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	308.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	80.000	LB.

Contract ID CNY301 - HICKMAN

Item No.	Description	Quantity	Units
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	217.440	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	150.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	175.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	11.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	841.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	9.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	250.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	345.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	550.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	24.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	24.500	L.M.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	9.640	L.M.
716-15.10	PREFORMED PERMANENT TAPE (6IN LINE)	420.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY294 - JEFFERSON

Contract ID: CNY294**Letting Date:** December 06, 2024 10:00 AM**Projects:** 45006-3244-94

HSIP-34(106)

Counties: JEFFERSON**District:****DBE Goal Percent:** 7.50**Description:** The grading, drainage, signals, and paving on U.S. 11E (S.R. 34, East Broadway Boulevard) at the intersection of North Chucky Pike (L.M. 13.55).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (24" ,STA. 409+29.57)	42.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (18" ,STA. 411+04.31)	81.000	L.F.
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (36" ,STA. 31+30.00)	21.000	L.F.
202-02.04	REMOVAL OF PIPE (SIZE ,STA.) (15" ,STA. 411+30.00)	64.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	2,773.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	210.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	293.000	C.Y.
203-06	WATER	7.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-05	SEDIMENT REMOVAL	160.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	2,370.000	L.F.
209-08.07	ROCK CHECK DAM	12.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	7.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	11.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,643.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	48.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	767.000	TON

Contract ID CNY294 - JEFFERSON

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	103.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	387.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	911.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	813.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	8.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	13.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	222.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	361.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	1,055.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.700	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	931.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	188.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	235.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	428.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	1.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	45.000	LB.
611-07.33	30IN ENDWALL (SIDE DRAIN)	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
611-60.01	CATCH BASIN, 48IN ROUND,> 4FT-8FT DEPTH	3.000	EACH
611-60.10	CATCH BASIN, 60IN ROUND,> 4FT-8FT DEPTH	1.000	EACH
611-60.30	CATCH BASIN, 84IN ROUND,> 4FT-8FT DEPTH	2.000	EACH
611-60.40	CATCH BASIN, 96IN ROUND,> 4FT-8FT DEPTH	2.000	EACH
611-62.01	MANHOLE STRUCTURE, 48IN ROUND,> 4FT-8FT DEPTH	1.000	EACH
611-62.11	MANHOLE STRUCTURE, 60IN ROUND,> 8FT-12FT DEPTH	1.000	EACH

Contract ID CNY294 - JEFFERSON

Item No.	Description	Quantity	Units
621-03.03	24" TEMPORARY DRAINAGE PIPE	48.000	L.F.
701-03	CONCRETE MEDIAN PAVEMENT	87.000	C.Y.
702-01	CONCRETE CURB	117.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	79.000	C.Y.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	330.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	510.000	L.F.
710-05	LATERAL UNDERDRAIN	124.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	3,480.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	8.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	175.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	174.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	948.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	7,170.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	176.000	L.F.
713-11.21	P POST SLIP BASE	7.000	EACH
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	74.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	7.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	528.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	12.000	EACH

Contract ID CNY294 - JEFFERSON

Item No.	Description	Quantity	Units
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	76.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	22.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	134.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	109.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	370.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	23.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,446.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	3.000	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	35,470.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-01.03	MODIFICATION OF EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	8.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (140 A3F WITH BACKPLATE)	4.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	5.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	380.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	860.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	896.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	248.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	478.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	4.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	4.000	EACH

Contract ID CNY294 - JEFFERSON

Item No.	Description	Quantity	Units
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	1.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH
730-25.16	CANTILEVER SIGNAL SUPPORT (1 ARM @ 80')	1.000	EACH
730-25.17	CANTILEVER SIGNAL SUPPORT (1 ARM @ 85')	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,052.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	16.000	UNIT
801-03	WATER (SEEDING & SODDING)	4.000	M.G.
803-01	SODDING (NEW SOD)	2,621.000	S.Y.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	745.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	440.000	L.F.
795-05.92	4IN PVC CASING PIPE OPEN CUT	40.000	L.F.
795-05.99	FLOWABLE FILL (TRENCH PLUGS)	17.000	C.Y.
795-06.01	CONNECT TO 2IN WATER LINE	1.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	5.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	2.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	2.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	3.000	EACH
795-06.37	CUT AND CAP 12IN WATER LINE	2.000	EACH
795-07.05	8IN X 6IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-07.06	8IN X 8IN TAPPING SLEEVE AND VALVE	3.000	EACH
795-08.01	2IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.08	12IN BUTTERFLY VALVE ASSEMBLY	2.000	EACH
795-09.17	2IN HDPE SERVICE PIPE	60.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	1.000	EACH
795-12.01	REMOVE FIRE HYDRANT	1.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-13.01	DI FITTINGS	4,500.000	LB.

Contract ID CNY294 - JEFFERSON

Item No.	Description	Quantity	Units
795-14.05	CONCRETE ENCASEMENT	50.000	L.F.
795-14.08	RESTORE ASPHALT	26.000	S.Y.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	2.000	EACH
795-16.21	RELOCATE/RECONNECT 2IN WATER METER ASSEMBLY	1.000	EACH
797-05.02	8IN DIP GRAVITY SEWER 6FT-12FT DEPTH	654.000	L.F.
797-05.99	FLOWABLE FILL (TRENCH PLUGS)	3.000	C.Y.
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	3.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	5.000	EACH
797-07.75	TRAFFIC RATED FRAMES AND COVERS	6.000	EACH
797-07.80	REMOVE SEWER MANHOLE	2.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	180.000	L.F.
797-08.08	6IN CLEAN OUT ASSEMBLY	4.000	EACH
797-09.44	CUT AND CAP 8IN GRAVITY	2.000	EACH
797-10.06	CONNECT 6IN LATERAL TO SEWER LINE	4.000	EACH
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	2.000	EACH
797-11.25	RETIREIN PLACE 48IN MANHOLE	2.000	EACH
797-11.35	REMOVE EXISTING SEWER 8IN-14IN	150.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.40	RESTORE ASPHALT	55.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY269 - LAWRENCE

Contract ID: CNY269**Letting Date:** December 06, 2024 10:00 AM**Projects:** 50LCOU-F3-003

BRZ-5000(22)

Counties: LAWRENCE**District:****DBE Goal Percent:** 7.50**Description:** The construction of a concrete box bridge on Pleasant Valley Road over Dry Weakley Creek (L.M. 1.07), including grading, drainage, and paving.**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (10' X 6' CONC. BOX BRIDGE, STA 53+00)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	261.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	363.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	40.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	92.000	C.Y.
209-05	SEDIMENT REMOVAL	13.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	450.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	129.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	280.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	592.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	50.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	70.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.900	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.200	TON

Contract ID CNY269 - LAWRENCE

Item No.	Description	Quantity	Units
411-01.10	ACS MIX(PG64-22) GRADING D	41.000	TON
705-01.04	METAL BEAM GUARD FENCE	75.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	363.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	208.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	450.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	292.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	90.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.300	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	246.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	327.000	L.F.
801-01	SEEDING (WITH MULCH)	2.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	1.200	UNIT
801-02	SEEDING (WITHOUT MULCH)	2.800	UNIT
801-03	WATER (SEEDING & SODDING)	7.200	M.G.
803-01	SODDING (NEW SOD)	242.000	S.Y.
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	55.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	13,039.000	LB.

() Item will be bid as lump sum.

Contract ID CNY278 - LAWRENCE

Contract ID: CNY278**Letting Date:** December 06, 2024 10:00 AM**Projects:** 50S006-S3-006

N/A

Counties: LAWRENCE**District:****DBE Goal Percent:****Description:** The installation of signals on U.S. 43 (S.R. 6) at the intersection of U.S. 64 (S.R. 15) (L.M. 18.04) in Lawrenceburg.**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	55.000	EACH
712-06	SIGNS (CONSTRUCTION)	317.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	1.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W3-3, 48"x48", SIGNAL AHEAD SIGN)	2.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	80.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	79.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	76.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	33.000	S.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	482.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
717-01	MOBILIZATION	(1)	LS
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	1.000	EACH

Contract ID CNY278 - LAWRENCE

Item No.	Description	Quantity	Units
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	4.000	EACH
730-02.11	SIGNAL HEAD ASSEMBLY (130 A2 WITH BACKPLATE)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	6.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	908.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	434.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	562.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	237.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	3.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.08	CABINET (DESCRIPTION) (ATC)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-24.85	CANTILEVER SIGNAL SUPPORT (2 @ 40' & 50')	1.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-50.11	WARNING SIGN FLASHING ASSEMBLY (HARD-WIRED)	1.000	EACH
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	118.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY271 - LAWRENCE & MARSHALL

Contract ID: CNY271**Letting Date:** December 06, 2024 10:00 AM**Projects:** 50945-3477-94
59945-3493-94

HSIP-5000(20)

HSIP-5900(26)

Counties: LAWRENCE, MARSHALL**District:****DBE Goal Percent:** 3.00**Description:** The miscellaneous safety improvements on various local roads.**Contract Time:** DT - 7/31/2025

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,757.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	7,272.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	7,740.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	697.900	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	2,040.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	260.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,571.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	758.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	9.000	S.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	141.661	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	16,216.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY272 - MACON

Contract ID: CNY272**Letting Date:** December 06, 2024 10:00 AM**Projects:** 56946-3442-94

HSIP-5600(51)

Counties: MACON**District:****DBE Goal Percent:** 4.00**Description:** The miscellaneous safety improvements on various local roads.**Contract Time:** DT - 7/31/2025

Item No.	Description	Quantity	Units
705-01.05	GUARDRAIL AT BRIDGE ENDS LOW VOLUME	1.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	5.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	1,898.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	860.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	912.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
706-01	GUARDRAIL REMOVED	935.000	L.F.
706-10.26	ROUNDED END ELEMENT	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	416.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,616.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,940.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	202.500	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	474.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	42.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	159.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	60.500	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	6,167.000	L.F.
717-01	MOBILIZATION	(1)	LS

Contract ID CNY272 - MACON

() Item will be bid as lump sum.

Contract ID CNY291 - MADISON

Contract ID: CNY291**Letting Date:** December 06, 2024 10:00 AM**Projects:** 57201-3159-44

NH-SIP-I-40-1(362)

Counties: MADISON**District:****DBE Goal Percent:** 8.00**Description:** The interchange improvements on I-40 at S.R. 138 (Exit 68) (L.M. 0.78 - L.M. 1.34), including grading, drainage, and paving.**Contract Time:** DT - 10/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	4,770.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	19,811.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,621.000	C.Y.
203-06	WATER	180.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	1,919.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	23.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	20.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-03.23	FILTER SOCK (24 INCH)	1,900.000	L.F.
209-05	SEDIMENT REMOVAL	134.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,090.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	540.000	L.F.
209-08.07	ROCK CHECK DAM	7.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	9.000	EACH
209-09.01	SANDBAGS	200.000	BAG
209-09.04	SEDIMENT FILTER BAG(15' X 10')	4.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	100.000	S.Y.

Contract ID CNY291 - MADISON

Item No.	Description	Quantity	Units
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	100.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	9,555.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	266.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (D)	200.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	29.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	737.000	TON
307-01.22	ASP. CONC. MIX(PG76-22) (BPMB-HM) GR. A-S	815.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	2,658.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	487.000	TON
307-03.10	ASPHALT CONC MIX (PG76-22)(BPMB-HM) GR CS	275.000	TON
309-01.01	MINERAL AGGREGATE (A-CBC)	1,181.000	TON
309-01.02	PORTLAND CEMENT (A-CBC)	49.000	TON
309-02	BITUMINOUS MATERIAL (A-CBC)	4.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	14.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	53.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	4,620.000	L.F.
411-03.10	ACS MIX(PG76-22) GRADING D	317.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	534.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	265.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	104.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	21,772.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	83.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	354.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	65.000	L.F.

Contract ID CNY291 - MADISON

Item No.	Description	Quantity	Units
607-37.07	48" CORRUGATED METAL PIPE CULVERT	6.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-02.12	JUNCTION BOX, TYPE 3	2.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	18.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	640.000	LB.
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	40.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	120.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	330.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	607.000	L.F.
707-03.01	STOCK FENCE	1,400.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	10.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (STOCK R.O.W. FENCE)	1,371.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,870.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	60.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	46.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	85.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	555.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	4,500.000	L.F.
710-05	LATERAL UNDERDRAIN	350.000	L.F.
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	25.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	5,375.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH

Contract ID CNY291 - MADISON

Item No.	Description	Quantity	Units
712-04.50	BARRIER RAIL DELINEATOR	270.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	18.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	704.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	4.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	200.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	121.000	LB.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	585.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	120.000	L.F.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	1,508.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	188.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,178.000	LB.
713-11.21	P POST SLIP BASE	30.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	66.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	573.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	456.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	150.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	221.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	177.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	160.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	160.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	203.000	L.F.

Contract ID CNY291 - MADISON

Item No.	Description	Quantity	Units
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	14.000	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	8.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	6.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,485.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,540.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	966.000	S.Y.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	270.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	246.000	UNIT
801-03	WATER (SEEDING & SODDING)	301.000	M.G.
803-01	SODDING (NEW SOD)	27,600.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	108.000	S.Y.
403-02.01	TRACKLESS TACK COAT	20.000	TON
403-02.02	HOT APPLIED TACK COAT	7.000	TON
403-02.01	TRACKLESS TACK COAT	30.000	TON

() Item will be bid as lump sum.

Contract ID CNY214 - MADISON

Contract ID: CNY214**Letting Date:** December 06, 2024 10:00 AM**Projects:** 57011-3226-94

PHSIP-20(57)

Counties: MADISON**District:****DBE Goal Percent:** 10.00**Description:** The improvement of the intersection on U.S. 412 (S.R. 20) at Old Bells Road (L.M. 5.62) in Jackson, including grading, drainage, and paving.**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (STA. 49+75 - STA. 52+45)	450.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,288.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	60.000	C.Y.
203-06	WATER	28.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.440	L.M.
209-05	SEDIMENT REMOVAL	17.500	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,450.000	L.F.
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	100.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,700.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	75.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	13.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	150.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	110.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	485.000	TON

Contract ID CNY214 - MADISON

Item No.	Description	Quantity	Units
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	150.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	10.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	6.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	137.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	550.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.170	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.450	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	537.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	110.000	L.F.
611-02.10	JUNCTION BOX, TYPE 1	1.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	730.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	124.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	125.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	60.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	839.500	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	3,130.000	L.F.
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	42.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
713-16.20	SIGNS (DESCRIPTION) (EAST, M3-2)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (U.S. ROUTE SIGN (US-412)	1.000	EACH

Contract ID CNY214 - MADISON

Item No.	Description	Quantity	Units
713-16.22	SIGNS (DESCRIPTION) (BIKE ROUTE, D11-1)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (HOSPITAL, D9-2)	1.000	EACH
713-16.24	SIGNS (DESCRIPTION) (DO NOT ENTER, R5-1)	4.000	EACH
713-16.25	SIGNS (DESCRIPTION) (WRONG WAY, R5-1A)	4.000	EACH
713-16.26	SIGNS (DESCRIPTION) (ONE WAY, R6-1L)	3.000	EACH
713-16.27	SIGNS (DESCRIPTION) (ONE WAY, R6-1R)	1.000	EACH
713-16.28	SIGNS (DESCRIPTION) (DISTANCE,(2 LINES)	1.000	EACH
713-16.29	SIGNS (DESCRIPTION) (DIVIDED HIGHWAY, R6-3A)	1.000	EACH
713-16.30	SIGNS (DESCRIPTION) (KEEP RIGHT, R4-7)	1.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	30.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	40.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	40.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	200.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	130.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	11.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	165.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.192	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	1,360.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	145.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	2.990	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,790.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.495	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,010.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	2.000	EACH

Contract ID CNY214 - MADISON

Item No.	Description	Quantity	Units
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	5.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	1.000	EACH
730-03.20	INSTALL PULL BOX (TYPE A)	5.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	6.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	219.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	629.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	532.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	427.000	L.F.
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	993.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	30.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	30.000	L.F.
730-13.03	VEHICLE DETECTOR (4 - CHANNEL, RACK MOUNT)	2.000	EACH
730-14.01	SHIELDED DETECTOR CABLE	2,002.000	L.F.
730-14.02	SAW SLOT	947.000	L.F.
730-14.03	LOOP WIRE	2,598.000	L.F.
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	4.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	310.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	10.000	UNIT
801-03	WATER (SEEDING & SODDING)	12.000	M.G.
803-01	SODDING (NEW SOD)	1,100.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY285 - MARSHALL

Contract ID: CNY285**Letting Date:** December 06, 2024 10:00 AM**Projects:** 59S417-F8-002

STP-417(12)

Counties: MARSHALL**District:****DBE Goal Percent:****Description:** The microsurfacing on S.R. 417 from near North Ellington Parkway (L.M. 0.12) to S.R. 373 (L.M. 1.90).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	3.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	458.000	TON
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	8.000	TON
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	84.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	694.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	93.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	2.000	EACH
712-06	SIGNS (CONSTRUCTION)	332.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	263.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	59.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	217.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	122.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	87.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	360.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.300	L.M.

Contract ID CNY285 - MARSHALL

Item No.	Description	Quantity	Units
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	54.000	S.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	1,320.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	122.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	87.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	360.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	1.000	EACH
716-08.19	REMOVAL OF PAVEMENT MARKING (YIELD LINE)	54.000	S.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	7.700	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	7.700	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY286 - MONTGOMERY

Contract ID: CNY286**Letting Date:** December 06, 2024 10:00 AM**Projects:** 63S048-F8-005

STP-48(71)

Counties: MONTGOMERY**District:****DBE Goal Percent:** 6.00**Description:** The resurfacing on S.R. 48 from U.S. 79 (S.R. 13) (L.M. 6.86) to the Kentucky State line (L.M. 12.44).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	7.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,027.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	28.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	5,746.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	6.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,801.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,606.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,253.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,253.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,640.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	228.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	28.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	27.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	617.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.700	L.M.

Contract ID CNY286 - MONTGOMERY

Item No.	Description	Quantity	Units
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	9.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	15.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	15.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	685.000	L.F.
730-14.03	LOOP WIRE	1,570.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY298 - PERRY

Contract ID: CNY298**Letting Date:** December 06, 2024 10:00 AM**Projects:** 68S020-F8-002

NH-20(90)

Counties: PERRY**District:****DBE Goal Percent:** 4.00**Description:** The resurfacing (either microsurface or thin mix overlay) on U.S. 412 (S.R. 20) from the Decatur County line (L.M. 0.00) to west of Deer Valley Road (L.M. 6.10).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.200	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,614.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	8,531.000	S.Y.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	2.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	10.300	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	107.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	883.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	403.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	403.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	12.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	160.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	152.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	46.000	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	2.700	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN	23.000	L.M.

Contract ID CNY298 - PERRY

Item No.	Description	Quantity	Units
	LINE)		
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	18.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	3,483.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	66.000	TON
712-06	SIGNS (CONSTRUCTION)	816.000	S.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	2.700	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	12.000	TON
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	158.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	1,315.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	47.000	TON
712-06	SIGNS (CONSTRUCTION)	464.000	S.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	12.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	160.000	L.F.
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	152.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	23.000	L.M.

() Item will be bid as lump sum.

Contract ID CNY118 - RHEA**Contract ID:** CNY118**Letting Date:** December 06, 2024 10:00 AM**Projects:** 72S029-F8-008
72S029-M3-009

NH-29(127)

NH-29(127)

Counties: RHEA**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on U.S. 27 (S.R. 29) from south of Boofer Lane (L.M. 14.56) to south of Metzger Lane (L.M. 19.80), including bridge expansion joint repairs.**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,040.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	61,113.000	S.Y.
403-02.01	TRACKLESS TACK COAT	80.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	12,121.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	9.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	11,918.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	330.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	165.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,965.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	825.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	825.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	67.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	144.000	L.F.

Contract ID CNY118 - RHEA

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	16.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	156.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	34.600	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	144.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	23.600	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	675.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,585.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	160.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY302 - ROANE

Contract ID: CNY302**Letting Date:** December 06, 2024 10:00 AM**Projects:** 73I040-F8-005

NH-I-40-7(186)

Counties: ROANE**District:****DBE Goal Percent:** 6.00**Description:** The resurfacing on I-40 from near S.R. 58 and S.R. 326 (L.M. 16.24) to the Loudon County line (L.M. 22.98).**Contract Time:** DT - 10/31/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	27.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	35.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	19,197.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	101.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	178.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	20,539.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	27.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	20,532.000	TON
502-08.01	RESEALING JOINTS (HOT POURED ELASTIC)	4,265.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	381.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	190.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,643.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	2.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY

Contract ID CNY302 - ROANE

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.12	RAISED PVTM MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	354.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,682.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,682.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	239.000	S.Y.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,371.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	5.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	7.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	48.000	S.F.
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	36.000	L.M.
716-10.07	PREFORMED PLASTIC PAVEMENT MARKING (STOP LINE)	80.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVTM MRKNG (6IN LINE)	36.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVTM MRKNG (8IN BARRIER LINE)	6,163.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVTM MRKNG (6IN DOTTED LINE)	2,493.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	4,823.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	2,237.000	L.F.
403-02.01	TRACKLESS TACK COAT	298.000	TON
403-02.02	HOT APPLIED TACK COAT	224.000	TON

() Item will be bid as lump sum.

Contract ID CNY275 - ROBERTSON

Contract ID: CNY275**Letting Date:** December 06, 2024 10:00 AM**Projects:** 74S065-F8-002

STP-65(27)

Counties: ROBERTSON**District:****DBE Goal Percent:** 7.50**Description:** The resurfacing on U.S. 431 (S.R. 65) from Brick School Road (L.M. 14.49) to the Kentucky State line (L.M. 16.20).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	3.400	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	426.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	57.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	100.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	12.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	1,832.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	3.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	1,814.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	444.000	S.F.
713-16.20	SIGNS (DESCRIPTION) (W11-10)	2.000	EACH
713-16.21	SIGNS (DESCRIPTION) (W1-4L)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (W1-4R)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (TN-17B)	2.000	EACH
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (M1- 4a)	1.000	EACH
713-16.51	REMOVE AND REPLACE SIGN (DESCRIPTION) (M3- 1)	1.000	EACH

Contract ID CNY275 - ROBERTSON

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	113.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	51.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	5.700	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.700	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY297 - ROBERTSON

Contract ID: CNY297**Letting Date:** December 06, 2024 10:00 AM**Projects:** 74S257-F3-004

STP/HSIP-257(14)

74S257-F8-004

STP/HSIP-257(14)

74S258-F8-002

STP-258(16)

Counties: ROBERTSON**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on S.R. 257 from west of U.S. 41 (S.R. 11) (L.M. 11.69) to the Sumner County line (L.M. 14.50), and on S.R. 258 from the Sumner County line (L.M. 0.00) to S.R. 76 (L.M. 0.56).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	558.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	476.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	446.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	25.100	TON
411-02.10	ACS MIX(PG70-22) GRADING D	3,584.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	5.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	3,927.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	50.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,184.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS	186.000	EACH

Contract ID CNY297 - ROBERTSON

Item No.	Description	Quantity	Units
	(BI-DIR) (1 COLOR)		
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	186.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	160.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	153.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	268.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	313.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	1.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	3.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	35.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	14.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	14.100	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	858.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	72.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	64.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	919.000	L.F.
730-14.03	LOOP WIRE	2,038.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY274 - ROBERTSON

Contract ID: CNY274**Letting Date:** December 06, 2024 10:00 AM**Projects:** 74S049-F3-002
74S049-F8-002STP/HSIP-49(58)
STP/HSIP-49(58)**Counties:** ROBERTSON**District:****DBE Goal Percent:** 7.50**Description:** The resurfacing on S.R. 49 from S.R. 25 (L.M. 16.81) to north of S.R. 52 (L.M. 23.51).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
203-06	WATER	14.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.300	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,758.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	2,912.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	35.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,039.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	10.700	L.M.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	3.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
706-01	GUARDRAIL REMOVED	150.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	552.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	433.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	433.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	255.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	74.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	26.800	L.M.

Contract ID CNY274 - ROBERTSON

Item No.	Description	Quantity	Units
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,316.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	26.800	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY307 - SHELBY

Contract ID: CNY307**Letting Date:** December 06, 2024 10:00 AM**Projects:** 79961-3280-94

HSIP-3(154)

Counties: SHELBY**District:****DBE Goal Percent:** 4.00**Description:** The installation of multimodal signal and intersection upgrades on U.S. 51 (S.R. 3) at U.S. 78 (S.R. 4, Lamar Avenue) (L.M. 9.30) and at Eastmoreland Avenue (L.M. 9.81) in Memphis.**Contract Time:** DT - 7/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	139.000	S.Y.
203-07	FURNISHING & SPREADING TOPSOIL	1.000	C.Y.
209-05	SEDIMENT REMOVAL	1.000	C.Y.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	39.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	39.000	TON
701-01.02	CONCRETE SIDEWALK (6 ")	53.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	1,248.000	S.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	492.500	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	12.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	410.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	185.000	LB.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (R10-15R)	8.000	EACH
714-09.03	LUMINAIRES (250 WATT)	1.000	EACH
714-14.02	MASTARM - 6'	1.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (MLGW OVERHEAD LUMINAIRE SERVICE)	(1)	LS

Contract ID CNY307 - SHELBY

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	285.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	585.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	585.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	285.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	8.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	4.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	740.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	760.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	1.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	120.000	L.F.
730-15.11	MODIFY CABINET (DESCRIPTION) (WIRING AND CONTROLLER SETTINGS)	2.000	EACH
730-26.06	PEDESTRIAN PUSHBUTTON POST	9.000	EACH
730-26.09	PEDESTRIAN PUSHBUTTON WITH 15IN SIGN	16.000	EACH
801-01	SEEDING (WITH MULCH)	0.200	UNIT
801-02	SEEDING (WITHOUT MULCH)	0.200	UNIT
803-01	SODDING (NEW SOD)	1.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY292 - SUMNER

Contract ID: CNY292**Letting Date:** December 06, 2024 10:00 AM**Projects:** 83950-3565-04

N/A

Counties: SUMNER**District:****DBE Goal Percent:****Description:** The grading, drainage, signals, and paving on a S.I.A. route serving Project Woolhawk (Facebook Data Center), including U.S. 31E (S.R. 6) and S.R. 25.**Contract Time:** DT - 12/15/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.56	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (EXISTING 5.5' X4' BOX CULVERT AT STA. 75+20.00 ON GALLATIN PIKE)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	7,022.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	600.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	155.000	C.Y.
203-05	UNDERCUTTING	395.000	C.Y.
203-06	WATER	20.000	M.G.
204-08	FOUNDATION FILL MATERIAL	120.000	C.Y.
209-05	SEDIMENT REMOVAL	38.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,076.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	2,180.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	8.000	EACH
209-09.01	SANDBAGS	700.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	3.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	20.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	8,295.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	18.000	TON

Contract ID CNY292 - SUMNER

Item No.	Description	Quantity	Units
303-10.01	MINERAL AGGREGATE (SIZE 57)	47.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	3,212.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,050.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	28.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	111.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	6,200.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	1,222.000	TON
415-01.03	COLD PLANING BITUMINOUS PAVEMENT	400.000	C.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	83.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	15,930.000	LB.
621-03.05	36" TEMPORARY DRAINAGE PIPE	75.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,451.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	7.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	8.000	EACH
706-01	GUARDRAIL REMOVED	467.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	930.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,900.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	212.000	S.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,000.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	39.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	8.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	74.000	S.F.
713-16.20	SIGNS (DESCRIPTION) (R10-12)	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	32.000	EACH

Contract ID CNY292 - SUMNER

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	100.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	17.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	125.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.900	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	6,500.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.600	L.M.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	1,200.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	651.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-01.03	MODIFICATION OF EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	5.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	5.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	3.000	EACH
730-03.36	FIBER SPLICE ENCLOSURE (DESCRIPTION) (12F)	1.000	EACH
730-03.41	ETHERNET SWITCH (FIELD LAYER 2)	2.000	EACH
730-03.54	FIBER OPTIC DROP CABLE (12F)	225.000	L.F.
730-03.57	FIBER OPTIC DROP PANEL (DESCRIPTION) (12F)	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-05.04	MODIFY EXISTING ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,195.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	415.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	65.000	L.F.
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	90.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	2.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.07	CABINET (DESCRIPTION) (16 PHASE TS2-TYPE 1)	2.000	EACH

Contract ID CNY292 - SUMNER

Item No.	Description	Quantity	Units
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-23.95	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 45')	1.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	2.000	EACH
801-01	SEEDING (WITH MULCH)	15.000	UNIT
801-01.02	CROWN VETCH MIXTURE (WITH MULCH)	8.000	UNIT
801-03	WATER (SEEDING & SODDING)	20.000	M.G.
803-01	SODDING (NEW SOD)	840.000	S.Y.
805-12.03	EROSION CONTROL BLANKET (TYPE III)	540.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY306 - TIPTON

Contract ID: CNY306**Letting Date:** December 06, 2024 10:00 AM**Projects:** 84S003-F3-002

NH/HSIP-3(172)

84S003-F8-002

NH/HSIP-3(172)

84S003-M3-003

NH/HSIP-3(172)

Counties: TIPTON**District:****DBE Goal Percent:** 8.00**Description:** The resurfacing on U.S. 51 (S.R. 3) from East Woodlawn Avenue (L.M. 9.60) to Winn Street (L.M. 15.40), including bridge expansion joint repairs and thin epoxy overlay.**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	880.000	S.Y.
203-06	WATER	28.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.200	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	3,666.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	405.000	TON
403-02.01	TRACKLESS TACK COAT	102.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	14.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	18,598.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	9.600	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	11.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	18,223.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	50.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNY306 - TIPTON

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	320.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,952.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	193.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	761.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	709.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	96.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	57.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	541.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	31.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	3,126.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	15.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	4.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	108.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	27.200	L.M.
716-09.88	CONTRAST PAVEMENT MARKING 8"	0.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	27.200	L.M.
717-01	MOBILIZATION	(1)	LS
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	50.000	L.F.
730-14.01	SHIELDED DETECTOR CABLE	50.000	L.F.
730-14.02	SAW SLOT	2,244.000	L.F.
730-14.03	LOOP WIRE	4,488.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	89.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	1,341.000	S.Y.

Contract ID CNY306 - TIPTON

() Item will be bid as lump sum.

Contract ID CNY310 - WASHINGTON

Contract ID: CNY310**Letting Date:** December 06, 2024 10:00 AM**Projects:** 90S081-F3-003
90S081-F8-003STP-NH/HSIP-81(27)
STP-NH/HSIP-81(27)**Counties:** WASHINGTON**District:****DBE Goal Percent:** 7.00**Description:** The resurfacing on S.R. 81 from near Ridgecrest Drive (L.M. 10.97) to S.R. 75 (L.M. 17.99).**Contract Time:** DT - 8/31/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	795.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,077.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	86.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	5,390.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	1.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	600.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	4.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	34.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	17.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,549.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	520.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	32.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	552.000	EACH

Contract ID CNY310 - WASHINGTON

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	290.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	720.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	5.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	60.000	L.F.
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	8.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	914.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	150.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	11.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	28.000	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	335.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY277 - WAYNE

Contract ID: CNY277**Letting Date:** December 06, 2024 10:00 AM**Projects:** 91S013-F8-005

STP-13(95)

Counties: WAYNE**District:****DBE Goal Percent:** 7.00**Description:** The resurfacing on S.R. 13 from south of Chalk Creek Road (L.M. 21.50) to Hill Street West (L.M. 26.80).**Contract Time:** DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,403.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	49.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,286.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	6.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	7,218.000	TON
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	64.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,940.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	350.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	350.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	321.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	150.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	510.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-03.09	PLASTIC WORD PAVEMENT MARKING () ("20 MIN MAX")	9.000	EACH

Contract ID CNY277 - WAYNE

Item No.	Description	Quantity	Units
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	286.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	20.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	20.200	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY215 - WILLIAMSON

Contract ID: CNY215**Letting Date:** December 06, 2024 10:00 AM**Projects:** 94007-3235-94**HSIP-11(111)****Counties:** WILLIAMSON**District:****DBE Goal Percent:** 9.00**Description:** The intersection improvements including signals on U.S. 31A (S.R. 11, Nolensville Road) from south of Sanford Road (L.M. 13.25) to south of Summerlyn Drive (L.M. 13.6).**Contract Time:** DT - 12/15/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	45.000	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	750.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.270	L.M.
209-05	SEDIMENT REMOVAL	138.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	3,350.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	5,676.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	7.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	122.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	787.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	557.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	454.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	6.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	19.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	9.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	140.000	TON
411-01.11	ACS MIX(PG64-22) GRADING E RDWY	150.000	TON

Contract ID CNY215 - WILLIAMSON

Item No.	Description	Quantity	Units
411-02.10	ACS MIX(PG70-22) GRADING D	368.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	469.000	TON
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	125.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	60.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	23.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	48.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	50.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,710.000	L.F.
712-02.36	REMOVE AND RELOCATE PORTABLE BARRIER RAIL	1,600.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	5.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	68.000	EACH
712-06	SIGNS (CONSTRUCTION)	318.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-09.09	REMOVABLE PAVEMENT MARKING (4" line)	4,225.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	295.000	LB.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	42.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	80.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	125.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	12.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	22.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	707.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	90.000	L.F.

Contract ID CNY215 - WILLIAMSON

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.060	L.M.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	4,000.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	7.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	5.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	850.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	200.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	850.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	4.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.72	CANTILEVER SIGNAL SUPPORT (1 ARM @ 35')	1.000	EACH
730-23.88	CANTILEVER SIGNAL SUPPORT (1 ARM @ 45')	2.000	EACH
730-25.01	CANTILEVER SIGNAL SUPPORT (1 ARM @ 50')	1.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	1.000	EACH
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	150.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	450.000	L.F.
801-01	SEEDING (WITH MULCH)	59.000	UNIT
801-03	WATER (SEEDING & SODDING)	6.000	M.G.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	6,540.000	S.Y.

Contract ID CNY215 - WILLIAMSON

Item No.	Description	Quantity	Units
791-01.06	8IN STEEL GAS MAIN	1,310.000	L.F.
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-03.05	6IN HDPE GAS MAIN	1,330.000	L.F.
791-06.04	CONNECT TO 6IN EX. PE MAIN	3.000	EACH
791-06.12	CONNECT TO 6IN EX. STL MAIN	1.000	EACH
791-06.13	CONNECT TO 8IN EX. STL MAIN	1.000	EACH
791-07.03	6IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.12	8IN STEEL GAS VALVE ASSEMBLY	1.000	EACH
791-08.07	3/4IN PE SERVICE PIPE	6.000	L.F.
791-09.03	17LB MAGNESIUM ANODES	5.000	EACH
791-09.21	CATHODIC PROTECTION JUNCTION BOX	1.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	965.000	L.F.
793-14.40	10IN SPLIT CONDUIT (FMP)	965.000	L.F.
793-14.41	LATERALLY ADJUST CONDUIT BANK	490.000	L.F.

() Item will be bid as lump sum.

