

Estimated Quantities -- Letting February 09, 2024

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNY902 - CUMBERLAND & WHITE

Contract ID: CNY902

Letting Date: February 09, 2024 10:00 AM

Projects: 18S001-F3-003	STP/HSIP-1(470)
18S001-F8-003	STP/HSIP-1(470)
18S001-M3-006	STP/HSIP-1(470)
93S111-F8-003	NH-111(123)
93S111-M3-006	NH-111(123)

Counties: CUMBERLAND, WHITE

District:

DBE Goal Percent: 3.00

Description: The microsurfacing on U.S. 70 (S.R. 1) in Cumberland County from west of Dorton Access Road to west of Bullard Road and on S.R. 111 in White County from the Van Buren County line to Shady Oak Road.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	41.000	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	45.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	126,587.000	S.Y.
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	425.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	3,542.000	TON
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	3,420.000	EACH
711-04.21	CONCRETE BARRIER DELINEATION ENHANCEMENT	372.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	212.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	52.000	EACH

Contract ID CNY902 - CUMBERLAND & WHITE

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,877.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	122.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,087.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	570.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	373.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	2,030.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,890.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	893.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	23.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,680.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	1.100	L.M.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	4.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	188.000	S.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	624.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	41.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	64.600	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,053.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	500.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	162.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	85.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	82.000	S.Y.

Contract ID CNY902 - CUMBERLAND & WHITE

Item No.	Description	Quantity	Units
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	4,123.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY900 - HAMILTON

Contract ID: CNY900

Letting Date: February 09, 2024 10:00 AM

Projects: 33006-3136-44

STP-I-124-3(83)

Counties: HAMILTON

District:

DBE Goal Percent: 5.00

Description: The landscaping on I-124 (U.S. 27, S.R. 29) from the I-24/I-124 interchange (L.M. 1.15) to south of the Tennessee River (Olgiate) Bridge (L.M. 1.95).

Contract Time: DT - 11/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	45.000	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	55.000	C.Y.
209-05	SEDIMENT REMOVAL	150.000	C.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	6.000	EACH
303-10.01	MINERAL AGGREGATE (SIZE 57)	5.000	TON
709-05.05	MACHINED RIP-RAP (CLASS A-3)	300.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	23.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	570.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	125.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	216.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (DO NOT MOW)	3.000	EACH
717-01	MOBILIZATION	(1)	LS
721-01.01	BENCH	274.000	EACH
721-01.07	1" CONTROL VALVE (RAIN BIRD PEB-100)	7.000	EACH
721-01.08	1-1/2" CONTROL VALVE (RAIN BIRD PEB-150)	9.000	EACH

Contract ID CNY900 - HAMILTON

Item No.	Description	Quantity	Units
721-01.12	1" QUICK COUPLER VALVE (RAIN BIRD 44LRC)	9.000	EACH
721-01.13	ISOLATION VALVE (CLASS 125 BRONZE)	6.000	EACH
721-01.14	1-1/2" MASTER VALVE (BUCKNER-SUPERIOR 3100)	1.000	EACH
721-01.15	1-1/2" BACKFLOW PREVENTER	1.000	EACH
721-01.16	2-WIRE DECODER CONTROLLER (RAIN BIRD LXDIVM-LXMSS-LXMMPED)	1.000	EACH
721-01.17	FIELD DECODER (RAIN BIRD FD-101-TURF)	7.000	EACH
721-01.18	FIELD DECODER (RAIN BIRD FD-202-TURF)	3.000	EACH
721-01.19	FIELD DECODER (RAIN BIRD FD-401-TURF)	1.000	EACH
721-01.21	SENSOR DECODER (RAIN BIRD SD-210-TURF)	1.000	EACH
721-01.22	WIRELESS RAIN/FREEZE SENSOR (RAIN BIRD WR2-RFS)	1.000	EACH
721-01.23	1.5" FLOW SENSOR (CREATIVE SENSOR TECHNOLOGY FSI-T15-001)	1.000	EACH
721-01.24	SURGE ARRESTOR AND 2-WIRE GROUNDING POINT (RAIN BIRD LSP01)	8.000	EACH
721-01.25	1-1/2" WATER METER	1.000	EACH
721-01.28	IRRIGATION LATERAL LINE (PVC CLASS 200 SDR 21 1")	6,200.000	L.F.
721-01.29	IRRIGATION LATERAL LINE (PVC CLASS 200 SDR 21 1-1/2")	720.000	L.F.
721-01.30	IRRIGATION LATERAL LINE (PVC CLASS 200 SDR 21 2")	5.000	L.F.
721-01.33	IRRIGATION MAINLINE (PVC CLASS 200 SDR 21 1")	20.000	L.F.
721-01.34	IRRIGATION MAINLINE (PVC CLASS 200 SDR 21 1-1/2")	230.000	L.F.
721-01.35	IRRIGATION MAINLINE (PVC CLASS 200 SDR 21 2")	1,640.000	L.F.
721-01.37	4" PVC SCHEDULE 40 (DIRECTIONAL BORE)	313.000	L.F.
721-01.39	1-1/4" PVC SCHEDULE 40 ELECTRICAL CONDUIT(DIRECT BURIAL)	1,560.000	L.F.
721-01.40	1-1/4" PVC SCHEDULE 40 ELECTRICAL CONDUIT(DIRECTIONAL BORE)	313.000	L.F.
721-01.41	CONTROL WIRE CABLE (RAIN BIRD MAXI-WIRE)	2,100.000	L.F.
721-01.42	IRRIGATION DRIPLINE HEADER (RAIN BIRD XQF-1, 1")	1,470.000	L.F.

Contract ID CNY900 - HAMILTON

Item No.	Description	Quantity	Units
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	520.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	5,056.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	70.000	UNIT
801-01.65	TEMPORARY MULCH	185.000	UNIT
802-01.10	TREES (DESCRIPTION) (ACER BUERGERIANUM 'AERYN')	18.000	EACH
802-01.11	TREES (DESCRIPTION) (AMELANCHIER X GRANDIFLORA 'AUTUMN BRILLIANCE')	30.000	EACH
802-01.12	TREES (DESCRIPTION) (CEDRUS DEODARA')	11.000	EACH
802-01.13	TREES (DESCRIPTION) (CERCIS CANADENSIS 'FOREST PANSY')	22.000	EACH
802-01.14	TREES (DESCRIPTION) (CRATAEGUS VIRDIS 'WINTER KING')	31.000	EACH
802-01.15	TREES (DESCRIPTION) (CRYPTOMERIA JAPONICA)	19.000	EACH
802-01.16	TREES (DESCRIPTION) (ILEX 'NELLIE R. STEVENS')	35.000	EACH
802-01.17	TREES (DESCRIPTION) (JUNIPERUS VIRGINIANA 'BURKII')	118.000	EACH
802-01.18	TREES (DESCRIPTION) (LAGERSTROEMIA INDICA 'DYNAMITE')	26.000	EACH
802-01.19	TREES (DESCRIPTION) (LIRIODENDRON TULIPIFERA 'ARNOLD')	5.000	EACH
802-01.20	TREES (DESCRIPTION) (MAGNOLIA GRANDIFLORA 'D.D. BLANCHARD')	6.000	EACH
802-01.21	TREES (DESCRIPTION) (MAGNOLIA X SOULANGIANA)	24.000	EACH
802-01.22	TREES (DESCRIPTION) (NYSSA SYLVATICA 'DAVID ODOM')	6.000	EACH
802-03.01	SHRUBS (DESCRIPTION) (CALLICARPA AMERICANA)	72.000	EACH
802-03.02	SHRUBS (DESCRIPTION) (HYDRANGEA QUERCIFOLIA 'ALICE')	17.000	EACH
802-03.03	SHRUBS (DESCRIPTION) (ILEX GLABRA 'COMPACTA')	10.000	EACH
802-03.04	SHRUBS (DESCRIPTION) (ITEA VIRGINICA 'HENRY'S GARNET')	27.000	EACH
802-04.70	GROUND COVER (DESCRIPTION) (AMSONIA TABERNAEMONTANA)	1,657.000	EACH

Contract ID CNY900 - HAMILTON

Item No.	Description	Quantity	Units
802-04.71	GROUND COVER (DESCRIPTION) (ANDROPOGON GERARDII 'RED OCTOBER')	1,151.000	EACH
802-04.72	GROUND COVER (DESCRIPTION) (PANICUM VIRGATUM 'NORTHWIND')	2,755.000	EACH
802-04.73	GROUND COVER (DESCRIPTION) (PERENNIAL MIX 1)	1,656.000	EACH
802-04.74	GROUND COVER (DESCRIPTION) (PERENNIAL MIX 2)	3,866.000	EACH
802-04.75	GROUND COVER (DESCRIPTION) (PERENNIAL MIX 3)	1,247.000	EACH
802-05	WATER (PLANT ESTABLISHMENT)	672.000	M.G.
802-06.01	LANDSCAPE MULCH (SHREDDED HARDWOOD)	1,250.000	C.Y.
802-60.99	PLANTING BED (TREES, SHRUBS, PERENNIALS)	89,670.000	S.F.
802-70.99	PLANTING BED (WILDFLOWER AND PRAIRIE GRASS SEED MIX)	66,297.000	S.F.
803-01	SODDING (NEW SOD)	330.000	S.Y.
806-02.03	PROJECT MOWING	3.000	CYCL

() Item will be bid as lump sum.

Contract ID CNY901 - JACKSON

Contract ID: CNY901

Letting Date: February 09, 2024 10:00 AM

Projects: 44NMSC-S3-004

NA

Counties: JACKSON

District:

DBE Goal Percent:

Description: The construction of a TDOT maintenance building at 2636 S Grundy Quarles Highway in Gainesboro.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
607-65.20	SITE PREPARATION	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (FOUNDATION AND STRUCTURE)	1.000	EACH
680-02.02	BUILDING (DESCRIPTION) (INTERIOR CONSTRUCTION)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY053 - ANDERSON , BLOUNT, ETC.

Contract ID: CNY053

Letting Date: February 09, 2024 10:00 AM

Projects: R1BVAR-M3-038

n/a

R1BVAR-M3-039

NA

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER, GREENE,
HAMBLÉN, HANCOCK, HAWKINS,
JEFFERSON, JOHNSON, KNOX, LOUDON,
MONROE, MORGAN, ROANE, SCOTT,
SEVIER, SULLIVAN, UNICOI, UNION,
WASHINGTON

District:

DBE Goal Percent:

Description: The retracing of pavement markings with spray thermoplastic and random on-call pavement marking on various Interstate and State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	5.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	5.000	L.M.
712-01.50	MAINTENANCE OF TRAFFIC	30.000	EACH
713-02.34	DELINEATORS (ALL)	300.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	250.000	EACH
716-01.12	RAISED PVMT MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	250.000	EACH
716-01.13	RAISED PVMT MARKERS (BI-DIRECTIONAL) (2 COLOR LENS)	250.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	250.000	EACH

Contract ID CNY053 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	250.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	250.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	250.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	150.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	500.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	350.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	45.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	100.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	200.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	60.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	15.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	10.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	5.000	EACH
716-03.04	PLASTIC WORD PAVEMENT MARKING (SCHOOL)	5.000	EACH
716-03.05	PLASTIC WORD PAVEMENT MARKING (BIKE LANE)	10.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	8.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	10.000	EACH
716-03.08	PLASTIC WORD PAVEMENT MARKING (PED-XING)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	5.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	5.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	200.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	10.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	10.000	EACH

Contract ID CNY053 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	10.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	10.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	20.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	5.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	75.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	20.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	20.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	15.000	L.M.
716-05.72	PERFORMANCE BASED RETRACING SPRAY THERMO 4IN	411.000	L.M.
716-05.73	PERFORMANCE BASED RETRACING SPRAY THERMO 6IN	2,561.000	L.M.
716-05.74	PERFORMANCE BASED RETRACING SPRAY THERMO 8IN	132,000.000	L.F.
716-05.79	PERFORMANCE BASED RETRACING SPRAY THERMO 12IN	4.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	5,000.000	L.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	500.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	100.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	50.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	200.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	50.000	L.F.
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	50.000	L.F.

Contract ID CNY053 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	5.000	EACH
716-08.12	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	3.000	EACH
716-08.13	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (SCHOOL)	2.000	EACH
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.000	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	25.000	EACH
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	5.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	175.000	L.F.
716-12.04	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN DOTTED LINE)	175.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	175.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	300.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	75.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	100.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	100.000	L.F.
716-13.06	SPRAY THERMO PVMT MRKNG (40 mil) (4IN LINE)	20.000	L.M.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	45.000	L.M.
716-13.08	SPRAY THERMO PVMT MRKNG (40 mil) (8IN BARRIER LINE)	7,000.000	L.F.
716-13.09	SPRAY THERMO PVMT MRKNG (40 mil) (4IN DOTTED LINE)	100.000	L.F.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	2,500.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	11.000	L.M.
717-01	MOBILIZATION	(1)	LS
717-01.03	MOBILIZATION (PER CALL-OUT)	15.000	EACH

Contract ID CNY053 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
717-01.04	MOBILIZATION (DESCRIPTION) (PER LEVEL 1 CALL-OUT)	3.000	EACH

() Item will be bid as lump sum.

Contract ID CNY007 - ANDERSON , BLOUNT, ETC.

Contract ID: CNY007

Letting Date: February 09, 2024 10:00 AM

Projects: R1BVAR-F3-031

NH-098-1(23)

Counties: ANDERSON, BLOUNT, CAMPBELL, COCKE,
GREENE, JEFFERSON, KNOX, LOUDON,
MONROE, ROANE, SEVIER, SULLIVAN,
WASHINGTON

District:

DBE Goal Percent:

Description: The Knoxville SmartWay Intelligent Transportation System (ITS) Maintenance (2023- 2026).

Contract Time: DT - 5/31/2027

Item No.	Description	Quantity	Units
725-10.75	TDOT SMARTWAY ITS SYSTEM MAINTENANCE (3 YEARS)	(1)	LS
725-10.76	REPAIR MAINTENANCE LABOR	5,000.000	HOUR
725-10.77	SPARE PARTS AND EQUIPMENT REPLACEMENT	1,000,000.000	DOLL
725-10.78	ONE CALL SERVICE	5,000.000	HOUR
725-10.79	SOFTWARE AND NETWORK MAINTENANCE AND SUPPORT	750,000.000	DOLL
725-10.80	SPECIAL MAINTENANCE REPAIR	4,000,000.000	DOLL

() Item will be bid as lump sum.

Contract ID CNY052 - ANDERSON , CAMPBELL, ETC.

Contract ID: CNY052

Letting Date: February 09, 2024 10:00 AM

Projects: R1BVAR-M3-040

n/a

Counties: ANDERSON, CAMPBELL, CARTER, COCKE,
GRAINGER, GREENE, HAMBLEN, HAWKINS,
JOHNSON, MONROE, MORGAN, SCOTT,
SEVIER, SULLIVAN, UNICOI

District:

DBE Goal Percent:

Description: The retracing of painted pavement marking lines on various Interstate and State Routes.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
716-05.69	PERFORMANCE BASED RETRACING PAINTED 4IN LINE	781.000	L.M.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	5.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY051 - ANDERSON , CAMPBELL, ETC.

Contract ID: CNY051

Letting Date: February 09, 2024 10:00 AM

Projects: R1BVAR-M3-041

n/a

Counties: ANDERSON, CAMPBELL, COCKE,
GRAINGER, GREENE, HAMBLEN,
JEFFERSON, KNOX, LOUDON, UNION

District:

DBE Goal Percent:

Description: The relensing of snowplowable pavement markers on various Interstate and State Routes.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
705-07.11	TRUCK MOUNTED ENERGY ATTENUATOR	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	128.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	250.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	58,873.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY064 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNY064

Letting Date: February 09, 2024 10:00 AM

Projects: R3BVAR-M3-046

NA

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The random on-call concrete pavement repair on various Interstate and State Routes.

Contract Time: DT - 3/31/2025

Item No.	Description	Quantity	Units
502-02	HOLES	10.000	EACH
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	1,750.000	C.Y.
502-03.26	PARTIAL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	50.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	11,500.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	4,000.000	EACH
502-04.03	TRANSVERSE TIE-BARS	735.000	EACH
502-08	PRE-ROLLING	8.000	S.Y.
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	8,000.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	2,500.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	200.000	L.F.
502-10	CEMENT-FLY ASH GROUT	40.000	C.F.
503-01	GRINDING CONCRETE PAVEMENT	425.000	S.Y.
503-60	RETROFIT DOWEL BAR	50.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-01.02	LANE CLOSURE	10.000	EACH

Contract ID CNY064 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
712-01.03	LANE CLOSURE(NIGHT WORK)	9.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	160.000	EACH
712-06	SIGNS (CONSTRUCTION)	560.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	100.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	20.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	3,100.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.10	SNOWPLOWABLE REFLECTIVE MARKER	5.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	8.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	100.000	L.F.
717-01.04	MOBILIZATION (DESCRIPTION) (WORK ORDER)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNY044 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNY044

Letting Date: February 09, 2024 10:00 AM

Projects: R3BVAR-M3-047

NA

R3BVAR-M3-048

NA

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The retracing of pavement markings with spray thermoplastic and random on-call pavement marking on various Interstate and State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	5.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	5.000	L.M.
712-01.50	MAINTENANCE OF TRAFFIC	30.000	EACH
713-02.34	DELINEATORS (ALL)	250.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	250.000	EACH
716-01.12	RAISED PVMT MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	250.000	EACH
716-01.13	RAISED PVMT MARKERS (BI-DIRECTIONAL) (2 COLOR LENS)	250.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS	250.000	EACH

Contract ID CNY044 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
716-01.22	(BI-DIR) (1 COLOR) SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	200.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	250.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	175.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	250.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	250.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	2,000.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	200.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	60.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,400.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,400.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	25.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	15.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	5.000	EACH
716-03.04	PLASTIC WORD PAVEMENT MARKING (SCHOOL)	5.000	EACH
716-03.05	PLASTIC WORD PAVEMENT MARKING (BIKE LANE)	5.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	25.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	5.000	EACH
716-03.08	PLASTIC WORD PAVEMENT MARKING (PED-XING)	5.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	8.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	5.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	100.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	14.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY)	5.000	EACH

Contract ID CNY044 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
	ARROW)		
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	5.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	7.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	7.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	5.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	150.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	10.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	5.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	10.000	L.M.
716-05.72	PERFORMANCE BASED RETRACING SPRAY THERMO 4IN	1,204.000	L.M.
716-05.73	PERFORMANCE BASED RETRACING SPRAY THERMO 6IN	649.000	L.M.
716-05.79	PERFORMANCE BASED RETRACING SPRAY THERMO 12IN	25.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	5,000.000	L.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	250.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	100.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	100.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	100.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	50.000	L.F.
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	50.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	5.000	EACH

Contract ID CNY044 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
716-08.12	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	3.000	EACH
716-08.13	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (SCHOOL)	2.000	EACH
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.000	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	20.000	EACH
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	5.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	400.000	L.F.
716-12.04	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN DOTTED LINE)	200.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	200.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	450.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	100.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	100.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	100.000	L.F.
716-13.06	SPRAY THERMO PVMT MRKNG (40 mil) (4IN LINE)	10.000	L.M.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	30.000	L.M.
716-13.08	SPRAY THERMO PVMT MRKNG (40 mil) (8IN BARRIER LINE)	12,000.000	L.F.
716-13.09	SPRAY THERMO PVMT MRKNG (40 mil) (4IN DOTTED LINE)	100.000	L.F.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	250.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	16.000	L.M.
717-01	MOBILIZATION	(1)	LS
717-01.03	MOBILIZATION (PER CALL-OUT)	25.000	EACH
717-01.04	MOBILIZATION (DESCRIPTION) (PER LEVEL 1 CALL-OUT)	3.000	EACH

Contract ID CNY044 - BEDFORD , CHEATHAM, ETC.

() Item will be bid as lump sum.

Contract ID CNY047 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNY047

Letting Date: February 09, 2024 10:00 AM

Projects: R3BVAR-M3-049

NA

Counties: BEDFORD, CHEATHAM, DICKSON, GILES,
HICKMAN, HOUSTON, HUMPHREYS,
LAWRENCE, LEWIS, LINCOLN, MACON,
MARSHALL, MAURY, MONTGOMERY,
MOORE, PERRY, ROBERTSON,
RUTHERFORD, SMITH, STEWART, SUMNER,
TROUSDALE, WAYNE, WILLIAMSON,
WILSON

District:

DBE Goal Percent:

Description: The retracing of painted pavement marking lines on various Interstate and State Routes.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
716-05.69	PERFORMANCE BASED RETRACING PAINTED 4IN LINE	3,720.000	L.M.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	8.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY046 - BEDFORD , DAVIDSON, ETC.

Contract ID: CNY046

Letting Date: February 09, 2024 10:00 AM

Projects: R3BVAR-M3-050

NA

Counties: BEDFORD, DAVIDSON, DICKSON, GILES,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MOORE, PERRY, ROBERTSON,
RUTHERFORD, SUMNER, TROUSDALE,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The relensing of snowplowable pavement markers on various Interstate and State Routes.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
705-07.11	TRUCK MOUNTED ENERGY ATTENUATOR	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	128.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,876.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	49,540.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY050 - BENTON , CARROLL, ETC.

Contract ID: CNY050

Letting Date: February 09, 2024 10:00 AM

Projects: R4BVAR-M3-046
R4BVAR-M3-047

NA
NA

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
DECATUR, DYER, FAYETTE, GIBSON,
HARDEMAN, HARDIN, HAYWOOD,
HENDERSON, HENRY, LAKE, LAUDERDALE,
MADISON, MCNAIRY, OBION, SHELBY,
TIPTON, WEAKLEY

District:

DBE Goal Percent:

Description: The retracing of pavement markings with spray thermoplastic and random on-call pavement marking on various Interstate and State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	5.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	5.000	L.M.
712-01.50	MAINTENANCE OF TRAFFIC	65.000	EACH
713-02.34	DELINEATORS (ALL)	175.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	150.000	EACH
716-01.12	RAISED PVMT MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	150.000	EACH
716-01.13	RAISED PVMT MARKERS (BI-DIRECTIONAL) (2 COLOR LENS)	250.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	250.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS	150.000	EACH

Contract ID CNY050 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
716-01.23	(MONO-DIR)(1 COLOR) SNOWPLOWABLE RAISED PAVEMENT MARKERS	100.000	EACH
716-01.30	(BI-DIR)(2 COLOR) REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	30.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	300.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	1,000.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	300.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,000.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	75.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	30.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	100.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	500.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	15.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	10.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	5.000	EACH
716-03.04	PLASTIC WORD PAVEMENT MARKING (SCHOOL)	5.000	EACH
716-03.05	PLASTIC WORD PAVEMENT MARKING (BIKE LANE)	5.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	5.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	5.000	EACH
716-03.08	PLASTIC WORD PAVEMENT MARKING (PED-XING)	3.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	5.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	5.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	500.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	5.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY)	5.000	EACH

Contract ID CNY050 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
	ARROW)		
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	3.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	5.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	5.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	5.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	50.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	5.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	5.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	60.000	L.M.
716-05.73	PERFORMANCE BASED RETRACING SPRAY THERMO 6IN	2,384.000	L.M.
716-05.74	PERFORMANCE BASED RETRACING SPRAY THERMO 8IN	77,504.000	L.F.
716-05.75	PERFORMANCE BASED RETRACING SPRAY THERMO 6IN DOTTED	14,705.000	L.F.
716-05.79	PERFORMANCE BASED RETRACING SPRAY THERMO 12IN	2.000	L.M.
716-05.81	PERFORMANCE BASED RETRACING SPRAY THERMO 12IN DOTTED	2,852.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	2,500.000	L.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	175.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	50.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	50.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	100.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	5.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	5.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	50.000	L.F.

Contract ID CNY050 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	50.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	5.000	EACH
716-08.12	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	3.000	EACH
716-08.13	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (SCHOOL)	2.000	EACH
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	4.000	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	10.000	EACH
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	5.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	250.000	L.F.
716-12.04	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN DOTTED LINE)	250.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	250.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	200.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	100.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	100.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	400.000	L.F.
716-13.06	SPRAY THERMO PVMT MRKNG (40 mil) (4IN LINE)	100.000	L.M.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	90.000	L.M.
716-13.08	SPRAY THERMO PVMT MRKNG (40 mil) (8IN BARRIER LINE)	10,000.000	L.F.
716-13.09	SPRAY THERMO PVMT MRKNG (40 mil) (4IN DOTTED LINE)	100.000	L.F.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	900.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	13.000	L.M.
717-01	MOBILIZATION	(1)	LS

Contract ID CNY050 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
717-01.03	MOBILIZATION (PER CALL-OUT)	16.000	EACH
717-01.04	MOBILIZATION (DESCRIPTION) (PER LEVEL 1 CALL-OUT)	5.000	EACH

() Item will be bid as lump sum.

Contract ID CNY055 - BLEDSOE , BRADLEY, ETC.

Contract ID: CNY055

Letting Date: February 09, 2024 10:00 AM

Projects: R2BVAR-M3-028

NA

R2BVAR-M3-029

NA

Counties: BLEDSOE, BRADLEY, CANNON, CLAY,
COFFEE, CUMBERLAND, DEKALB,
FENTRESS, FRANKLIN, GRUNDY,
HAMILTON, JACKSON, MARION, MCMINN,
MEIGS, OVERTON, PICKETT, POLK,
PUTNAM, RHEA, SEQUATCHIE, VAN BUREN,
WARREN, WHITE

District:

DBE Goal Percent:

Description: The retracing of pavement markings with spray thermoplastic and random on-call pavement marking on various Interstate and State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	5.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	5.000	L.M.
712-01.50	MAINTENANCE OF TRAFFIC	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	32.000	S.F.
713-02.34	DELINEATORS (ALL)	250.000	EACH
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	150.000	EACH
716-01.12	RAISED PVMT MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	200.000	EACH
716-01.13	RAISED PVMT MARKERS (BI-DIRECTIONAL) (2 COLOR LENS)	150.000	EACH

Contract ID CNY055 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	275.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	150.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	75.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	250.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	1,500.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	250.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	3,000.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	100.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	300.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	250.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,200.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	10.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	10.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	5.000	EACH
716-03.04	PLASTIC WORD PAVEMENT MARKING (SCHOOL)	10.000	EACH
716-03.05	PLASTIC WORD PAVEMENT MARKING (BIKE LANE)	10.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	10.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	7.000	EACH
716-03.08	PLASTIC WORD PAVEMENT MARKING (PED-XING)	3.000	EACH
716-03.13	PLASTIC PVMT MARKING (NO TRUCKS THIS LANE) (NO TRUCKS THIS LANE)	3.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	10.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	5.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	200.000	L.F.

Contract ID CNY055 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	12.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	15.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	7.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	5.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	5.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	10.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	100.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	10.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	15.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	10.000	L.M.
716-05.73	PERFORMANCE BASED RETRACING SPRAY THERMO 6IN	602.000	L.M.
716-05.74	PERFORMANCE BASED RETRACING SPRAY THERMO 8IN	43,728.000	L.F.
716-05.80	PERFORMANCE BASED RETRACING SPRAY THERMO 8IN DOTTED	9,457.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	5,000.000	L.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	1,600.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	1,100.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	250.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	1,500.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	50.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	5.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	2.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	100.000	L.F.
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE	100.000	L.F.

Contract ID CNY055 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
	SHOULDER)		
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (ONLY)	5.000	EACH
716-08.12	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (STOP AHEAD)	3.000	EACH
716-08.13	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (SCHOOL)	2.000	EACH
716-08.14	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (WRONG WAY ARROW)	3.000	EACH
716-08.15	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (EXIT ONLY ARROW)	3.000	EACH
716-08.16	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (OPTION LANE ARROW)	3.000	EACH
716-08.17	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (NO TRUCKS THIS LANE)	3.000	EACH
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.000	L.M.
716-10.15	PREFORMED PLASTIC PAVEMENT MARKING (NO TRUCKS THIS LANE)	3.000	EACH
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	4.000	EACH
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	5.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	500.000	L.F.
716-12.04	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN DOTTED LINE)	350.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	500.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	200.000	L.F.
716-12.07	ENHANCED FLAT LINE THERMO (8IN BROKEN LN)	100.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	100.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	300.000	L.F.
716-13.06	SPRAY THERMO PVMT MRKNG (40 mil) (4IN LINE)	5.000	L.M.
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	50.000	L.M.

Contract ID CNY055 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
716-13.08	SPRAY THERMO PVMT MRKNG (40 mil) (8IN BARRIER LINE)	5,000.000	L.F.
716-13.09	SPRAY THERMO PVMT MRKNG (40 mil) (4IN DOTTED LINE)	100.000	L.F.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	1,800.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	23.000	L.M.
717-01	MOBILIZATION	(1)	LS
717-01.03	MOBILIZATION (PER CALL-OUT)	3.000	EACH
717-01.04	MOBILIZATION (DESCRIPTION) (PER LEVEL 1 CALL-OUT)	3.000	EACH

() Item will be bid as lump sum.

Contract ID CNY058 - BLEDSOE , COFFEE, ETC.

Contract ID: CNY058

Letting Date: February 09, 2024 10:00 AM

Projects: R2BVAR-M3-030

NA

Counties: BLEDSOE, COFFEE, DEKALB, FENTRESS,
GRUNDY, HAMILTON, JACKSON, MARION,
PICKETT, POLK, PUTNAM, WARREN

District:

DBE Goal Percent:

Description: The retracing of painted pavement marking lines on various Interstate and State Routes.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	32.000	S.F.
716-05.70	PERFORMANCE BASED RETRACING PAINTED 6IN LINE	375.000	L.M.
716-05.71	PERFORMANCE BASED RETRACING PAINTED 8IN LINE	1,383.000	L.F.
716-05.82	PERFORMANCE BASED RETRACING PAINTED 8IN DOTTED	505.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	3.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY014 - BLOUNT

Contract ID: CNY014

Letting Date: February 09, 2024 10:00 AM

Projects: 05S073-F3-003
05S073-F8-003
05S073-M3-004

NH/HSIP-73(82)
NH/HSIP-73(82)
NH/HSIP-73(82)

Counties: BLOUNT

District:

DBE Goal Percent: 5.00

Description: The resurfacing on U.S. 321 (S.R. 73) from near Tuckaleechee Pike (L.M. 17.05) to near the bridge over Hesse Creek (L.M. 22.90), including thin epoxy overlay on bridges.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.000	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	2,517.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	201.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	12,570.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	9.100	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	11.400	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	0.100	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,277.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	262.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	131.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,305.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	56.000	EACH

Contract ID CNY014 - BLOUNT

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	77.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	19.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	938.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,034.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	370.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	16.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	795.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	11.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	27.000	L.M.
717-01	MOBILIZATION	(1)	LS
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,272.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY059 - BRADLEY , HAMILTON, ETC.

Contract ID: CNY059

Letting Date: February 09, 2024 10:00 AM

Projects: R2BVAR-M3-031

NA

Counties: BRADLEY, HAMILTON, MCMINN, MEIGS,
POLK, RHEA

District:

DBE Goal Percent:

Description: The relensing of snowplowable pavement markers on various Interstate and State Routes.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
705-07.11	TRUCK MOUNTED ENERGY ATTENUATOR	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	128.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	700.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	107,401.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY015 - CAMPBELL

Contract ID: CNY015

Letting Date: February 09, 2024 10:00 AM

Projects: 07S009-M3-006

n/a

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The repair of the bridges on U.S. 25W (S.R. 9) over Cove Lake (L.M. 31.35 and L.M. 31.79).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
201-05.31	VEGETATION REMOVAL	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 07-SR009-31.35 L&R)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 07-SR009-31.79)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	500.000	L.F.
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	810.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.800	TON
411-02.10	ACS MIX(PG70-22) GRADING D	1,000.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	9,560.000	S.Y.
604-02.03	EPOXY COATED REINFORCING STEEL	46,000.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	8.000	C.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	42.000	C.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	1,600.000	S.Y.
604-10.05	CONCRETE	107.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	95.000	S.Y.
604-10.42	CONCRETE REPAIRS	1.000	C.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	245.000	S.Y.

Contract ID CNY015 - CAMPBELL

Item No.	Description	Quantity	Units
604-10.54	CONCRETE REPAIRS	107.000	S.F.
604-10.58	EPOXY INJECTION (INJECTION)	82.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	815.000	L.F.
610-10.45	DECK DRAINS (DESCRIPTION) (MEDIAN DRAINS)	13.000	EACH
617-01	BRIDGE DECK SEALANT	3,385.000	S.Y.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	845.000	L.F.
702-01	CONCRETE CURB	45.000	C.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	5.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	325.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	9.000	EACH
706-01	GUARDRAIL REMOVED	825.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,520.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	600.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	46.000	EACH
712-06	SIGNS (CONSTRUCTION)	602.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	12.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	38,500.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	40.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	40.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	4.500	L.M.
717-01	MOBILIZATION	(1)	LS

Contract ID CNY015 - CAMPBELL

() Item will be bid as lump sum.

Contract ID CNY049 - CHESTER , CROCKETT, ETC.

Contract ID: CNY049

Letting Date: February 09, 2024 10:00 AM

Projects: R4BVAR-M3-048

NA

Counties: CHESTER, CROCKETT, DECATUR,
HARDEMAN, HARDIN, HAYWOOD,
HENDERSON, MADISON, MCNAIRY

District:

DBE Goal Percent:

Description: The retracing of painted pavement marking lines on various Interstate and State Routes.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
716-05.70	PERFORMANCE BASED RETRACING PAINTED 6IN LINE	2,931.000	L.M.
716-05.71	PERFORMANCE BASED RETRACING PAINTED 8IN LINE	16,000.000	L.F.
716-50.01	ROADWAY CLEANING FOR PAVEMENT MARKING	25.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY048 - CHESTER , DECATUR, ETC.

Contract ID: CNY048

Letting Date: February 09, 2024 10:00 AM

Projects: R4BVAR-M3-049

NA

Counties: CHESTER, DECATUR, FAYETTE,
HENDERSON, MADISON, SHELBY

District:

DBE Goal Percent:

Description: The relensing of snowplowable pavement markers on various Interstate and State Routes.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
705-07.11	TRUCK MOUNTED ENERGY ATTENUATOR	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	128.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	337.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	34.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	683.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	48,042.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY069 - COCKE

Contract ID: CNY069

Letting Date: February 09, 2024 10:00 AM

Projects: 15S032-F3-003

PROT-32(103)

Counties: COCKE

District:

DBE Goal Percent: 3.00

Description: The slide mitigation on U.S. 25E (S.R. 32) near L.M. 28.27, including grading, drainage, retaining wall, and paving.

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-01.01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	4,122.000	C.Y.
203-06	WATER	48.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	533.000	C.Y.
204-06.02	FLOWABLE FILL (EXCAVATABLE)	260.000	C.Y.
204-14	CORE DRILLING FOR PILES(ROCK)	2,750.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	3,700.000	L.F.
209-05	SEDIMENT REMOVAL	80.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,080.000	L.F.
209-08.07	ROCK CHECK DAM	8.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	3.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	1.000	EACH
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,861.000	TON
303-01.03	GRANULAR BACKFILL (RETAINING WALLS)	4,242.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	124.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	70.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON

Contract ID CNY069 - COCKE

Item No.	Description	Quantity	Units
402-02	AGGREGATE FOR COVER MATERIAL (PC)	9.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	262.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	0.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	143.000	TON
604-03.07	CLASS A CONCRETE (DESCRIPTION) (PILE FOUNDATION)	970.000	C.Y.
604-07.01	RETAINING WALL (DESCRIPTION) (1)	10,220.000	S.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	55.000	L.F.
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	40.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	945.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	761.000	L.F.
709-02.01	RUBBLE STONE RIP-RAP (GROUTED)	34.000	C.Y.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,202.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	32.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	45.000	EACH
712-06	SIGNS (CONSTRUCTION)	601.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	2,820.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	12.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS

Contract ID CNY069 - COCKE

Item No.	Description	Quantity	Units
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-06.01	GEOMEMBRANE	583.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	350.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	3,742.000	L.F.
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	35.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	56.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.500	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	3,077.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY010 - CUMBERLAND

Contract ID: CNY010

Letting Date: February 09, 2024 10:00 AM

Projects: 18S101-F3-003
18S101-F8-003

STP/HSIP-101(27)
STP/HSIP-101(27)

Counties: CUMBERLAND

District:

DBE Goal Percent: 8.50

Description: The resurfacing on S.R. 101 from south of S.R. 282 (Dunbar Lane) (L.M. 12.36) to U.S. 70 (S.R. 1) (L.M. 15.92).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	2.100	L.M.
209-09.41	CURB INLET PROTECTION (TYPE 2)	14.000	EACH
403-02.01	TRACKLESS TACK COAT	69.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	20.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	10,555.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,415.000	TON
701-02.01	CONCRETE CURB RAMP (RETROFIT)	2,888.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	15.000	EACH
712-06	SIGNS (CONSTRUCTION)	792.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	60.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	16.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	653.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	572.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,156.000	EACH

Contract ID CNY010 - CUMBERLAND

Item No.	Description	Quantity	Units
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	401.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	74.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	434.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	56.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,486.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	9.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	45.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	19.200	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	410.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	19.200	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	470.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	280.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	250.000	L.F.
730-14.03	LOOP WIRE	500.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY022 - DAVIDSON

Contract ID: CNY022

Letting Date: February 09, 2024 10:00 AM

Projects: 19S006-F3-007
19S006-F8-007

NH/HSIP-6(158)
NH/HSIP-6(158)

Counties: DAVIDSON

District:

DBE Goal Percent: 8.50

Description: The resurfacing on U.S. 31 (S.R. 6) from the Williamson County line (L.M. 0.00) to Norwood Drive (L.M. 4.53).

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	5.600	S.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,064.000	TON
307-02.07	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M	150.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	67.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	10,078.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.100	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	6.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,149.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	5,360.000	LB.
701-01.02	CONCRETE SIDEWALK (6 ")	50.000	S.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	6.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	6.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	3.000	EACH
706-01	GUARDRAIL REMOVED	375.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNY022 - DAVIDSON

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,435.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	8.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	466.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	713.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	95.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,037.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	20.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	2,233.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.500	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	3.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	3.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	22.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	22.600	L.M.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	428.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	4,328.000	L.F.
730-14.03	LOOP WIRE	9,356.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY037 - DAVIDSON

Contract ID: CNY037

Letting Date: February 09, 2024 10:00 AM

Projects: 19S100-M3-002

n/a

Counties: DAVIDSON

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 100 over the Harpeth River (L.M. 7.36).

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.700	L.M.
209-05	SEDIMENT REMOVAL	5.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	320.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	697.000	TON
602-08.01	JACKING STRUCTURES (DESCRIPTION) (STEEL TRUSS)	(1)	LS
602-10.12	BEARING DEVICE (REPAIR)	(1)	LS
602-10.32	STRUCTURAL STEEL (REPAIRS)	6,375.000	LB.
603-02.15	REPAINT EXISTING BEARINGS	(1)	LS
604-10.05	CONCRETE	6.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	56.000	S.Y.
604-10.44	EXPANSION JOINT REPAIRS	1,122.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	56.000	S.Y.
604-10.54	CONCRETE REPAIRS	6.000	S.F.
604-10.63	CONCRETE REPAIRS (CRACKS)	12.000	L.F.
617-01	BRIDGE DECK SEALANT	3,690.000	S.Y.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	320.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	300.000	L.F.

Contract ID CNY037 - DAVIDSON

Item No.	Description	Quantity	Units
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	887.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	48.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	45.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	769.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	70.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	6,085.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	3,653.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.700	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNY040 - DYER

Contract ID: CNY040

Letting Date: February 09, 2024 10:00 AM

Projects: 23S104-F3-004
 23S104-F8-004
 23S181-F3-003
 23S181-F8-003

STP/HSIP-104(50)
 STP/HSIP-104(50)
 STP/HSIP-181(19)
 STP/HSIP-181(19)

Counties: DYER

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 104 from Chic Road (L.M. 0.00) to S.R. 181 (L.M. 2.53), and on S.R. 181 from the Lauderdale County line (L.M. 0.00) to S.R. 104 (L.M. 11.48).

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	777.000	S.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	28.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	4,194.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	357.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	28,976.000	TON
403-02.01	TRACKLESS TACK COAT	113.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	18.200	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	4.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	8,000.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,662.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	928.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	54.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP	1.000	EACH

Contract ID CNY040 - DYER

Item No.	Description	Quantity	Units
716-05.01	AHEAD) PAINTED PAVEMENT MARKING (4" LINE)	33.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	33.800	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY041 - DYER

Contract ID: CNY041

Letting Date: February 09, 2024 10:00 AM

Projects: R4SVAR-F8-032

STP-REG4(223)

Counties: DYER

District:

DBE Goal Percent:

Description: The crack sealing at various locations on various State Routes.

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
411-04	CRACK SEALANT	11,800.000	LB.
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY068 - FRANKLIN

Contract ID: CNY068

Letting Date: February 09, 2024 10:00 AM

Projects: 26LCIT-F3-005

BRZ-2600(51)

Counties: FRANKLIN

District:

DBE Goal Percent: 10.00

Description: The construction of a concrete I-beam bridge on Old Decherd Road over Wagner Creek (L.M. 0.25), including grading, drainage, and paving.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP ,20+50.28)	150.000	L.F.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (SEE PLANS)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,036.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	153.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	236.000	C.Y.
203-06	WATER	9.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	304.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	766.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO, 1)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 2)	(1)	LS
209-05	SEDIMENT REMOVAL	95.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	5,852.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	10.000	EACH
209-09.01	SANDBAGS	20.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH

Contract ID CNY068 - FRANKLIN

Item No.	Description	Quantity	Units
209-65.04	TEMPORARY IN STREAM DIVERSION	300.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	224.000	TON
303-01.02	GRANULAR BACKFILL (BRIDGES)	76.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	619.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	49.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	2.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	938.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	120.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	88.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	81,572.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	812.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	209,966.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	214.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	230.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,246.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
606-03.03	STEEL PILES (12 INCH)	3,451.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	70.000	EACH
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	146.000	L.F.
610-10.46	DECK DRAINS (DESCRIPTION) (SEE PLANS)	27.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	93.000	LB.
611-07.33	30IN ENDWALL (SIDE DRAIN)	1.000	EACH
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	1,011.000	L.F.
620-05	CONCRETE PARAPET WITH STRUCTURAL TUBING	458.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	182.000	L.F.
701-02.03	CONCRETE CURB RAMP	220.000	S.F.

Contract ID CNY068 - FRANKLIN

Item No.	Description	Quantity	Units
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	50.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
706-01	GUARDRAIL REMOVED	186.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	2,500.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	368.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	23.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	834.000	TON
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	238.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	28.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	44.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	46.000	EACH
712-06	SIGNS (CONSTRUCTION)	474.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	108.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-09.03	WET REFLECTIVE PAVEMENT MARKING(6" LINE)	0.200	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.700	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	880.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	589.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	220.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,700.000	L.F.
801-01.37	NATVE SEED MX ENCAPSULATION & CLEAR ZONE	24.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	32.000	UNIT
801-03	WATER (SEEDING & SODDING)	22.000	M.G.
803-01	SODDING (NEW SOD)	1,638.000	S.Y.

Contract ID CNY068 - FRANKLIN

Item No.	Description	Quantity	Units
805-12.01	EROSION CONTROL BLANKET (TYPE I)	4,000.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY057 - HAMILTON

Contract ID: CNY057

Letting Date: February 09, 2024 10:00 AM

Projects: 33S058-F3-003
33S058-F8-003

NH/HSIP-58(62)
NH/HSIP-58(62)

Counties: HAMILTON

District:

DBE Goal Percent: 8.00

Description: The resurfacing on S.R. 58 from S.R. 153 (L.M. 4.57) to near Eller Road (L.M. 6.45).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	113.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	41.000	TON
403-02.01	TRACKLESS TACK COAT	40.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	11.100	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	6,054.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	6,035.000	TON
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	2.000	EACH
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	57.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	32.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	16.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,262.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	232.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	582.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	814.000	EACH

Contract ID CNY057 - HAMILTON

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	186.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,038.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	30.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	425.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	505.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	45.000	S.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	16.800	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	1,038.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	11.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	11,070.000	L.F.
730-14.03	LOOP WIRE	28,956.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY030 - HARDIN

Contract ID: CNY030

Letting Date: February 09, 2024 10:00 AM

Projects: 36PARK-M8-002

N/A

Counties: HARDIN

District:

DBE Goal Percent:

Description: The resurfacing on various routes in Pickwick Landing State Park.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	14.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	160.000	S.Y.
203-06	WATER	2.400	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	4.200	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	311.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	74.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	2,724.000	TON
403-02.01	TRACKLESS TACK COAT	11.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	605.000	S.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	120.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	228.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	944.000	S.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	70.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	105.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	24.000	L.F.
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	2.000	EACH
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	2,134.000	L.F.

Contract ID CNY030 - HARDIN

Item No.	Description	Quantity	Units
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	4.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	9.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY028 - HAYWOOD

Contract ID: CNY028

Letting Date: February 09, 2024 10:00 AM

Projects: 38999-3609-04

NA

Counties: HAYWOOD

District:

DBE Goal Percent:

Description: The construction of a 40' x 80' maintenance building at 3548 Windrow Road in Brownsville.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
607-65.20	SITE PREPARATION	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (FOUNDATION AND STRUCTURE)	1.000	EACH
680-02.02	BUILDING (DESCRIPTION) (INTERIOR CONSTRUCTION)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY042 - HENDERSON , MADISON, ETC.

Contract ID: CNY042

Letting Date: February 09, 2024 10:00 AM

Projects: R4SVAR-F8-033

STP-REG4(224)

Counties: HENDERSON, MADISON, MCNAIRY

District:

DBE Goal Percent:

Description: The crack sealing at various locations on various State Routes.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
411-04	CRACK SEALANT	165,086.000	LB.
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY025 - HENRY & WEAKLEY

Contract ID: CNY025

Letting Date: February 09, 2024 10:00 AM

Projects: 40S022-F3-002	NH/HSIP-22(100)
40S022-F8-002	NH/HSIP-22(100)
92S022-F3-002	NH/HSIP-22(101)
92S022-F8-002	NH/HSIP-22(101)
92S022-M3-003	NH/HSIP-22(101)

Counties: HENRY, WEAKLEY

District: **DBE Goal Percent:** 6.00

Description: The resurfacing with hot in-place recycling on S.R. 22 from the Carroll County line (L.M. 0.00) in Henry County to S.R. 217 (L.M. 10.30) in Weakley County.

Contract Time: DT - 11/15/2024

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,400.000	S.Y.
203-06	WATER	43.400	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	34.200	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C or D)	5,395.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	483.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	158.000	TON
311-03.04	HOT IN PLACE RECYCLING OF ASPHALT PAVEMENT (2.00IN)	363,615.000	S.Y.
311-03.10	ASPHALT REJUVENATING AGENT	181,808.000	GAL.
403-02.01	TRACKLESS TACK COAT	185.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	58.600	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	1,690.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	21,279.000	TON
411-03.34	ACS MIX(PG64-22) THIN LIFT E SHOULDER	5,557.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN)	15.700	L.M.

Contract ID CNY025 - HENRY & WEAKLEY

Item No.	Description	Quantity	Units
411-12.02	WIDTH) SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	13.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,836.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	32.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	32.000	EACH
706-01	GUARDRAIL REMOVED	1,600.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	4,550.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	8.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	620.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	46.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	445.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	70.000	EACH
712-06	SIGNS (CONSTRUCTION)	4,444.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	8.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	15,600.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	789.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	1,599.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	113.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	2,329.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	423.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	515.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	97.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	850.000	L.F.

Contract ID CNY025 - HENRY & WEAKLEY

Item No.	Description	Quantity	Units
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	912.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	4.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	390.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	60.000	S.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	384.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	119.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	59.700	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	2,250.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	3,400.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	765.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	16,918.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY027 - HICKMAN & PERRY

Contract ID: CNY027

Letting Date: February 09, 2024 10:00 AM

Projects: 41S100-F8-004
68S013-F8-005
68S013-M3-006

STP-100(101)
STP-13(94)
STP-13(94)

Counties: HICKMAN, PERRY

District:

DBE Goal Percent: 5.00

Description: The resurfacing on S.R. 100 from the Perry County line to west of Depriest Branch Road, and on S.R. 13 from the Wayne County line to Old Highway 13 South, including bridge expansion joint repair and thin epoxy overlay.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	29.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,836.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	500.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	450.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	194.500	TON
411-01.10	ACS MIX(PG64-22) GRADING D	17,017.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	21.000	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	1.600	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	334.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	2,045.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	433.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,807.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	965.000	EACH

Contract ID CNY027 - HICKMAN & PERRY

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	965.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	20.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	250.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	81.400	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	3,900.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	53.200	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	77.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	4,365.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY021 - HOUSTON

Contract ID: CNY021

Letting Date: February 09, 2024 10:00 AM

Projects: 42S147-F3-002
42S147-F8-002

STP/HSIP-147(13)
STP/HSIP-147(13)

Counties: HOUSTON

District:

DBE Goal Percent: 5.00

Description: The resurfacing on S.R. 147 from the bridge over Cane Creek (L.M. 6.16) to S.R. 49 (L.M. 12.42).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.600	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,657.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	300.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	42.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,989.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	13.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	3,953.000	TON
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	200.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,342.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	418.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	614.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	41.000	S.Y.

Contract ID CNY021 - HOUSTON

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	240.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	269.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	50.200	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	500.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	25.100	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	273.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY065 - HUMPHREYS

Contract ID: CNY065

Letting Date: February 09, 2024 10:00 AM

Projects: 43S013-M3-006

n/a

Counties: HUMPHREYS

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 13 over Hurricane Creek (L.M. 11.42).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	1,400.000	TON
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,355.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	692.000	L.F.
709-05.08	MACHINED RIP-RAP (CLASS B)	300.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	543.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	90.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	21.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	90.000	EACH
712-06	SIGNS (CONSTRUCTION)	178.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	5,674.000	L.F.
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	36.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	36.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	36.000	L.M.
717-01	MOBILIZATION	(1)	LS
801-02	SEEDING (WITHOUT MULCH)	10.000	UNIT
805-12.05	TURF REINFORCEMENT MAT (CHANNEL LINER)	1,140.000	S.Y.

Contract ID CNY065 - HUMPHREYS

Item No.	Description	Quantity	Units
-----------------	--------------------	-----------------	--------------

() Item will be bid as lump sum.

Contract ID CNY006 - JEFFERSON

Contract ID: CNY006

Letting Date: February 09, 2024 10:00 AM

Projects: 45010-3212-94

HSIP-113(24)

Counties: JEFFERSON

District:

DBE Goal Percent: 10.00

Description: The improvement of the intersection on S.R. 113 at S.R. 341 (L.M. 5.17 to L.M. 5.35), including grading, drainage, signals, and paving.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
202-01.56	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (METAL FLAGPOLE ON TRACT 8)	(1)	LS
202-01.57	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (10 L.F. OF CHAINLINK FENCING ON TRACT 11)	(1)	LS
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (30"X19" ARCH ,STA. 63+22.78)	112.000	L.F.
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	39.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (PEDESTRIAN BRIDGE)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,377.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	183.000	C.Y.
203-06	WATER	7.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	485.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	6.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.800	L.M.
209-02.07	18" TEMPORARY SLOPE DRAIN	80.000	L.F.
209-05	SEDIMENT REMOVAL	53.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	61.000	L.F.

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
209-08.07	ROCK CHECK DAM	31.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	11.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	17.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	4.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	4,354.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	4.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	114.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	75.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	15.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	4.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	83.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	657.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	6,195.000	TON
607-02.02	15" CONCRETE PIPE CULVERT(CLASS III)	6.000	L.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	1,241.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	305.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	160.000	L.F.
607-57.04	REINFORCED CONCRETE PIPE ARCH (44" X 27")	100.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	7.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	398.000	LB.
611-07.03	STRUCTURAL STEEL (PIPE ENDWALLS)	1,166.000	LB.
611-07.32	24IN ENDWALL (SIDE DRAIN)	12.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	4.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	4.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	7.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	3.000	EACH

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
611-14.01	CATCH BASINS, TYPE 14, 0' - 4' DEPTH	1.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	128.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	6,520.000	S.F.
701-02	CONCRETE DRIVEWAY	2,236.000	S.F.
701-02.03	CONCRETE CURB RAMP	385.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	110.000	C.Y.
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (10 L.F. ON TRACT 11)	10.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	17.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	350.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	64.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	8.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	147.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,240.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	102.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	72.000	EACH
712-06	SIGNS (CONSTRUCTION)	660.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	124.000	L.F.
712-12.10	TEMPORARY CURB W/FLEXIBLE DELINEATOR	400.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	3.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	600.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	789.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	991.000	LB.
713-11.21	P POST SLIP BASE	25.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	248.000	S.F.
713-13.04	FLAT SHEET ALUMINUM SIGNS (0.125" THICK)	17.000	S.F.

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	96.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	126.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	27.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	153.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	18.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	124.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	456.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	142.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.400	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	8.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	650.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	673.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	36.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	116.000	L.F.

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	50.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	75.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	111.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (RADAR - STOP BAR)	4.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.30	PEDESTAL POLE (DESCRIPTION) (TYPE A)	3.000	EACH
730-23.72	CANTILEVER SIGNAL SUPPORT (1 ARM @ 35')	1.000	EACH
730-23.80	CANTILEVER SIGNAL SUPPORT (1 ARM @ 40')	1.000	EACH
730-24.90	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 50')	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	4.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	656.000	S.Y.
801-01	SEEDING (WITH MULCH)	0.100	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	23.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	47.000	UNIT
801-03	WATER (SEEDING & SODDING)	2.000	M.G.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	5,191.000	S.Y.
790-02.04	POLE 35FT CLASS 5 WOOD	1.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	3.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	6.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	2.000	EACH
790-21.10	1PH VERTICAL DDE 15KV	1.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	3.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	1.000	EACH
790-25.15	3PH VERTICAL 15KV	2.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	2.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	3.000	EACH
790-30.01	SECONDARY ASSEMBLIES SMALL ANGLE	2.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	7.000	EACH

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
790-31.12	SERVICE CONDUCTOR 1/0 AL TRIPLEX	285.000	L.F.
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	14.000	EACH
790-32.08	OH GUY - THROUGH BOLT TYPE HEAVY DUTY	3.000	EACH
790-32.23	GUY GUARD	8.000	EACH
790-33.04	SCREW TYPE ANCHOR 10,000LB-12,000LB	8.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	4.000	EACH
790-36.13	TRANSFER STREET LIGHT	3.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	3.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	228.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	3,717.000	L.F.
790-40.39	OH COND 4/0 7 AAC OXLIP	1,060.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	1,611.000	L.F.
790-43.46	SECONDARY PULLBOX LARGE	1.000	EACH
790-58.06	GOAB SWITCH 15KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	10.000	EACH
790-68.07	POLE GROUND FOR AIR BREAK SWITCH	1.000	EACH
790-98.01	REMOVE WIRE	6,920.000	L.F.
790-98.02	REMOVE POLES	11.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	50.000	EACH
791-02.04	4IN MDPE GAS MAIN	2,135.000	L.F.
791-06.31	CONNECT TO 2IN EX. STL MAIN W/ STOPPLE	2.000	EACH
791-06.52	4IN PE HOT TAP CONNECTION	8.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	2.000	EACH
791-07.21	EXCESS FLOW VALVE (EFV)	8.000	EACH
791-08.07	3/4IN PE SERVICE PIPE	10.000	L.F.
791-09.10	FLOWABLE FILL (EXCAVATABLE)	2.000	C.Y.
791-10.01	RETIRE IN PLACE 3/4IN SERV CUT & PLUG	4.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
795-03.06	8IN PVC WATER LINE	500.000	L.F.

Contract ID CNY006 - JEFFERSON

Item No.	Description	Quantity	Units
795-06.05	CONNECT TO 8IN WATER LINE	2.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	2.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	3.000	EACH
795-09.14	3/4IN HDPE SERVICE PIPE	150.000	L.F.
797-04.03	6IN FPVC FORCE MAIN	100.000	L.F.
797-05.01	8IN DIP GRAVITY SEWER 0FT-6FT DEPTH	455.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	559.000	L.F.
797-05.52	8IN PVC GRAVITY SEWER 6FT-12FT DEPTH	126.000	L.F.
797-06.89	OPEN CUT 12IN STEEL CASING PIPE	90.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	1.000	EACH
797-10.02	CONNECT 8IN SEWER TO EXIST. MANHOLE	8.000	EACH
797-10.17	CONNECT TO 6IN FORCE MAIN	1.000	EACH
797-11.38	BY-PASS PUMPING	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY023 - LEWIS

Contract ID: CNY023

Letting Date: February 09, 2024 10:00 AM

Projects: 51S020-F8-002
51S099-F8-002

STP-NH-20(89)
NH-99(73)

Counties: LEWIS

District:

DBE Goal Percent: 6.00

Description: The resurfacing on U.S. 412 (S.R. 20) from near West Linden Drive (L.M. 5.66) to South Park Street (L.M. 6.13) and on U.S. 412 (S.R. 99) from South Park Street (L.M. 14.35) to Kilpatrick Drive (L.M. 18.17).

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	702.709	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	70.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	1,178.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	9,500.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	11,230.960	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	670.000	LB.
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	19.000	EACH
702-03	CONCRETE COMBINED CURB & GUTTER	10.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	109.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,319.500	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	575.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	524.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,099.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION)	228.000	S.Y.

Contract ID CNY023 - LEWIS

Item No.	Description	Quantity	Units
	STRIPING)		
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	956.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	32.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	374.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	2,388.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.700	L.M.
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	23.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	28.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	224.000	L.F.
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	2,494.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	21.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	21.300	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	121.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY026 - LINCOLN

Contract ID: CNY026

Letting Date: February 09, 2024 10:00 AM

Projects: 52S015-F8-002
52S015-M3-003

NH-15(227)
NH-15(227)

Counties: LINCOLN

District:

DBE Goal Percent: 5.00

Description: The resurfacing on U.S. 64 (S.R. 15) from U.S. 231 (S.R. 10) (L.M. 17.28) to Smithland Road (L.M. 23.60), including bridge expansion joint repair and thin epoxy overlay.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
208-01.03	GRADE AND RESHAPE SHOULDERS	6.500	L.M.
208-01.05	BROOMING & DEGRASSING SHOULDERS	9.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,283.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	200.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	19.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	67.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	133.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	6,041.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	40.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	22,752.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	9.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	26,301.000	TON
701-01.02	CONCRETE SIDEWALK (6 ")	175.000	S.F.
702-01	CONCRETE CURB	3.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,827.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH

Contract ID CNY026 - LINCOLN

Item No.	Description	Quantity	Units
713-02.17	REMOVE & REPLACE DELINEATORS (SINGLE WHITE)	21.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	642.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	947.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,589.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	361.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	310.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	46.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	3.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	0.800	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	3,564.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.300	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	4,098.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	993.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	164.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	7,246.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY031 - MACON

Contract ID: CNY031

Letting Date: February 09, 2024 10:00 AM

Projects: 56946-3431-94

BRZE-5600(38)

Counties: MACON

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete box bridge on Hoot Owl Lane over Middle Fork Goose Creek (L.M. 0.06), including grading, drainage, and paving.

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	476.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	350.000	TON
203-04	PLACING AND SPREADING TOPSOIL	72.370	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	2.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	9.000	C.Y.
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	84.000	L.F.
209-05	SEDIMENT REMOVAL	10.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	440.000	L.F.
209-08.07	ROCK CHECK DAM	2.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	3.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	152.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	378.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	156.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	25.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	118.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.600	TON

Contract ID CNY031 - MACON

Item No.	Description	Quantity	Units
402-02	AGGREGATE FOR COVER MATERIAL (PC)	5.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.400	TON
411-01.10	ACS MIX(PG64-22) GRADING D	71.800	TON
621-03.07	48" TEMPORARY DRAINAGE PIPE	32.000	L.F.
621-03.09	60" TEMPORARY DRAINAGE PIPE	96.000	L.F.
705-01.04	METAL BEAM GUARD FENCE	75.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	75.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	240.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	31.500	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	117.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
713-16.06	DEAD END SIGN AND SUPPORT	1.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R2-1, SPEED LIMIT 20 MPH)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R1-1 STOP)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.400	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.01	GEO GRID REINFORCEMENT	94.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	442.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	200.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	534.000	L.F.
801-01	SEEDING (WITH MULCH)	1.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	7.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	1.000	UNIT
801-03	WATER (SEEDING & SODDING)	9.000	M.G.
802-02.40	CUTTINGS: SALIX NIGRA (24-48IN LENGTH)	252.000	EACH

Contract ID CNY031 - MACON

Item No.	Description	Quantity	Units
802-02.42	CUTTINGS: CORNUS AMOMUM (24-48IN)	252.000	EACH
802-02.43	CUTTINGS: SAMBUCUS CANADENSIS (24-48IN)	252.000	EACH
802-02.45	CUTTINGS: CEPHALANTHUS OCCIDENTALIS (24-48IN)	252.000	EACH
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	386.000	S.Y.
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (WOOD BRIDGE, STA. 24+25)	(1)	LS
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	65.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	15,168.000	LB.

() Item will be bid as lump sum.

Contract ID CNY029 - MACON & SUMNER

Contract ID: CNY029

Letting Date: February 09, 2024 10:00 AM

Projects: 56S052-F8-004
83S174-F8-003

NH-52(104)
STP-174(30)

Counties: MACON, SUMNER

District:

DBE Goal Percent: 5.50

Description: The resurfacing on S.R. 52 in Macon County from near Old Highway 52 Access Road to Old Highway 52, and on S.R. 174 in Sumner County from Albert Gallatin Avenue to South Tunnel Road.

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	20.600	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	4,593.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,676.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	2,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	112.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	16,247.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.500	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	9.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	17,235.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,132.000	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	5.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	806.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	90.000	EACH

Contract ID CNY029 - MACON & SUMNER

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	846.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	39.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	608.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	315.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	290.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.300	L.M.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	27.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	33.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	43.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	38.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	250.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY056 - MARION

Contract ID: CNY056

Letting Date: February 09, 2024 10:00 AM

Projects: 58S108-F3-003
58S108-F8-003

STP/HSIP-108(104)
STP/HSIP-108(104)

Counties: MARION

District:

DBE Goal Percent: 5.00

Description: The resurfacing (microsurfacing) on S.R. 108 from S.R. 28 (L.M. 0.00) to the Grundy County line (L.M. 11.01).

Contract Time: CD - 60 Days

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.100	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	21.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	28,466.000	S.Y.
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	198.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	1,648.000	TON
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	1,275.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	597.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	30.000	L.F.
713-02.27	CONCRETE BARRIER/PARAPET DELINEATOR (BI-DIRECTIONAL)	44.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (CHEVRON (W1-8)	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,377.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,377.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	188.000	S.Y.

Contract ID CNY056 - MARION

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	276.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	3.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	639.000	L.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	60.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	21.100	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	21.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	44.100	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	284.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY063 - MARION

Contract ID: CNY063

Letting Date: February 09, 2024 10:00 AM

Projects: 58S156-M3-002

NA

Counties: MARION

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 156 over the Tennessee River (L.M. 15.19).

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 58-SR156-15.19)	(1)	LS
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	5.000	C.Y.
209-03.21	FILTER SOCK (12 INCH)	130.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	400.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	45.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	24.000	TON
602-10.01	STRUCTURAL STEEL REPAIRS	(1)	LS
602-10.20	BOLTS	10.000	EACH
603-02.01	REPAINTING EXISTING STEEL STRUCTURES (LOC. & DES.) (BRIDGE NO. 58-SR156-15.19)	(1)	LS
603-05.20	CONTAINMENT & DISPOSAL OF WASTE(LOCATION & DESCRP) (BRIDGE NO. 58-SR156-15.19)	(1)	LS
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	8,132.000	S.Y.
604-10.05	CONCRETE	90.000	S.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	16.000	S.Y.
604-10.54	CONCRETE REPAIRS	90.000	S.F.
604-10.90	MISCELLANEOUS BRIDGE ITEMS	(1)	LS
604-10.91	MISCELLANEOUS BRIDGE ITEMS (Description)	(1)	LS
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	7,823.000	S.Y.

Contract ID CNY063 - MARION

Item No.	Description	Quantity	Units
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	152.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	200.000	L.F.
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	200.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	400.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	98.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	3,100.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	89.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	40.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,500.000	L.F.
714-16.01	NAVIGATIONAL LIGHTING	(1)	LS
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.500	L.M.
717-01	MOBILIZATION	(1)	LS
719-01.08	CLEAN DRAIN	1.000	EACH
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	85.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY011 - MEIGS

Contract ID: CNY011

Letting Date: February 09, 2024 10:00 AM

Projects: 61S068-F3-003
61S068-F8-002

STP/HSIP-68(65)
STP/HSIP-68(65)

Counties: MEIGS

District:

DBE Goal Percent: 5.00

Description: The resurfacing on S.R. 68 from the Rhea County line (L.M. 0.00) to the McMinn County line (L.M. 7.52).

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,871.000	TON
403-02.01	TRACKLESS TACK COAT	84.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	5,569.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,287.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	21.200	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	11.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,548.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,500.000	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	590.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	20.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	573.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	127.000	S.Y.

Contract ID CNY011 - MEIGS

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	300.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	150.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	36.000	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	300.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	1.700	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	2.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	24.300	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY018 - MONTGOMERY

Contract ID: CNY018

Letting Date: February 09, 2024 10:00 AM

Projects: 63S012-F3-008
63S012-F8-008

STP/HSIP-12(70)
STP/HSIP-12(70)

Counties: MONTGOMERY

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 12 from the Cheatham County line (L.M. 0.00) to west of Robin Hill Drive (L.M. 5.90).

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	566.000	TON
307-01.07	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M	600.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	65.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	10,490.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	7.600	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	4.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,391.000	TON
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	90.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,292.000	S.F.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	24.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	370.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	106.000	EACH

Contract ID CNY018 - MONTGOMERY

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	500.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	25.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	270.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	175.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	13.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	23.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	23.600	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY032 - MONTGOMERY

Contract ID: CNY032

Letting Date: February 09, 2024 10:00 AM

Projects: 63S012-S3-005

N/A

Counties: MONTGOMERY

District:

DBE Goal Percent:

Description: The construction of a concrete box culvert on U.S. 41A Bypass (S.R. 12) near S.R. 13/S.R. 48 (L.M. 12.85), including grading, drainage, and paving.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (DESCRIPTION)	1,935.000	L.F.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,040.000	S.Y.
203-04	PLACING AND SPREADING TOPSOIL	384.000	C.Y.
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	27,847.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	275.000	C.Y.
209-05	SEDIMENT REMOVAL	1.000	C.Y.
209-09.04	SEDIMENT FILTER BAG(15' X 10')	38.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	13.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,690.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	7,780.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	400.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	51.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	40.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	50.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	11.000	L.F.
611-01.06	MANHOLES, > 20' - 24' DEPTH	1.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	1.000	EACH

Contract ID CNY032 - MONTGOMERY

Item No.	Description	Quantity	Units
611-38.03	CATCH BASINS, TYPE 38, > 8' - 12' DEPTH	1.000	EACH
611-38.04	CATCH BASINS, TYPE 38, > 12' - 16' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	75.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	60.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	140.000	L.F.
621-05.01	TEMPORARY SHORING	47,875.000	S.F.
630-10.02	ELECTRICAL WORK-INSTALLED COMPLETE	(1)	LS
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	200.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,520.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	900.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	15.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	45.000	EACH
712-06	SIGNS (CONSTRUCTION)	184.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	9.000	C.Y.
714-08.20	FOUNDATION (ONLY) FOR LIGHT STANDARD	15.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	172.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,900.000	L.F.
801-03	WATER (SEEDING & SODDING)	6.700	M.G.
803-01	SODDING (NEW SOD)	7,450.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	3,600.000	S.Y.
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	1,458.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	317,340.000	LB.

Contract ID CNY032 - MONTGOMERY

() Item will be bid as lump sum.

Contract ID CNY066 - PUTNAM

Contract ID: CNY066

Letting Date: February 09, 2024 10:00 AM

Projects: 71S024-M3-004

NA

Counties: PUTNAM

District:

DBE Goal Percent:

Description: The repair of the bridge on U.S. 70N (S.R. 24) over Falling Water River (L.M. 24.42).

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 71-SR024-24.42)	(1)	LS
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	195.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	10.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (NO. 67)	508.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	45.200	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	183.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	157.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	18.000	TON
604-03.01	CLASS A CONCRETE (BRIDGES)	2.000	C.Y.
604-03.04	PAVEMENT @ BRIDGE ENDS	105.000	S.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	800.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,323.000	S.Y.
604-10.05	CONCRETE	3.000	S.F.
604-10.20	HYDRODEMOLITION	1,296.000	S.Y.
604-10.58	EPOXY INJECTION (INJECTION)	2.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	22.000	L.F.

Contract ID CNY066 - PUTNAM

Item No.	Description	Quantity	Units
604-10.91	MISCELLANEOUS BRIDGE ITEMS (Description)	(1)	LS
610-10.45	DECK DRAINS (DESCRIPTION) (CLEAN & MAINTAIN EXISTING)	6.000	EACH
619-01	BRIDGE DECK OVERLAY (PMC)	1,296.000	S.Y.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	100.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	68.000	TON
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	67.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	42.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	380.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	382.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	356.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	800.000	L.F.
713-02.34	DELINEATORS (ALL)	44.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	6.000	EACH
716-09.85	CONTRAST PAVEMENT MARKING 4"	0.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	898.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	185.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY019 - ROBERTSON

Contract ID: CNY019

Letting Date: February 09, 2024 10:00 AM

Projects: 74018-8210-14
74S025-F8-002

STP-25(67)
STP-25(66)

Counties: ROBERTSON

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 25 from S.R. 161 (L.M. 0.00) to S.R. 49 (L.M. 6.96).

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.920	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,382.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	524.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	45.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,875.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	2,835.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	11.220	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	6,647.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	105.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,169.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	475.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	475.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	79.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	158.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	2.000	EACH

Contract ID CNY019 - ROBERTSON

Item No.	Description	Quantity	Units
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	275.000	L.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	264.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	16.000	L.M.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	4.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	21.900	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY036 - ROBERTSON

Contract ID: CNY036

Letting Date: February 09, 2024 10:00 AM

Projects: 74S076-M3-003

N/A

Counties: ROBERTSON

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 76 over the CSX Railroad (L.M. 4.65).

Contract Time: DT - 12/31/2024

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 74SR0760003)	(1)	LS
411-01.10	ACS MIX(PG64-22) GRADING D	58.000	TON
411-01.11	ACS MIX(PG64-22) GRADING E RDWY	93.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	880.000	S.Y.
604-02.03	EPOXY COATED REINFORCING STEEL	2,504.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	8.000	C.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	12.000	C.Y.
604-10.01	CONCRETE REPAIRS	(1)	LS
604-10.05	CONCRETE	100.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.22	CONCRETE PARAPET REPAIR	41.000	L.F.
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	10.000	S.Y.
604-10.44	EXPANSION JOINT REPAIRS	105.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	10.000	S.Y.
604-10.54	CONCRETE REPAIRS	5.000	S.F.
604-10.58	EPOXY INJECTION (INJECTION)	1.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	43.000	L.F.
604-10.63	CONCRETE REPAIRS (CRACKS)	6.000	L.F.
604-10.83	COMPOSITE FIBER ENCASMENT	150.000	S.F.
604-20.10	MODIFY BRIDGE RAIL	156.000	L.F.

Contract ID CNY036 - ROBERTSON

Item No.	Description	Quantity	Units
615-02.22	PRESTRESSED CONCRETE BOX BEAM (18" X 36")	41.000	L.F.
617-01	BRIDGE DECK SEALANT	454.000	S.Y.
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	4.000	EACH
707-07.01	CHAIN-LINK FENCE (BRIDGES)	980.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	260.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	17.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	11.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	23.000	EACH
712-06	SIGNS (CONSTRUCTION)	285.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	45.000	L.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	36.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	3,700.000	L.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	4.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	4.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	190.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY024 - RUTHERFORD

Contract ID: CNY024

Letting Date: February 09, 2024 10:00 AM

Projects: 75I024-F8-012
75I024-M3-011

NH-I-24-1(142)
NH-I-24-1(142)

Counties: RUTHERFORD

District:

DBE Goal Percent: 8.00

Description: The resurfacing on I-24 from near the Stones River (L.M. 15.52) to east of the CSXT Railroad (L.M. 19.07), including bridge expansion joint repair.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	7.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	4,035.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	6,340.000	TON
307-03.11	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING CW	23,374.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	136.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	2,600.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	9,615.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	12.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	21,000.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	5.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	4,270.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	13.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	5.000	EACH
706-01	GUARDRAIL REMOVED	4,204.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	150.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH

Contract ID CNY024 - RUTHERFORD

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	3,894.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	6.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	6.000	DAY
713-02.11	REMOVAL OF EXISTING DELINEATORS	355.000	EACH
713-02.34	DELINEATORS (ALL)	355.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	14.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	2,080.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	2,080.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	70.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	3,975.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	14.000	EACH
716-04.09	PLASTIC PAVEMENT MARKING (H.O.V. DIAMOND)	30.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	50.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	7.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	24,600.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	47.000	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.390	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	22.400	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	25,265.000	L.F.

Contract ID CNY024 - RUTHERFORD

Item No.	Description	Quantity	Units
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	12,300.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	14,092.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	8,023.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	6.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	120.000	L.F.
730-14.02	SAW SLOT	1,670.000	L.F.
730-14.03	LOOP WIRE	5,800.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	455.000	L.F.
403-02.01	TRACKLESS TACK COAT	246.000	TON
403-02.02	HOT APPLIED TACK COAT	188.000	TON

() Item will be bid as lump sum.

Contract ID CNY061 - RUTHERFORD

Contract ID: CNY061

Letting Date: February 09, 2024 10:00 AM

Projects: 75I840-F3-006
75I840-F8-005
75I840-M3-004

NH-I-840(23)
NH-I-840(23)
NA

Counties: RUTHERFORD

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-840 from near I-24 (L.M. 7.53) to near the West Fork Stones River (L.M. 10.46), including bridge deck and expansion joint repair, and epoxy overlay.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (PVMT @ BRIDGE ENDS, MULTIPLE LOCATIONS)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	395.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,326.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	2,127.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	200.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	2,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	68.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	10,407.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	9.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,982.000	TON
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	167.000	C.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	690.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	559.000	EACH

Contract ID CNY061 - RUTHERFORD

Item No.	Description	Quantity	Units
502-04.03	TRANSVERSE TIE-BARS	182.000	EACH
604-03.04	PAVEMENT @ BRIDGE ENDS	788.000	S.Y.
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	84.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	808.000	TON
711-02.04	REINFORCED CONCRETE MEDIAN BARRIER (DESCRIPTION) (LM 9.705 AND 9.825)	100.000	L.F.
711-05.01	REMOVAL & DISPOSAL OF CONCRETE MEDIAN BARRIER	100.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	2,000.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	150.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,342.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	50.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	7.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	240.000	DAY
713-02.14	FLEXIBLE DELINEATOR (WHITE)	275.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	10.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	964.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	964.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	14.000	EACH

Contract ID CNY061 - RUTHERFORD

Item No.	Description	Quantity	Units
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	13.700	L.M.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	8.300	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.300	L.M.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	17.900	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,950.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	1,300.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	7,080.000	L.F.
716-15.10	PREFORMED PERMANENT TAPE (6IN LINE)	9,000.000	L.F.
716-15.11	PREFORMED PERMANENT TAPE (8IN LINE)	7,383.000	L.F.
716-15.20	PREFORMED PERMANENT TAPE (24IN BARRIER LINE)	2,087.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	4,233.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,762.000	S.Y.
604-10.44	EXPANSION JOINT REPAIRS	108.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	30.000	S.Y.
604-10.53	CONCRETE REPAIRS	25.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	11,395.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY020 - RUTHERFORD

Contract ID: CNY020

Letting Date: February 09, 2024 10:00 AM

Projects: 75S001-F3-005
75S001-F8-005
75S002-F8-003

NH/HSIP-1(482)
NH/HSIP-1(482)
STP-2(297)

Counties: RUTHERFORD

District:

DBE Goal Percent: 10.00

Description: The resurfacing on U.S. 41 (S.R. 2) from U.S. 70S (S.R. 1) to near Kensington Square Court and on U.S. 70S (S.R. 1) from south of Ash Street to near South Rutherford Boulevard.

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,081.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	400.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	581.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	70.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	10,590.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	1.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,657.000	TON
607-03.30	18" PIPE CULVERT	138.000	L.F.
611-07.73	18IN ENDWALL (MEDIAN DRAIN)	6.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	115.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,193.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	100.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS	207.000	EACH

Contract ID CNY020 - RUTHERFORD

Item No.	Description	Quantity	Units
716-01.23	(MONO-DIR)(1 COLOR) SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	481.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	788.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,476.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	654.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	45.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	641.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	19.810	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	19.810	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY060 - SHELBY

Contract ID: CNY060

Letting Date: February 09, 2024 10:00 AM

Projects: 79010-3228-94

HSIP-1(339)

Counties: SHELBY

District:

DBE Goal Percent: 8.50

Description: The intersection improvements on U.S. 51 (S.R. 1, Danny Thomas Boulevard) from Poplar Avenue (L.M. 2.85) to S.R. 14 (L.M. 3.47) in Memphis.

Contract Time: DT - 12/20/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	60.000	S.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	500.000	L.F.
604-04.20	PAINTING CONCRETE SURFACES	420.000	S.F.
701-01.01	CONCRETE SIDEWALK (4 ")	445.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	3,185.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	80.000	S.F.
702-01	CONCRETE CURB	1.000	C.Y.
705-01.01	GUARDRAIL AT BRIDGE ENDS	108.000	L.F.
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	300.000	L.F.
706-01	GUARDRAIL REMOVED	108.000	L.F.
707-11.01	PEDESTRIAN CONSTRUCTION BARRIER FENCE	150.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	26.000	EACH
712-06	SIGNS (CONSTRUCTION)	228.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	1,920.000	L.F.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	35.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	11.000	EACH
713-02.21	SIGN POST DELINEATION ENHANCEMENT	164.000	L.F.

Contract ID CNY060 - SHELBY

Item No.	Description	Quantity	Units
713-11.01	"U" SECTION STEEL POSTS	115.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,405.000	LB.
713-11.21	P POST SLIP BASE	11.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	139.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	457.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	207.000	S.F.
713-15.08	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.100" THICK)	14.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	33.000	EACH
714-03.02	DIRECT BURIAL CONDUIT (3" PVC, SCHEDULE 40)	1,000.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	151.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	688.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	28.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	152.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,284.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	19.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	3.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	1.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	4.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	3.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	3.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.700	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	990.000	L.F.

Contract ID CNY060 - SHELBY

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	3.000	EACH
730-02.02	SIGNAL HEAD ASSEMBLY (130 A3)	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	24.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	9.000	EACH
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2 POLE MOUNTED)	9.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	19.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	4.000	EACH
730-03.52	FIBER OPTIC CABLE (6F)	1,000.000	L.F.
730-05.04	MODIFY EXISTING ELECTRICAL SERVICE CONNECTION	3.000	EACH
730-08.01	SIGNAL CABLE - 3 CONDUCTOR	2,469.000	L.F.
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	1,355.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	8,344.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	1,882.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	640.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	2,356.000	L.F.
730-13.06	VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	12.000	EACH
730-13.16	VEHICLE DETECTOR (RADAR/VIDEO)	12.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	3.000	EACH
730-16.04	CONTROLLER (ATC)	3.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	11.000	EACH
730-25.01	CANTILEVER SIGNAL SUPPORT (1 ARM @ 50')	1.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	2.000	EACH
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	3.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	2.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH

Contract ID CNY060 - SHELBY

Item No.	Description	Quantity	Units
730-25.16	CANTILEVER SIGNAL SUPPORT (1 ARM @ 80')	1.000	EACH
730-25.18	CANTILEVER SIGNAL SUPPORT (1 ARM @ 90')	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	24.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	3.000	EACH
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	500.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY034 - SHELBY

Contract ID: CNY034

Letting Date: February 09, 2024 10:00 AM

Projects: 79S014-F3-005

R-STP-14(70)

Counties: SHELBY

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, paving, construction of a concrete Bulb-Tee beam bridge and box bridge on S.R. 14 (Austin Peay Highway) from east of Kerrville-Rosemark Road (L.M. 34.29) to the Tipton County line (L.M. 38.87).

Contract Time: DT - 6/30/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	5,240.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	357,898.000	C.Y.
203-01.13	ROAD & DRAINAGE EXCAVATION (STREAM MITIGATION)	3,121.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	168,356.000	C.Y.
203-03.10	SELECT GRANULAR MATERIAL	50,000.000	TON
203-04	PLACING AND SPREADING TOPSOIL	39,854.000	C.Y.
203-05	UNDERCUTTING	325.000	C.Y.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	16.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-08	FOUNDATION FILL MATERIAL	851.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	483.000	C.Y.
209-02.07	18" TEMPORARY SLOPE DRAIN	173.000	L.F.
209-03.23	FILTER SOCK (24 INCH)	111.000	L.F.
209-03.40	STREAM MITIGATION - LOG RIFFLE	32.000	L.F.
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	249.000	L.F.
209-03.47	STREAM MITIGATION - LONGITUDINAL STONE TOE	128.000	C.Y.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
	(DESCRIP)		
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	249.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	13.000	EACH
209-05	SEDIMENT REMOVAL	6,831.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (LOW FLOW CHANNEL)	444.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	47,729.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	70,762.000	L.F.
209-08.07	ROCK CHECK DAM	119.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	134.000	EACH
209-09.01	SANDBAGS	18,533.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	17.000	EACH
209-10.20	TEMPORARY SEDIMENT TRAP	1,387.000	C.Y.
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	467.000	S.Y.
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	115.000	S.Y.
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	26.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	3.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	1,238.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	376.000	L.F.
302-01.01	HYDRATED LIME	5,255.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	12,015.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,791.000	TON
303-10.03	MINERAL AGGREGATE (SIZE 68)	236.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,974.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	21,962.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	800.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	2,167.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	8.100	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN	7.800	L.M.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
	WIDTH)		
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	3,972.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	1,183.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	232,270.000	LB.
606-24.12	TEMPORARY SHEET PILES	2,250.000	S.F.
607-03.05	18" CONCRETE PIPE CULVERT(CLASS IV)JACKED-IN-PLACE	50.000	L.F.
607-03.30	18" PIPE CULVERT	2,620.000	L.F.
607-05.06	24" PIPE CULVERT (JACKED-IN-PLACE)	85.000	L.F.
607-05.30	24" PIPE CULVERT	547.000	L.F.
607-06.06	30" PIPE CULVERT (JACKED-IN-PLACE)	182.000	L.F.
607-06.07	36" PIPE CULVERT (JACKED-IN-PLACE)	290.000	L.F.
607-06.30	30" PIPE CULVERT	286.000	L.F.
607-07.30	36" PIPE CULVERT	638.000	L.F.
607-08.30	42" PIPE CULVERT	325.000	L.F.
607-09.05	48" CONCRETE PIPE CULVERT(CLASS IV)JACKED-IN-PLACE	124.000	L.F.
607-09.30	48" PIPE CULVERT	235.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	1,490.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	576.000	L.F.
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	68.000	L.F.
607-39.05	36" PIPE CULVERT (SIDE DRAIN)	82.000	L.F.
611-01.01	MANHOLES, 0' - 4' DEPTH	1.000	EACH
611-02.10	JUNCTION BOX, TYPE 1	1.000	EACH
611-02.12	JUNCTION BOX, TYPE 3	4.000	EACH
611-05.01	TRENCH DRAINS	200.000	L.F.
611-05.02	12IN PVC PIPE FOR TRENCH DRAINS	37.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	49.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	1,753.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	23.000	EACH
611-07.32	24IN ENDWALL (SIDE DRAIN)	5.000	EACH

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
611-07.33	30IN ENDWALL (SIDE DRAIN)	5.000	EACH
611-07.34	36IN ENDWALL (SIDE DRAIN)	4.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	9.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	6.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.59	24IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.61	30IN ENDWALL (CROSS DRAIN) 4:1	3.000	EACH
611-07.62	30IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.64	36IN ENDWALL (CROSS DRAIN) 4:1	6.000	EACH
611-07.65	36IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-07.66	42IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.67	42IN ENDWALL (CROSS DRAIN) 4:1	9.000	EACH
611-07.70	48IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.73	18IN ENDWALL (MEDIAN DRAIN)	9.000	EACH
611-38.01	CATCH BASINS, TYPE 38, 0' - 4' DEPTH	11.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	2.000	EACH
611-38.03	CATCH BASINS, TYPE 38, > 8' - 12' DEPTH	4.000	EACH
611-38.04	CATCH BASINS, TYPE 38, > 12' - 16' DEPTH	1.000	EACH
611-39.01	CATCH BASINS, TYPE 39, 0' - 4' DEPTH	3.000	EACH
611-39.02	CATCH BASINS, TYPE 39, > 4' - 8' DEPTH	2.000	EACH
611-39.03	CATCH BASINS, TYPE 39, > 8' - 12' DEPTH	1.000	EACH
611-39.04	CATCH BASINS, TYPE 39, > 12' - 16' DEPTH	1.000	EACH
611-40.01	CATCH BASINS, TYPE 40, 0' - 4' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	28.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	44.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	53.000	L.F.
621-03.07	48" TEMPORARY DRAINAGE PIPE	27.000	L.F.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
621-03.10	66" TEMPORARY DRAINAGE PIPE	100.000	L.F.
621-03.12	TEMPORARY DRAINAGE PIPE ARCH (DESCRIPTION) (87" X 63" ALUMINIUM)	107.000	L.F.
701-02	CONCRETE DRIVEWAY	3,216.000	S.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	56.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	12,092.000	L.F.
705-06.10	GR TERMINAL TRAILING END (TYPE 13) MASH TL-3	24.000	EACH
705-06.15	SHORT-RADIUS GUARDRAIL SYSTEM (16 FT RADIUS) MASH TL-3 (11 @ R=8' AND 1 @ R=48')	12.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	19.000	EACH
705-06.25	THREE BEAM BRIDGE TRANSITION MASH TL-3	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	1,411.000	L.F.
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	2.000	EACH
707-03.01	STOCK FENCE	4,275.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY (STOCK FENCE)	28.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	25,762.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	89.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	5,211.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	2,558.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	2,054.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	513.000	TON
709-05.81	ROCK RIFFLES	(1)	LS
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	42,588.000	L.F.
710-05	LATERAL UNDERDRAIN	5,928.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	3.000	EACH
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	16.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	75.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	125.000	EACH
710-10.02	6" PERFORATED PLASTIC PIPE	345.000	L.F.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
711-05.78	GRADE SEPARATED SINGE SLOPE MEDIAN WALL	300.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	19,870.000	L.F.
712-02.36	REMOVE AND RELOCATE PORTABLE BARRIER RAIL	19,870.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	61.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	314.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	980.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,473.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	144.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	2.500	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	45.000	LB.
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	6.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	40.000	EACH
713-11.01	"U" SECTION STEEL POSTS	11,333.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,730.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	2,148.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	318.750	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	593.000	EACH
716-01.07	TEMPORARY RAISED PAVEMENT MARKER,YELLOW	508.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	562.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	130.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	272.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	128.000	S.Y.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	510.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	15.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,979.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.500	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	11.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	179.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	9.400	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	5,817.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	443.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	24.000	L.M.
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	20.000	L.M.
716-08.33	HYDROBLAST REMOVAL OF PAVEMENT MARKING (DESCRIPTION) (PAVEMENT ARROWS)	2.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	20.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,600.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	2,884.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	7,387.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	75,887.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	37,136.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	819.000	UNIT
801-01.30	COVER CROP SEED MIX (RIPZN/FLPL) W/MULCH	21.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	65.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	87.000	UNIT
801-03	WATER (SEEDING & SODDING)	2,833.000	M.G.
801-07	SEED (SUPPLEMENTAL APPLICATION)	200.000	LB.
801-08	FERTILIZER (SUPPLEMENTAL APPLICATION)	3.000	TON
802-02.40	CUTTINGS: SALIX NIGRA (24-48IN LENGTH)	1,383.000	EACH

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
802-02.41	CUTTINGS: SALIX SERICEA (24-48IN)	1,383.000	EACH
802-02.42	CUTTINGS: CORNUS AMOMUM (24-48IN)	1,383.000	EACH
802-02.45	CUTTINGS: CEPHALANTHUS OCCIDENTALIS (24-48IN)	1,383.000	EACH
802-11.01	ACER NEGUNDO (BOX ELDER 2-5FT CNTNR GRWN)	44.000	EACH
802-11.16	FRAXINUS PENNSYLVANICA (GREEN ASH 2-5FT CNTNR GRWN)	44.000	EACH
802-11.18	LIQUIDAMBER STYRACIFLUA (SWEETGUM 2-5FT CNTNR GRWN)	44.000	EACH
802-11.39	QUERCUS RUBRA (NORTHERN RED OAK 2-5FT CNTNR GRWN)	44.000	EACH
802-11.44	ULMUS AMERICANA (AMERICAN ELM 2-5FT CNTNR GRWN)	44.000	EACH
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	94.000	EACH
802-12.16	FRAXINUS PENNSYLVANICA (GREEN ASH SEEDLNG B.R.)	94.000	EACH
802-12.18	LIQUIDAMBER STYRACIFLUA (SWEETGUM SEEDLNG B.R.)	94.000	EACH
802-12.38	QUERCUS PHELLOS (WILLOW OAK SEEDLNG B.R.)	94.000	EACH
802-12.44	ULMUS AMERICANA (AMERICAN ELM SEEDLNG B.R.)	94.000	EACH
803-01	SODDING (NEW SOD)	240,776.000	S.Y.
805-01.03	TURF REINFORCEMENT MAT (CLASS III)	8,164.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	17,476.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	1,844.000	S.Y.
806-02.03	PROJECT MOWING	10.000	CYCL
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (64' OF 2 @ 10'X7' RCBB, STA. 597+95)	(1)	LS
202-04.51	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (76' OF 2 @ 10'X9' RCBB, STA. 724+28)	(1)	LS
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	1,522.400	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	298,087.400	LB.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EX. BR. NO. 79-SR14-38.24)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	348.000	C.Y.

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
303-01.02	GRANULAR BACKFILL (BRIDGES)	64.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	64,952.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	208.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	22,108.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	436.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	266.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	738.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	8.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,404.000	S.Y.
606-09.01	TEST PILES (PRECAST CONCRETE, SIZE 1)	250.000	L.F.
606-09.02	LOADING TEST (PRECAST CONCRETE, SIZE 1)	2.000	EACH
606-09.03	PRECAST CONCRETE PILES (SIZE 1)	3,150.000	L.F.
606-12.01	PILE ANCHORAGE SYSTEM (SEISMIC)	60.000	EACH
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	1,070.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	566.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	264.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	72.000	L.F.
790-02.30	POLE 35FT CLASS 1 WOOD	1.000	EACH
790-03.02	POLE 40FT CLASS 3 WOOD	9.000	EACH
790-03.30	POLE 40FT CLASS 1 WOOD	2.000	EACH
790-04.01	POLE 45FT CLASS 1 WOOD	10.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	12.000	EACH
790-05.01	POLE 50FT CLASS 1 WOOD	4.000	EACH
790-05.03	POLE 50FT CLASS 3 WOOD	7.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	3.000	EACH
790-22.01	1PH SGL PRIMARY SUPPORT 25KV	9.000	EACH
790-22.02	1PH DBL PRIMARY SUPPORT 25KV	7.000	EACH
790-22.11	1PH DDE ANGLE 25KV	7.000	EACH
790-22.13	1PH DEAD END 25KV	3.000	EACH

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
790-22.14	1PH DEAD END TAP 25KV	11.000	EACH
790-26.03	3PH CROSSARM SGL LRG COND 25KV	2.000	EACH
790-26.12	3PH CROSSARM DBL SM ANGLE 25KV	1.000	EACH
790-26.25	3PH CROSSARM DDE 25KV	5.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	3.000	EACH
790-30.04	SECONDARY ASSEMBLIES MISC	5.000	EACH
790-30.42	SECONDARY CONDUCTOR___ SGL COND (SEE PLANS)	150.000	L.F.
790-32.24	GUY (DESCRIPTION) (OVERHEAD,LIGHT, INCL ANCH PER MLGW DESIG)	3.000	EACH
790-36.06	TRANSFER LIGHT	4.000	EACH
790-36.14	TRANSFER CONDUCTOR	20.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	610.000	L.F.
790-40.02	OH COND 2 7/1 ACSR SPARATE	14,300.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	203.000	L.F.
790-40.06	OH COND 4/0 6/1 ACSR PENGUIN	1,060.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	3,180.000	L.F.
790-41.51	UG SEC COND 350 AL TPLX	110.000	L.F.
790-42.09	3IN DIA PVC PIPE	115.000	L.F.
790-42.10	4IN DIA PVC PIPE	150.000	L.F.
790-43.46	SECONDARY PULLBOX LARGE	1.000	EACH
790-43.60	PRIMARY RISER (DESCRIPTION) (316.77)	1.000	EACH
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	1.000	EACH
790-49.02	3PH XFMR BNK POLE MTD W/ FUSE/ARRESTERS	2.000	EACH
790-65.04	LIGHTNING ARRESTER POLE MTD 9 KV	2.000	EACH
790-98.01	REMOVE WIRE	21,500.000	L.F.
790-98.02	REMOVE POLES	54.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	99.000	EACH
203-06	WATER	3,442.000	M.G.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	281,388.000	TON

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	7,688.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	21,962.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	65,840.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	17,914.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	365.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1,298.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	145.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,300.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	10,065.000	TON
203-06	WATER	2,461.000	M.G.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	113,413.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	7,688.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	21,962.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	32,920.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	17,914.000	TON
309-01.01	MINERAL AGGREGATE (A-CBC)	52,752.000	TON
309-01.02	PORTLAND CEMENT (A-CBC)	2,037.000	TON
309-02	BITUMINOUS MATERIAL (A-CBC)	142.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	365.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1,298.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	145.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,300.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	10,065.000	TON
203-06	WATER	2,765.000	M.G.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	160,130.000	TON

Contract ID CNY034 - SHELBY

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	9,858.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	805.000	TON
309-01.01	MINERAL AGGREGATE (A-CBC)	41,358.000	TON
309-01.02	PORTLAND CEMENT (A-CBC)	1,597.000	TON
309-02	BITUMINOUS MATERIAL (A-CBC)	111.000	TON
313-03	TREATED PERMEABLE BASE	127,542.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	161.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	600.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	47.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,497.000	TON
501-01.02	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 9"	127,542.000	S.Y.
203-06	WATER	3,743.000	M.G.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (SEE PLANS)	316,167.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	9,858.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	805.000	TON
313-03	TREATED PERMEABLE BASE	127,542.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	161.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	600.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	47.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,497.000	TON
501-01.02	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 9"	127,542.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY038 - SHELBY

Contract ID: CNY038

Letting Date: February 09, 2024 10:00 AM

Projects: 79S023-F3-003
79S023-F8-003
79S023-M3-004

STP/HSIP-23(15)
STP/HSIP-23(15)
STP/HSIP-23(15)

Counties: SHELBY

District:

DBE Goal Percent: 8.00

Description: The resurfacing on S.R. 23 from S.R. 57 (L.M. 3.05) to I-240 (L.M. 8.83), including bridge expansion joint repairs and thin epoxy overlay.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	70.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	6,480.000	S.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.600	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	2,192.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	2,981.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	189.000	TON
403-02.01	TRACKLESS TACK COAT	95.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	23.200	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	14,196.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	14,034.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	22,000.000	LB.
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	25.000	EACH
701-01.01	CONCRETE SIDEWALK (4 ")	630.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	2,053.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	53.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNY038 - SHELBY

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	120.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,909.500	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	652.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	651.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	50.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	440.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	114.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	2,387.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	22.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	19.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	19.500	L.M.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	4.000	EACH
730-14.02	SAW SLOT	2,875.000	L.F.
730-14.03	LOOP WIRE	5,900.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	176.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	3,432.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY043 - SHELBY

Contract ID: CNY043

Letting Date: February 09, 2024 10:00 AM

Projects: R4SVAR-F8-034

STP-REG4(225)

Counties: SHELBY

District:

DBE Goal Percent:

Description: The crack sealing at various locations on various State Routes.

Contract Time: DT - 8/30/2024

Item No.	Description	Quantity	Units
411-04	CRACK SEALANT	130,996.000	LB.
712-01	TRAFFIC CONTROL	(1)	LS
712-08.12	QUEUE PROTECTION TRUCK	13.000	DAY
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY012 - SULLIVAN

Contract ID: CNY012

Letting Date: February 09, 2024 10:00 AM

Projects: 82S036-F3-003
 82S036-F8-003
 82S357-F3-002
 82S357-F8-002

NH/HSIP-36(77)
 NH/HSIP-36(77)
 NH/HSIP-357(4)
 NH/HSIP-357(4)

Counties: SULLIVAN

District:

DBE Goal Percent: 9.00

Description: The resurfacing on S.R. 36 from near Summerville Road (L.M. 4.78) to Eastman Road (L.M. 7.71), and on S.R. 357 from near S.R. 75 (L.M. 0.02) to near I-81 (L.M. 2.41).

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	18.000	L.M.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	112.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,599.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	12,552.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	4.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	16,370.000	TON
701-02.01	CONCRETE CURB RAMP (RETROFIT)	5,325.000	S.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	8.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	554.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	277.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,354.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH

Contract ID CNY012 - SULLIVAN

Item No.	Description	Quantity	Units
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	962.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	904.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,060.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,636.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	79.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	990.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	2,956.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	15.000	S.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	22.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	27.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	36.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	21,500.000	L.F.
730-14.03	LOOP WIRE	43,000.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY039 - SUMNER

Contract ID: CNY039

Letting Date: February 09, 2024 10:00 AM

Projects: 83S386-M3-003

n/a

Counties: SUMNER

District:

DBE Goal Percent:

Description: The repair of the bridge on S.R. 386 over U.S. 31E (S.R. 6, Gallatin Road) and Ramp F (L.M. 6.84).

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (PARTIAL, BR. NO. 83-SR386-06.84 LT)	(1)	LS
209-05	SEDIMENT REMOVAL	2.000	C.Y.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
502-01	CLEANING AND SEALING JOINTS	375.000	L.F.
602-08.01	JACKING STRUCTURES (DESCRIPTION) (STEEL SPAN AT ABUTMENT NO. 1 & BENT NO. 1)	(1)	LS
602-10.12	BEARING DEVICE (REPAIR)	(1)	LS
602-10.32	STRUCTURAL STEEL (REPAIRS)	11,590.000	LB.
602-10.60	BEARING DEVICE (DESCRIPTION) (EXP. BEARINGS @ ABUT. NO. 1)	8.000	EACH
604-02.03	EPOXY COATED REINFORCING STEEL	1,026.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	5.000	C.Y.
604-03.74	CLASS X CONCRETE	2.000	C.Y.
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	62.944	S.Y.
604-10.05	CONCRETE	7.000	S.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	10.000	S.Y.
604-10.54	CONCRETE REPAIRS	7.000	S.F.
604-10.60	EXPANSION JOINT REPAIRS (MODULAR TYPE)	147.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	348.250	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	73.000	S.Y.

Contract ID CNY039 - SUMNER

Item No.	Description	Quantity	Units
617-05	SEALANT (DESCRIPTION) (HMWM)	5.000	GAL.
620-09	REMOVAL & REPLACEMENT OF EXISTING BRIDGE RAIL	48.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	852.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	1,713.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	196.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	110.700	EACH
712-06	SIGNS (CONSTRUCTION)	617.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	48.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	31,304.550	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	700.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	559.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	2.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY016 - WEAKLEY

Contract ID: CNY016

Letting Date: February 09, 2024 10:00 AM

Projects: 92S445-F3-002

HSIP-445(10)

Counties: WEAKLEY

District:

DBE Goal Percent: 7.00

Description: The miscellaneous safety improvements including resurfacing on S.R. 445 from the Gibson County line (L.M. 0.00) to near Losson Puckett Road (L.M. 4.99).

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	852.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	4,638.000	TON
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	98.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	807.000	TON
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	9.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	2,042.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,220.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	16.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	2,042.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	6.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	12.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	270.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	390.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,957.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	174.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	408.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	40.000	EACH

Contract ID CNY016 - WEAKLEY

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	397.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	240.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	100.000	S.Y.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	20.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	20.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	792.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY035 - WEAKLEY

Contract ID: CNY035

Letting Date: February 09, 2024 10:00 AM

Projects: 92953-3555-04
92953-3557-04

n/a
NA

Counties: WEAKLEY

District:

DBE Goal Percent:

Description: The grading, drainage, and paving on S.I.A. routes serving Project Dove and MTD Projects, Inc.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (12", 15+91.03 LT)	30.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (12", 17+03.28 RT)	33.000	L.F.
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (12", 24+71.60 LT)	22.000	L.F.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	635.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	5,543.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,242.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	850.000	C.Y.
203-06	WATER	72.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	364.111	C.Y.
209-05	SEDIMENT REMOVAL	216.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	550.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	8,707.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	15.500	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,399.000	TON

Contract ID CNY035 - WEAKLEY

Item No.	Description	Quantity	Units
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,251.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	13.900	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	47.200	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	10.700	TON
411-02.10	ACS MIX(PG70-22) GRADING D	723.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	39.000	L.F.
607-03.30	18" PIPE CULVERT	45.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	157.000	L.F.
607-57.01	REINFORCED CONCRETE PIPE ARCH (22" X 13")	20.000	L.F.
611-07.31	18IN ENDWALL (SIDE DRAIN)	5.000	EACH
611-07.32	24IN ENDWALL (SIDE DRAIN)	2.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	90.000	L.F.
701-02	CONCRETE DRIVEWAY	654.000	S.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	300.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	175.700	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	78.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	18.000	EACH
712-06	SIGNS (CONSTRUCTION)	457.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	132.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.21	SIGNS (DESCRIPTION) (R1-1)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (R2-1)	2.000	EACH
713-16.23	SIGNS (DESCRIPTION) (D3-1)	2.000	EACH
713-16.24	SIGNS (DESCRIPTION) (R1-1)	2.000	EACH
713-16.25	SIGNS (DESCRIPTION) (R2-1)	2.000	EACH
713-16.26	SIGNS (DESCRIPTION) (D3-1)	4.000	EACH

Contract ID CNY035 - WEAKLEY

Item No.	Description	Quantity	Units
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.876	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	87.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	647.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	2,720.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	100.000	UNIT
801-03	WATER (SEEDING & SODDING)	98.000	M.G.
803-01	SODDING (NEW SOD)	10,621.751	S.Y.

() Item will be bid as lump sum.

Contract ID CNY017 - WILLIAMSON

Contract ID: CNY017

Letting Date: February 09, 2024 10:00 AM

Projects: 94S011-F3-006
94S011-F8-006

NH/HSIP-11(122)
NH/HSIP-11(122)

Counties: WILLIAMSON

District:

DBE Goal Percent: 6.00

Description: The resurfacing on U.S. 31A (U.S. 41A, S.R. 11) from S.R. 96 (L.M. 7.41) to the Davidson County line (L.M. 17.14).

Contract Time: DT - 10/15/2024

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	19.460	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,525.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	352.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	83.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	13,271.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	19.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,887.000	TON
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	100.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	1,030.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,922.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	943.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	362.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,305.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	360.000	S.Y.

Contract ID CNY017 - WILLIAMSON

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	540.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	54.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	4,000.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	74.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	1.300	L.M.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	6.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	85.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	42.800	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	2,028.000	L.F.
730-14.03	LOOP WIRE	4,570.000	L.F.

() Item will be bid as lump sum.

