

## Estimated Quantities -- Letting October 15, 2024

**Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from [www.bidx.com](http://www.bidx.com)**

**Contract ID CNY309 - MCMINN**

---

**Contract ID:** CNY309

**Letting Date:** October 15, 2024 10:00 AM

**Projects:** 54S039-M1-008

N/A

**Counties:** MCMINN

**District:**

**DBE Goal Percent:**

**Description:** The emergency sinkhole repairs at two locations on S.R. 39 at L.M. 4.2.

**Contract Time:** DT - 2/15/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	488.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	4,637.000	TON
203-06	WATER	8.000	M.G.
203-15.03	COMPACTED CLAY	90.000	C.Y.
204-05.20	GROUT CASING INSTALLATION	3,555.000	L.F.
204-06.01	FLOWABLE FILL (GENERAL)	598.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	500.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	493.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	95.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	68.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON

**Contract ID CNY309 - MCMINN**

<b>Item No.</b>	<b>Description</b>	<b>Quantity</b>	<b>Units</b>
411-01.10	ACS MIX(PG64-22) GRADING D	40.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	0.100	L.M.
604-15.20	COMPACTION GROUT	17,064.000	C.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	6.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	6.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS
801-03	WATER (SEEDING & SODDING)	25.000	M.G.
803-01	SODDING (NEW SOD)	271.000	S.Y.

**( ) Item will be bid as lump sum.**

