

Estimated Quantities -- Letting October 02, 2026

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CN261076 - ANDERSON

Contract ID: CN261076

Letting Date: October 02, 2026 10:00 AM

Projects: 01S061-F3-004

NH-SIP-61(58)

Counties: ANDERSON

District:

DBE Goal Percent:

Description: The construction of a turn lane on S.R. 61 at the intersection of Sinking Springs Road/Lewallen Hollow Road (L.M. 17.55) in Clinton, including grading, drainage, lighting and paving.

Contract Time: DT - 5/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	614.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	159.000	C.Y.
203-06	WATER	1.000	M.G.
209-05	SEDIMENT REMOVAL	14.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	617.000	L.F.
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	3.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	882.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	103.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	150.700	TON
307-01.20	ASP. CONC. MIX(PG64-22) (BPMB-HM) GR. A-S	98.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.100	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	515.000	L.F.

Contract ID CN261076 - ANDERSON

Item No.	Description	Quantity	Units
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	34.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	188.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.090	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	140.000	TON
709-05.05	MACHINED RIP-RAP (CLASS A-3)	89.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	516.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	180.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
714-03	JACKED OR BORED CONDUIT	250.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	330.000	L.F.
714-05.04	PULL BOXES (TYPE C)	2.000	EACH
714-06.04	CABLE (1/C # 8 AWG)	1,914.000	L.F.
714-08.30	REMOVE & RELOCATE LIGHT STANDARD	2.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (SEE FOOTNOTES SHEET L-1)	(1)	LS
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	7.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	159.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	20.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	404.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.230	L.M.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.200	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	20.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.100	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,200.000	S.Y.

Contract ID CN261076 - ANDERSON

Item No.	Description	Quantity	Units
801-02	SEEDING (WITHOUT MULCH)	5.300	UNIT
801-03	WATER (SEEDING & SODDING)	1.000	M.G.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	594.000	S.Y.

() Item will be bid as lump sum.

Contract ID CN261066 - ANDERSON , BLOUNT, ETC.

Contract ID: CN261066**Letting Date:** October 02, 2026 10:00 AM**Projects:** R1BVAR-M3-089

N/A

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER, GREENE,
HAMBLEN, HANCOCK, HAWKINS,
JEFFERSON, JOHNSON, KNOX, LOUDON,
MONROE, MORGAN, ROANE, SCOTT,
SEVIER, SULLIVAN, UNICOI, UNION,
WASHINGTON**District:****DBE Goal Percent:****Description:** The random on-call asphalt pothole patching on various Interstate and State Routes.**Contract Time:** DT - 12/31/2027

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	50.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	500.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	5,000.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
712-01.09	LANE CLOSURE (STATE ROUTES)	95.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	5.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
717-01.21	MOBILIZATION (STATE ROUTES) (STATE ROUTES)	35.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	60.000	EACH

() Item will be bid as lump sum.

Contract ID CN263064 - BEDFORD**Contract ID:** CN263064**Letting Date:** October 02, 2026 10:00 AM**Projects:** 02LCOU-F3-004

BRZ-200(45)

Counties: BEDFORD**District:****DBE Goal Percent:****Description:** The construction of a concrete box bridge on Old Highway 64 over Stokes Branch (L.M. 0.11), including grading, drainage, and paving.**Contract Time:** DT - 10/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	272.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BRIDGE # 020A664001, STA. 15+50.84)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	814.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	119.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	85.000	C.Y.
203-06	WATER	23.000	M.G.
209-05	SEDIMENT REMOVAL	17.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	450.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	340.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	8.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	150.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	385.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	44.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	56.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.400	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	5.000	TON

Contract ID CN263064 - BEDFORD

Item No.	Description	Quantity	Units
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.300	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	270.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	33.000	TON
621-05.02	TEMPORARY SHORING	(1)	LS
705-01.04	METAL BEAM GUARD FENCE	125.000	L.F.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	16.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	250.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
705-08.11	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	200.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	8.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	320.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	124.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	20.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	105.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	12.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	565.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	9.400	UNIT
801-03	WATER (SEEDING & SODDING)	1.000	M.G.
803-01	SODDING (NEW SOD)	521.000	S.Y.
204-08	FOUNDATION FILL MATERIAL	100.000	C.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	952.800	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	220.000	C.Y.

Contract ID CN263064 - BEDFORD

Item No.	Description	Quantity	Units
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	50,805.000	LB.
709-05.08	MACHINED RIP-RAP (CLASS B)	300.000	TON

() Item will be bid as lump sum.

Contract ID CN263062 - BEDFORD , CHEATHAM, ETC.

Contract ID: CN263062**Letting Date:** October 02, 2026 10:00 AM**Projects:** R3SVAR-M3-119

N/A

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON**District:****DBE Goal Percent:****Description:** The random on-call asphalt pothole patching on various Interstate and State Routes.**Contract Time:** DT - 12/31/2027

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	40.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	700.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	300.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
712-01.09	LANE CLOSURE (STATE ROUTES)	100.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	5.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
717-01.21	MOBILIZATION (STATE ROUTES) (STATE ROUTES)	60.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	40.000	EACH

() Item will be bid as lump sum.

Contract ID CN264056 - BENTON , CARROLL, ETC.

Contract ID: CN264056**Letting Date:** October 02, 2026 10:00 AM**Projects:** R4BVAR-M3-095

N/A

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
DECATUR, DYER, FAYETTE, GIBSON,
HARDEMAN, HARDIN, HAYWOOD,
HENDERSON, HENRY, LAKE, LAUDERDALE,
MADISON, MCNAIRY, OBION, SHELBY,
TIPTON, WEAKLEY**District:****DBE Goal Percent:****Description:** The random on-call asphalt pothole patching on various Interstate and State Routes.**Contract Time:** DT - 12/31/2027

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	40.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	700.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	300.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	27.000	EACH
712-01.09	LANE CLOSURE (STATE ROUTES)	40.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	10.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	27.000	EACH
717-01.21	MOBILIZATION (STATE ROUTES) (STATE ROUTES)	35.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	5.000	EACH

() Item will be bid as lump sum.

Contract ID CN264058 - BENTON , GIBSON, ETC.

Contract ID: CN264058**Letting Date:** October 02, 2026 10:00 AM**Projects:** 03S069-F3-008

CRP-69(118)

27S043-F3-004

CRP-43(51)

66S431-F3-004

CRP-431(21)

92SVAR-F3-001

CRP-9408(14)

Counties: BENTON, GIBSON, OBION, WEAKLEY**District:****DBE Goal Percent:****Description:** The traffic signal modernization improvements at various intersections along various U.S. and State Routes.**Contract Time:** DT - 11/30/2027

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	8.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	3.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	340.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,490.000	L.F.
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	4.000	EACH
730-13.18	VEHICLE DETECTOR (RADAR-SINGLE UNIT MULTI-APPROACH)	1.000	EACH
730-13.30	VEHICLE DETECTOR (GPS ACTIVATED PRIORITY CONTROL)	44.000	EACH
730-15.16	CABINET MAINTENANCE (FILTER)	15.000	EACH
730-15.25	MODIFY CABINET (CONTROLLER PROGRAMMING)	6.000	EACH
730-15.26	MODIFY CABINET (RADAR INSTALLATION)	1.000	EACH
730-15.28	MODIFY CABINET (EMERGENCY PREEMPTION)	12.000	EACH
730-16.04	CONTROLLER (ATC)	7.000	EACH

Contract ID CN264058 - BENTON , GIBSON, ETC.

Item No.	Description	Quantity	Units
730-16.51	CABINET MONITOR UNIT	7.000	EACH

() Item will be bid as lump sum.

Contract ID CN262063 - BLEDSOE , BRADLEY, ETC.

Contract ID: CN262063**Letting Date:** October 02, 2026 10:00 AM**Projects:** R2BVAR-M3-070

N/A

Counties: BLEDSOE, BRADLEY, CANNON, CLAY,
COFFEE, CUMBERLAND, DEKALB,
FENTRESS, FRANKLIN, GRUNDY,
HAMILTON, JACKSON, MARION, MCMINN,
MEIGS, OVERTON, PICKETT, POLK,
PUTNAM, RHEA, SEQUATCHIE, VAN BUREN,
WARREN, WHITE**District:****DBE Goal Percent:****Description:** The random on-call asphalt pothole patching on various Interstate and State Routes.**Contract Time:** DT - 12/31/2027

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	40.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	500.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	300.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
712-01.09	LANE CLOSURE (STATE ROUTES)	95.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	5.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
717-01.21	MOBILIZATION (STATE ROUTES) (STATE ROUTES)	45.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	40.000	EACH

() Item will be bid as lump sum.

Contract ID CN262064 - BRADLEY

Contract ID: CN262064**Letting Date:** October 02, 2026 10:00 AM**Projects:** 06S002-F3-006

HSIP-2(294)

Counties: BRADLEY**District:****DBE Goal Percent:****Description:** The installation of signals on U.S. 11 (S.R. 2) at the intersection of 17th Street Northwest (L.M. 9.93) in Cleveland.**Contract Time:** DT - 10/2/2027

Item No.	Description	Quantity	Units
701-01.01	CONCRETE SIDEWALK (4 ")	50.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	150.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	69.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	16.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	91.000	L.F.
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	91.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-01.03	MODIFICATION OF EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	560.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	1.000	EACH
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	70.000	L.F.
730-15.07	CABINET (DESCRIPTION) (16 PHASE BASE MOUNTED)	1.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	2.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	2.000	EACH
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	40.000	L.F.

Contract ID CN262064 - BRADLEY

() Item will be bid as lump sum.

Contract ID CN261065 - CAMPBELL & MORGAN**Contract ID:** CN261065**Letting Date:** October 02, 2026 10:00 AM**Projects:** 07LCOU-F3-002
65S062-F3-003HSIP-700(42)
HSIP-62(60)**Counties:** CAMPBELL, MORGAN**District:****DBE Goal Percent:****Description:** The miscellaneous safety improvements on various local roads in Campbell County, and on S.R. 62 in Morgan County from Petit Lane (L.M. 24.99) to the Roane County line (L.M. 35.73).**Contract Time:** DT - 8/31/2027

Item No.	Description	Quantity	Units
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	5.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	1,325.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,375.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
706-01	GUARDRAIL REMOVED	225.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	2,052.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	3,346.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	11,469.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,673.250	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	1,725.500	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	175.000	EACH
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (DESCRIPTION)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,100.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	709.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	101.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	125.000	L.M.

Contract ID CN261065 - CAMPBELL & MORGAN

Item No.	Description	Quantity	Units
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	6,390.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-26.08	FLASHING WARNING BEACON (DESCRIPTION) (DESCRIPTION)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CN261070 - CARTER

Contract ID: CN261070**Letting Date:** October 02, 2026 10:00 AM**Projects:** 10S037-M3-005
10S037-M3-006ER-NH-37(29)
ER-STP-37(32)**Counties:** CARTER**District:****DBE Goal Percent:****Description:** The bridge rehabilitation on U.S. 19E (S.R. 37) under the bridges over Laurel Fork Creek (L.M. 16.96), including slope repair near L.M. 17.1.**Contract Time:** DT - 7/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,169.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	5,972.000	TON
203-07	FURNISHING & SPREADING TOPSOIL	151.352	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-06.01	FLOWABLE FILL (GENERAL)	444.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.300	L.M.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	110.000	L.F.
209-09.60	BAG BARRIER SYSTEM (DESCRIPTION) (2 FOOT TALL)	1,050.000	L.F.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	2.000	EACH
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	34.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	108.000	TON
621-03.02	18" TEMPORARY DRAINAGE PIPE	60.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	680.000	L.F.
706-01	GUARDRAIL REMOVED	680.000	L.F.

Contract ID CN261070 - CARTER

Item No.	Description	Quantity	Units
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	110.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	182.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,200.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	380.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	5.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	76.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	79.000	EACH
712-06	SIGNS (CONSTRUCTION)	570.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	22.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	2,000.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	1,850.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	720.000	L.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	10.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	10.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	710.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.300	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	258.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,640.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	384.000	L.F.
801-02	SEEDING (WITHOUT MULCH)	5.000	UNIT
801-03	WATER (SEEDING & SODDING)	1.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	908.000	S.Y.

Contract ID CN261070 - CARTER

() Item will be bid as lump sum.

Contract ID CN261067 - CARTER**Contract ID:** CN261067**Letting Date:** October 02, 2026 10:00 AM**Projects:** 10S143-F3-005**ER-STP-143(10)****Counties:** CARTER**District:****DBE Goal Percent:****Description:** The slope stabilization on S.R. 143 near L.M. 9.8.**Contract Time:** DT - 7/31/2027

Item No.	Description	Quantity	Units
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	817.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	1,657.000	TON
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.100	L.M.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	150.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	200.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	64.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	9.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	4.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.030	TON
403-02	ASPHALT CEMENT FOR TACK COAT (TC)	0.460	TON
411-01.10	ACS MIX(PG64-22) GRADING D	69.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	68.000	TON
604-07.01	RETAINING WALL (DESCRIPTION) (WALL 1)	2,100.000	S.F.
610-12.02	HORIZONTAL DRAINS	400.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	150.000	L.F.
706-01	GUARDRAIL REMOVED	300.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	150.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	172.000	TON

Contract ID CN261067 - CARTER

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	150.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	13.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	18.000	EACH
712-06	SIGNS (CONSTRUCTION)	250.000	S.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	2,000.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	785.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	22.000	L.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	6.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	6.000	EACH
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	584.000	S.Y.

() Item will be bid as lump sum.

Contract ID CN261074 - CLAIBORNE

Contract ID: CN261074**Letting Date:** October 02, 2026 10:00 AM**Projects:** 13004-3216-94**BR-STP-33(126)****Counties:** CLAIBORNE**District:****DBE Goal Percent:****Description:** The construction of a concrete box beam bridge on S.R. 33 over South Fork Sycamore Creek (L.M. 20.56), including grading, drainage, and paving.**Contract Time:** DT - 11/15/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (EX. 18" CMP, STA. 98+93.54 TO 101+20.00)	54.000	L.F.
202-01.14	REMOVAL OF PIPE (SIZE, STA.) (EX. 24" CMP, STA. 20+21.05)	20.000	L.F.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CB1, STA. 100+19)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) TRACT NO.4	(1)	LS
203-01.07	RD & DRNG EXCV (ACID PRODUCING- OFF SITE DISPOSAL)	2,602.000	C.Y.
203-02.05	BORROW EXCAVATION (DESCRIPTION) (OFFSITE SOIL)	182.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	678.000	C.Y.
203-06	WATER	2.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	282.704	C.Y.
203-15.03	COMPACTED CLAY	13.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	25.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	47.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.210	L.M.
208-02.01	DITCH (RIPRAP, SAND & PLASTIC SHEETING)	62.000	L.F.
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	56.000	L.F.

Contract ID CN261074 - CLAIBORNE

Item No.	Description	Quantity	Units
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	56.000	L.F.
209-05	SEDIMENT REMOVAL	54.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	592.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	118.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,067.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	81.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	329.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	36.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	48.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	18.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	120.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	0.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	102.000	TON
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	90.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	163.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	8.000	EACH
611-07.69	48IN ENDWALL (CROSS DRAIN) 3:1	4.000	EACH
705-01.04	METAL BEAM GUARD FENCE	70.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	244.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	1.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	401.000	L.F.

Contract ID CN261074 - CLAIBORNE

Item No.	Description	Quantity	Units
706-06.03	RADIUS RAIL	32.000	L.F.
706-10.26	ROUNDED END ELEMENT	25.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	660.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	808.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	443.000	TON
709-05.81	ROCK RIFFLES	(1)	LS
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	330.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	120.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	52.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	761.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	24.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	1,036.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	1,036.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	99.000	LB.
713-11.21	P POST SLIP BASE	2.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	3.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	18.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	6.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	6.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	15.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.560	L.M.

Contract ID CN261074 - CLAIBORNE

Item No.	Description	Quantity	Units
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	1,250.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.560	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	436.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,339.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	218.000	S.Y.
801-01	SEEDING (WITH MULCH)	1.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	31.000	UNIT
801-01.08	SEEDING (SPECIAL MIXTURE) WITH MULCH	21.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	21.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	31.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
802-02.30	CUTTINGS: SALIX NIGRA (18IN-24IN LENGTH)	45.000	EACH
802-02.31	CUTTINGS: SALIX SERICEA (18IN-24IN)	45.000	EACH
802-02.32	CUTTINGS: CORNUS AMOMUM (18IN-24IN)	45.000	EACH
802-02.33	CUTTINGS: SAMBUCUS CANADENSIS (18IN-24IN)	45.000	EACH
802-12.07	BETULA NIGRA (RIVER BIRCH SEEDLNG B.R.)	22.000	EACH
802-12.12	CORNUS FLORIDA (FLOWERING DOGWOOD SEEDLNG B.R.)	14.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	22.000	EACH
802-12.35	QUERCUS NIGRA (WATER OAK SEEDLNG B.R.)	22.000	EACH
802-12.37	QUERCUS PALUSTRIS (PIN OAK SEEDLNG B.R.)	14.000	EACH
802-12.55	CARYA LACINIOSA (SHELLBARK HICKORY SEEDLING B.R.)	22.000	EACH
802-13.15	PHYSOCARPUS OPULIFOLIUS (NINEBARK) 2-5FT C.G.	46.000	EACH
802-13.57	ILEX OPACA (AMERICAN HOLLY SDLNG BARE ROOT)	22.000	EACH
802-13.59	LINDERA BENZOIN (SPICEBUSH SDLNG BARE ROOT)	46.000	EACH

Contract ID CN261074 - CLAIBORNE

Item No.	Description	Quantity	Units
802-13.62	ILEX VERTICILLATA (CMMN WINTERBERRY SDLNG B.R.)	46.000	EACH
805-12.03	EROSION CONTROL BLANKET (TYPE III)	1,696.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	335.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BRIDGE NO. 13SR0330009)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	130.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	146.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	82.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	19,249.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	69.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	8,858.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	260.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	110.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	337.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	1.000	EACH
606-02.03	STEEL PILES (10 INCH)	276.000	L.F.
615-02.04	PRESTRESSED CONCRETE BOX BEAM (27" X 36")	469.000	L.F.
620-06	CONCRETE RAILING	199.000	L.F.
621-05.02	TEMPORARY SHORING	(1)	LS
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	131.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	50.000	L.F.

() Item will be bid as lump sum.

Contract ID CN261069 - COCKE

Contract ID: CN261069**Letting Date:** October 02, 2026 10:00 AM**Projects:** 15I040-M3-024

ER-NH-I-40-8(198)

Counties: COCKE**District:****DBE Goal Percent:****Description:** The rehabilitation of the bridge on I-40 over the Pigeon River and Hartford Road near L.M. 15.05.**Contract Time:** DT - 7/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	33.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	12,830.000	TON
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	59.000	C.Y.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	32.000	L.F.
706-01	GUARDRAIL REMOVED	32.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	772.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	213.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	660.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	150.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	33.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	75.000	EACH
712-06	SIGNS (CONSTRUCTION)	421.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	5,491.000	L.F.

Contract ID CN261069 - COCKE

Item No.	Description	Quantity	Units
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	780.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	363.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,512.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,710.000	L.F.

() Item will be bid as lump sum.

Contract ID CN261075 - COCKE , HAWKINS, ETC.

Contract ID: CN261075**Letting Date:** October 02, 2026 10:00 AM

Projects:	15S032-F3-005	CRP-32(108)
	37S001-F3-008	CRP-1(522)
	45S034-F3-004	CRP-34(144)
	62S002-F3-001	CRP-2(307)
	62S033-F3-009	CRP-33(169)
	76S029-F3-009	CRP-29(133)
	90S034-F3-007	CRP-34(145)

Counties: COCKE, HAWKINS, JEFFERSON, MONROE,
SCOTT, WASHINGTON**District:****DBE Goal Percent:****Description:** The traffic signal modernization improvements at various intersections along various U.S. and State Routes.**Contract Time:** DT - 10/31/2027

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	48.000	S.F.
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	8.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R10-11, 24" X 30", GROUND MOUNTED)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R10-11, 24" X 30", STRAIN POLE MOUNTED)	1.000	EACH
713-16.70	REMOVE AND REINSTALL SIGN (STREET NAME)	6.000	EACH
713-16.71	REMOVE AND REINSTALL SIGN (DESCRIPTION) (INTERSECTION NUMBER SIGN)	2.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	75.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH

Contract ID CN261075 - COCKE , HAWKINS, ETC.

Item No.	Description	Quantity	Units
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	75.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-08.07	REMOVAL OF PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
717-01	MOBILIZATION	(1)	LS
730-02.02	SIGNAL HEAD ASSEMBLY (130 A3)	2.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	9.000	EACH
730-02.07	SIGNAL HEAD ASSEMBLY (130)	10.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	58.000	EACH
730-02.13	SIGNAL HEAD ASSEMBLY (140 A1)	2.000	EACH
730-02.16	SIGNAL HEAD ASSEMBLY (150 A2H)	4.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	13.000	EACH
730-02.24	SIGNAL HEAD ASSEMBLY (260)	6.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (260 A3)	1.000	EACH
730-02.31	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (260 A6)	1.000	EACH
730-05.04	MODIFY EXISTING ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	2,125.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	7,310.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	3,830.000	L.F.
730-09.21	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (Location 1)	190.000	L.F.
730-09.22	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (Location 2)	575.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	4,595.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	8.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	10.000	EACH
730-13.14	VEHICLE DETECTOR (360-DEGREE CAMERA)	1.000	EACH
730-13.16	VEHICLE DETECTOR (RADAR/VIDEO)	2.000	EACH
730-13.18	VEHICLE DETECTOR (RADAR-SINGLE UNIT MULTI-APPROACH)	4.000	EACH

Contract ID CN261075 - COCKE , HAWKINS, ETC.

Item No.	Description	Quantity	Units
730-15.16	CABINET MAINTENANCE (FILTER)	11.000	EACH
730-15.25	MODIFY CABINET (CONTROLLER PROGRAMMING)	1.000	EACH
730-15.26	MODIFY CABINET (RADAR INSTALLATION)	6.000	EACH
730-15.27	MODIFY CABINET (VIDEO INSTALLATION)	1.000	EACH
730-16.04	CONTROLLER (ATC)	11.000	EACH
730-16.51	CABINET MONITOR UNIT	11.000	EACH

() Item will be bid as lump sum.

Contract ID CN262062 - FRANKLIN , HAMILTON, ETC.

Contract ID: CN262062

Letting Date: October 02, 2026 10:00 AM

Projects: 26S015-F3-004 CRP-15(242)
33S319-F3-007 CRP-319(19)
44S053-F3-006 CRP-53(66)
54S030-F3-006 CRP-30(100)
71S084-F3-004 CRP-84(21)
72S029-F3-010 CRP-29(134)
93S001-F3-008 CRP-1(519)

Counties: FRANKLIN, HAMILTON, JACKSON, MCMINN,
PUTNAM, RHEA, WHITE

District:

DBE Goal Percent:

Description: The traffic signal modernization improvements at various intersections along various U.S. and State Routes.

Contract Time: DT - 11/30/2027

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-01.01	REMOVE & RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	2.000	EACH
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.02	SIGNAL HEAD ASSEMBLY (130 A3)	2.000	EACH
730-02.07	SIGNAL HEAD ASSEMBLY (130)	11.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	13.000	EACH
730-02.13	SIGNAL HEAD ASSEMBLY (140 A1)	2.000	EACH
730-02.16	SIGNAL HEAD ASSEMBLY (150 A2H)	3.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	3.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (Pole Mounted With Backplate)	1.000	EACH
730-05.04	MODIFY EXISTING ELECTRICAL SERVICE	2.000	EACH

Contract ID CN262062 - FRANKLIN , HAMILTON, ETC.

Item No.	Description	Quantity	Units
	CONNECTION		
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	250.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	2,620.000	L.F.
730-09.21	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (LOCATION 1)	425.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	425.000	L.F.
730-13.06	VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	14.000	EACH
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	2.000	EACH
730-13.18	VEHICLE DETECTOR (RADAR-SINGLE UNIT MULTI- APPROACH)	5.000	EACH
730-15.11	MODIFY CABINET (DESCRIPTION) (CONNECT EXISTING GPS UNIT)	1.000	EACH
730-15.12	MODIFY CABINET (DESCRIPTION) (VERIFY EXISTING GPS UNIT)	15.000	EACH
730-15.13	MODIFY CABINET (DESCRIPTION) (REPLACE CABINET DOOR LOCK)	2.000	EACH
730-15.15	MODIFY CABINET (DESCRIPTION) (Filter)	2.000	EACH
730-15.16	CABINET MAINTENANCE (FILTER)	23.000	EACH
730-15.25	MODIFY CABINET (CONTROLLER PROGRAMMING)	18.000	EACH
730-15.26	MODIFY CABINET (RADAR INSTALLATION)	6.000	EACH
730-15.28	MODIFY CABINET (EMERGENCY PREEMPTION)	4.000	EACH
730-15.33	CABINET (FLASHER)	2.000	EACH
730-16.04	CONTROLLER (ATC)	7.000	EACH
730-16.05	CONTROLLER (FLASHER)	2.000	EACH
730-16.50	CONFLICT MONITOR	2.000	EACH
730-16.51	CABINET MONITOR UNIT	5.000	EACH
730-16.60	GLOBAL POSITIONING SYSTEM (GPS) UNIT	1.000	EACH

() Item will be bid as lump sum.

Contract ID CN262061 - HAMILTON

Contract ID: CN262061**Letting Date:** October 02, 2026 10:00 AM**Projects:** 33021-3231-14

STP-8(52)

Counties: HAMILTON**District:****DBE Goal Percent:****Description:** The grading, drainage, construction of retaining walls and paving on U.S. 127 (S.R. 8) from near S.R. 27 (Suck Creek Road) (L.M. 13.96) to near Palisades Drive (L.M. 17.01).**Contract Time:** DT - 10/31/2028

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,720.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
201-07.01	REMOVAL AND DISPOSAL OF BRUSH & TREES	(1)	LS
202-01.56	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (2 Catchbasins)	(1)	LS
202-01.57	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (2 Manhole)	(1)	LS
202-01.58	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (See Footnotes)	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (Various Locations, Various Sizes)	721.000	L.F.
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	400.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,944.000	S.Y.
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 1)	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (TRACT NO. 22)	40.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	15,824.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,600.000	C.Y.
203-06	WATER	24.000	M.G.
203-11	SCALING AND TRIMMING	1,100.000	S.Y.
203-20.01	CHANNEL SUBSTRATE	98.000	C.Y.

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
204-08	FOUNDATION FILL MATERIAL	22.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	62.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.000	L.M.
209-02.05	12" TEMPORARY SLOPE DRAIN	612.000	L.F.
209-02.07	18" TEMPORARY SLOPE DRAIN	160.000	L.F.
209-03.21	FILTER SOCK (12 INCH)	1,539.000	L.F.
209-03.31	STREAM MITIGATION-COCONUT FIBER ROLLS	200.000	L.F.
209-05	SEDIMENT REMOVAL	359.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	7,200.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	391.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	21.000	EACH
209-09.01	SANDBAGS	2,974.000	BAG
209-09.04	SEDIMENT FILTER BAG(15' X 10')	3.000	EACH
209-09.41	CURB INLET PROTECTION (TYPE 2)	2.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	33.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	24.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	5.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	6.000	EACH
209-40.45	CATCH BASIN FILTER ASSEMBLY(TYPE 5)	1.000	EACH
209-40.48	CATCH BASIN FILTER ASSEMBLY(TYPE 8)	8.000	EACH
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (Pump Around)	(1)	LS
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,649.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	1,834.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	591.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	978.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	26.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	924.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	4,006.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-	6.000	L.M.

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
	CONTINUOUS) (4IN WIDTH)		
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	3,950.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	57.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	10,724.000	LB.
604-03.74	CLASS X CONCRETE	488.000	C.Y.
604-07.01	RETAINING WALL (DESCRIPTION) (Wall 1D)	7,162.000	S.F.
604-07.02	RETAINING WALL (DESCRIPTION) (Wall 2D)	6,218.000	S.F.
604-07.03	RETAINING WALL (DESCRIPTION) (Wall 3D)	2,371.000	S.F.
604-07.04	RETAINING WALL (DESCRIPTION) (Wall 4D)	712.000	S.F.
604-07.28	RETAINING WALL EXCAVATION	825.000	C.Y.
606-28.14	MICROPILE (10 3/4" x .545" MICROPILE)	7,675.000	L.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	50.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	298.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	128.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	861.000	L.F.
607-07.11	36" CONCRETE PIPE CULVERT (CLASS V) TRENCHLESS	114.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	56.000	L.F.
607-16.02	30"X 19" HORIZONTAL OVAL CONCRETE PIPE CULVERT	78.000	L.F.
607-16.04	38"X 24" HORIZONTAL OVAL CONCRETE PIPE CULVERT	26.000	L.F.
607-16.09	60"X 38" HORIZONTAL OVAL CONCRETE PIPE CULVERT	84.000	L.F.
607-16.10	68"X 43" HORIZONTAL OVAL CONCRETE PIPE CULVERT	207.000	L.F.
607-16.11	76"X 48" HORIZONTAL OVAL CONCRETE PIPE CULVERT	173.000	L.F.
607-57.06	REINFORCED CONCRETE PIPE ARCH (58" X 36")	48.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-02.14	JUNCTION BOX, TYPE 5	3.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	136.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	6,270.000	LB.

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
611-07.31	18IN ENDWALL (SIDE DRAIN)	2.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	3.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	5.000	EACH
611-39.02	CATCH BASINS, TYPE 39, > 4' - 8' DEPTH	1.000	EACH
611-40.01	CATCH BASINS, TYPE 40, 0' - 4' DEPTH	3.000	EACH
611-40.02	CATCH BASINS, TYPE 40, > 4' - 8' DEPTH	2.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	5.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	30.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	35.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	30.000	L.F.
621-05.02	TEMPORARY SHORING	(1)	LS
622-01.06	SHOTCRETE 12 IN THICKNESS	400.000	S.F.
624-03.01	RETAINING WALL REINFORCING STEEL	76,423.000	LB.
702-01.01	EXTRUDED SLOPING CURB	300.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	919.000	C.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	23.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	10.000	EACH
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	110.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,337.500	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
706-01	GUARDRAIL REMOVED	1,288.000	L.F.
707-02.43	ROCK ANCHOR, TYPE I	12,250.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	902.000	L.F.
707-10.06	ROCKFALL DRAPE (TYPE II)	11,150.000	S.Y.
707-11.01	PEDESTRIAN CONSTRUCTION BARRIER FENCE	500.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	150.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	315.000	TON

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
709-05.06	MACHINED RIP-RAP (CLASS A-1)	640.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	103.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	528.000	TON
709-10.05	GABIONS (DESCRIPTION) (Gabion Mattress)	95.000	C.Y.
711-05.72	SINGLE SLOPE HALF CONCRETE BARRIER WALL	1,350.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	2,200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	14.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	400.000	EACH
712-06	SIGNS (CONSTRUCTION)	921.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	60.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	1.000	EACH
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	2,890.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	220.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	202.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	10.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	3,366.000	EACH
716-01.07	TEMPORARY RAISED PAVEMENT MARKER,YELLOW	3,366.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,683.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	539.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,112.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	45.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	88.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	117.000	L.F.

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	7.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	57,932.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	204.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	137,280.000	L.F.
716-08.24	REMOVAL OF PAVEMENT MARKING (LANE REDUCTION ARROW)	7.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	14.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.01	PORTABLE TRAFFIC SIGNAL SYSTEM	4.000	EACH
740-06.01	GEOMEMBRANE	7,334.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,431.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	284.000	S.Y.
801-01	SEEDING (WITH MULCH)	2.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	5.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	8.000	UNIT
801-03	WATER (SEEDING & SODDING)	89.000	M.G.
803-01	SODDING (NEW SOD)	7,298.000	S.Y.
805-01.03	TURF REINFORCEMENT MAT (CLASS III)	3,372.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	7,537.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	300.000	S.Y.
790-01.01	POLE 30FT CLASS 2 WOOD	2.000	EACH
790-01.03	POLE 30FT CLASS 4 WOOD	1.000	EACH
790-04.09	POLE 45FT CLASS H2 METAL	1.000	EACH
790-06.08	POLE 55FT CLASS H2 METAL	1.000	EACH
790-07.08	POLE 60FT CLASS H2 METAL	2.000	EACH
790-08.06	POLE 65FT CLASS H4 METAL	1.000	EACH
790-21.07	1PH PRIMARY LG ANGLE 15KV	1.000	EACH
790-21.08	1PH DEADEND 15KV	1.000	EACH
790-25.01	3PH CROSSARM SGL 15KV	2.000	EACH

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
790-30.03	SECONDARY ASSEMBLIES DEADEND	2.000	EACH
790-30.04	SECONDARY ASSEMBLIES MISC	2.000	EACH
790-31.11	SERVICE CONDUCTOR 2 AL TRIPLEX	110.000	L.F.
790-32.23	GUY GUARD	3.000	EACH
790-32.29	DOWN GUY HEAVY CONSTRUCTION - PREFORM	10.000	EACH
790-32.30	OVERHEAD GUY HEAVY CONSTRUCTION - PREFORM	6.000	EACH
790-33.16	ROCK ANCHOR TRIPLE EYE	4.000	EACH
790-33.26	SCREW TYPE ANCHOR 28,000LB	4.000	EACH
790-36.01	SWITCH-900A-UNDERSLUNG	1.000	EACH
790-36.05	TRANSFER SECONDARY	2.000	EACH
790-36.06	TRANSFER LIGHT	2.000	EACH
790-36.14	TRANSFER CONDUCTOR	28.000	EACH
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	2.000	EACH
790-65.04	LIGHTNING ARRESTER POLE MTD 9 KV	1.000	EACH
790-65.20	LIGHTNING ARRESTER 3PH 46 KV	2.000	EACH
790-68.01	POLE GROUND ROD TYPE	7.000	EACH
790-68.13	SGL PHASE MOUNTING BRACKET - FIBERGLASS	2.000	EACH
790-71.03	SGL ARM LINE POST INS NO OHGW 46KV MAX	3.000	EACH
790-71.04	DBL ARM LINE POST INS NO OHGW 46KV MAX	1.000	EACH
790-98.01	REMOVE WIRE	115.000	L.F.
790-98.02	REMOVE POLES	7.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	51.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
793-01.07	POLE 35FT CLASS 4 WOOD	3.000	EACH
793-01.12	POLE 40FT CLASS 4 WOOD	2.000	EACH
793-01.41	ANCHOR 1IN	3.000	EACH
793-16.01	MH(RETIRE/REMOVE/GRAVEL BACKFILL)	1.000	EACH
793-98.04	REMOVE POLES ALL SIZES	25.000	EACH
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	200.000	L.F.

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
795-01.04	6IN DIP SLIP JOINT WATER LINE	1,400.000	L.F.
795-05.77	BORE/JACK 12IN STEEL CASING PIPE-ROCK.	60.000	L.F.
795-06.01	CONNECT TO 2IN WATER LINE	1.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	1.000	EACH
795-06.31	CUT AND CAP 2IN WATER LINE	1.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	4.000	EACH
795-07.35	2IN X 2IN TAPPING SADDLE AND VALVE	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	3.000	EACH
795-09.28	3/4IN COPPER SERVICE PIPE	50.000	L.F.
795-09.51	RECONNECT SERVICE ASSEMBLY	5.000	EACH
795-10.12	1/2IN AUTO AIR RELEASE VALVE ASSEMBLY	3.000	EACH
795-10.32	METER BOX FOR AUTO AIR RELEASE VALVE	3.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	1.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-13.01	DI FITTINGS	2,000.000	LB.
795-13.05	CREEK CROSSING (DESCRIPTION) (PALISADES DR)	(1)	LS
795-14.02	CLASS B CONCRETE	10.000	C.Y.
795-14.08	RESTORE ASPHALT	30.000	S.Y.
795-14.10	RESTORE GRAVEL	60.000	S.Y.
795-14.12	PIPE CHECK DAM	2.000	C.Y.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	5.000	EACH
797-01.53	VENT PIPE ASSEMBLY	2.000	EACH
797-04.60	8IN DIP RESTRAINED JOINT GRAVITY SEWER 0FT-6FT DEPTH	50.000	L.F.
797-04.64	10IN DIP RESTRAINED JOINT GRAVITY SEWER 0FT-6FT DEPTH	50.000	L.F.
797-05.41	6IN DIP SERVICE LATERAL	85.000	L.F.
797-05.45	10IN CURED IN PLACE PIPE (CIPP)	583.000	L.F.
797-05.46	12IN CURED IN PLACE PIPE (CIPP)	3,508.000	L.F.
797-05.49	CIPP LABORATORY TESTING	(1)	LS

Contract ID CN262061 - HAMILTON

Item No.	Description	Quantity	Units
797-07.01	48IN MANHOLE 0FT-4FT DEPTH	3.000	EACH
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	2.000	EACH
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	1.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	2.000	EACH
797-07.80	REMOVE SEWER MANHOLE	1.000	EACH
797-11.10	48IN MANHOLE REHABILITATION	85.000	V.F.
797-11.31	RETIREIN PLACE EXISTING SEWER 8IN-14IN	35.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.39	TV INSPECTION	8,182.000	L.F.
797-11.50	FRAME AND COVER (WATERTIGHT) (WATERTIGHT)	14.000	EACH
797-40.01	CONCRETE ENCASEMENT	105.000	L.F.
798-05.27	COMMUNICATION ASSEMBLY (BOND)	3.000	EACH
798-05.33	COMMUNICATION ASSEMBLY (DE)	2.000	EACH
798-05.34	COMMUNICATION ASSEMBLY (E1-2)	3.000	EACH
798-05.35	COMMUNICATION ASSEMBLY (E2-2)	2.000	EACH
798-05.37	COMMUNICATION ASSEMBLY (F2&F3)	1.000	EACH
798-05.54	COMMUNICATION ASSEMBLY (SVC)	3.000	EACH
798-08.05	TRANSFER FEEDER CABLE	6.000	EACH
798-09.03	REMOVE POLES, GUYS, ANCHORS	9.000	EACH
798-09.08	REMOVE STRAND POLE FRAMING	8.000	EACH

() Item will be bid as lump sum.

Contract ID CN264057 - HARDIN

Contract ID: CN264057**Letting Date:** October 02, 2026 10:00 AM**Projects:** 36ACOU-S3-002
36S057-S3-002

N/A

N/A

Counties: HARDIN**District:****DBE Goal Percent:****Description:** The grading, drainage, and paving on a S.I.A. route serving Packaging Corporation of America, including construction of turn lanes on S.R. 57.**Contract Time:** DT - 7/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (8", 211+19)	22.000	L.F.
202-13	WATER WELL ABANDONMENT	1.000	EACH
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	66,183.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	5,946.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,572.000	C.Y.
203-06	WATER	96.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	1,230.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	16.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	11.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	9.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.200	L.M.
209-02.05	12" TEMPORARY SLOPE DRAIN	65.000	L.F.
209-03.23	FILTER SOCK (24 INCH)	2,950.000	L.F.
209-05	SEDIMENT REMOVAL	302.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	4,436.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	2,706.000	L.F.

Contract ID CN264057 - HARDIN

Item No.	Description	Quantity	Units
209-08.07	ROCK CHECK DAM	10.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	13.000	EACH
209-09.01	SANDBAGS	1,975.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	3.000	EACH
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	1,235.000	S.Y.
209-65.03	TEMPORARY DIVERSION CHANNEL	235.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	6,700.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	192.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C or D)	200.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	56.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	970.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,670.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,410.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	11.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,100.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	740.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.400	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	3,735.000	S.Y.
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	70.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	12,587.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	152.000	L.F.
607-06.10	30" CONCRETE PIPE CULVERT (CLASS IV) TRENCHLESS	124.000	L.F.
607-13.03	72" CONCRETE PIPE CULVERT (CLASS III)	152.000	L.F.
611-02.01	SPRING DRAIN BOX, TYPE 1	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	34.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	2,230.000	LB.
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH

Contract ID CN264057 - HARDIN

Item No.	Description	Quantity	Units
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.69	48IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	36.000	L.F.
621-03.07	48" TEMPORARY DRAINAGE PIPE	70.000	L.F.
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	575.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	287.500	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
706-06.03	RADIUS RAIL	75.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,290.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	8.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	270.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	320.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	93.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	102.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	2,820.000	L.F.
710-04	FILTER CLOTH UNDERDRAIN (WITH PIPE)	1,240.000	L.F.
710-05	LATERAL UNDERDRAIN	220.000	L.F.
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	15.000	EACH
710-06.14	LATERAL UNDERDRAIN ENDWALL (5:1)	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	1,000.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	75.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	136.000	S.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	4,400.000	L.F.

Contract ID CN264057 - HARDIN

Item No.	Description	Quantity	Units
713-02.21	SIGN POST DELINEATION ENHANCEMENT	43.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	241.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	9.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	52.500	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.06	DEAD END SIGN AND SUPPORT	1.000	EACH
713-16.07	END OF ROADWAY SIGN AND SUPPORT	4.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	95.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	10.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	52.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	66.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	200.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.800	L.M.
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	535.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	0.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.200	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,129.000	S.Y.
740-11.05	TEMPORARY SEDIMENT TUBE 24IN	5,165.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	672.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	9.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	3.000	UNIT
801-02.15	FERTILIZER	10.000	TON

Contract ID CN264057 - HARDIN

Item No.	Description	Quantity	Units
801-03	WATER (SEEDING & SODDING)	374.000	M.G.
803-01	SODDING (NEW SOD)	26,640.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	42.000	S.Y.

() Item will be bid as lump sum.

Contract ID CN261079 - HAWKINS**Contract ID:** CN261079**Letting Date:** October 02, 2026 10:00 AM**Projects:** 37LCOU-F3-006

BRZ-3700(43)

Counties: HAWKINS**District:****DBE Goal Percent:****Description:** The construction of a concrete Bulb-Tee beam bridge on AFG Road over Southern Railway (L.M. 0.45), including grading, drainage, and paving.**Contract Time:** DT - 6/30/2028

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,100.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (12" CMP, STA. 108+57)	15.000	L.F.
202-01.14	REMOVAL OF PIPE (SIZE, STA.) (15" CMP, STA. 108+77)	38.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	8,540.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	647.000	C.Y.
203-06	WATER	32.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	74.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.100	L.M.
209-05	SEDIMENT REMOVAL	92.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,240.000	L.F.
209-08.07	ROCK CHECK DAM	10.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	9.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,915.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	68.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	25.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE VARIES)	808.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM)	400.000	TON

Contract ID CN261079 - HAWKINS

Item No.	Description	Quantity	Units
	GRADING A		
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	325.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	281.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	80.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	14.000	L.F.
607-06.30	30" PIPE CULVERT	21.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	114.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	3.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	122.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	5.000	EACH
611-63.02	JUNCTION STRUCTURE, 48IN ROUND,> (' 'FT DEPTH) ('4' FT DEPTH)	1.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	582.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	6.000	EACH
706-01	GUARDRAIL REMOVED	898.000	L.F.
706-06.03	RADIUS RAIL	17.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	600.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	304.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,480.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	8.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	68.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH

Contract ID CN261079 - HAWKINS

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	331.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	30.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	7,250.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	750.000	L.F.
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	72.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	16.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	1.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	1.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-06.01	GEOMEMBRANE	117.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,430.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	531.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	507.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,823.000	L.F.
801-01	SEEDING (WITH MULCH)	1.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	38.000	UNIT
801-03	WATER (SEEDING & SODDING)	6.500	M.G.
803-01	SODDING (NEW SOD)	277.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	3,268.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 37-0A352-0.46)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	214.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	184.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	32.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	101,237.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	429.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	66,898.000	LB.

Contract ID CN261079 - HAWKINS

Item No.	Description	Quantity	Units
604-03.04	PAVEMENT @ BRIDGE ENDS	204.000	S.Y.
604-03.32	CLASS DS CONCRETE	281.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,227.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,117.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	390.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	24.000	EACH
610-10.04	DRAINAGE SYSTEM - BRIDGE DECK(DESCRIPTION) (SPAN NO.3)	(1)	LS
615-01.11	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-63)	1,088.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	225.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	2.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	525.000	L.F.
621-05.02	TEMPORARY SHORING	(1)	LS
625-02.13	DRILLED SHAFT-ROCK (DIA.) (8'-0" DIA.)	48.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	90.000	C.Y.
625-02.46	SONIC LOGGING TESTING	4.000	EACH
707-07.01	CHAIN-LINK FENCE (BRIDGES)	2,360.000	S.F.
709-04	REINFORCED CONCRETE SLOPE PAVEMENT	125.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	142.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	38.000	L.F.
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	487.000	L.F.
795-03.05	6IN PVC WATER LINE	1,022.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	2.000	EACH
795-10.03	1IN AUTO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
795-13.01	DI FITTINGS	50.000	LB.
795-13.04	BRIDGE HANGER SYSTEM	(1)	LS
795-15.03	14IN STEEL CASING PIPE OPEN CUT METHOD	260.000	L.F.
797-01.11	___IN DIP FORCE MAIN (3)	338.000	L.F.

Contract ID CN261079 - HAWKINS

Item No.	Description	Quantity	Units
797-03.05	3IN PVC FORCE MAIN	563.000	L.F.
797-06.89	OPEN CUT 12IN STEEL CASING PIPE	80.000	L.F.
797-08.01	DI FITTINGS	50.000	LB.
797-11.43	BRIDGE HANGER SYSTEM	(1)	LS

() Item will be bid as lump sum.

Contract ID CN264061 - HENRY & STEWART**Contract ID:** CN264061**Letting Date:** October 02, 2026 10:00 AM**Projects:** 40S076-M3-003
40S076-M8-003

N/A

N/A

Counties: HENRY, STEWART**District:****DBE Goal Percent:****Description:** The resurfacing on U.S. 79 (S.R. 76) from West Antioch Road (L.M. 25.45) in Henry County to the east end of the Tennessee River Bridge (L.M. 037) in Stewart County, including thin epoxy overlay on the bridge.**Contract Time:** DT - 7/31/2027

Item No.	Description	Quantity	Units
203-06	WATER	15.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	15.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	1,921.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	60,124.000	S.Y.
403-02.01	TRACKLESS TACK COAT	62.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	2,062.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	9,156.000	TON
411-04	CRACK SEALANT	8,530.000	LB.
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	4.400	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.000	L.M.
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	244.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	2,012.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	3,197.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	50.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CN264061 - HENRY & STEWART

Item No.	Description	Quantity	Units
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	370.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	213.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	63.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,275.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	600.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	310.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	540.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,439.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	210.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	12.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	620.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.220	L.M.
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	9.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	145.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	34.000	L.M.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	190.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	75.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	12.000	EACH
716-08.08	REMOVAL OF PAVEMENT MARKING (DOUBLE TURNING ARROW)	9.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	19.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN	34.000	L.M.

Contract ID CN264061 - HENRY & STEWART

Item No.	Description	Quantity	Units
716-12.05	LINE) ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	490.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.02	SAW SLOT	300.000	L.F.
730-14.03	LOOP WIRE	600.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	5,916.000	S.Y.

() Item will be bid as lump sum.

Contract ID CN263065 - HUMPHREYS**Contract ID:** CN263065**Letting Date:** October 02, 2026 10:00 AM**Projects:** 43455-3435-04

BRZ-4300(32)

Counties: HUMPHREYS**District:****DBE Goal Percent:****Description:** The construction of a concrete Bulb-Tee beam bridge on Cedar Grove Road over Hurricane Creek (L.M. 0.49), including grading, drainage, and paving.**Contract Time:** DT - 4/30/2028

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,100.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CONCRETE DITCHES)	(1)	LS
202-04.03	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (GATE, STA. 63+15.68)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	453.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	99.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	123.000	C.Y.
203-06	WATER	1.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-03.22	FILTER SOCK (18 INCH)	286.000	L.F.
209-05	SEDIMENT REMOVAL	66.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,378.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	450.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	499.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	19.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM)	95.000	TON

Contract ID CN263065 - HUMPHREYS

Item No.	Description	Quantity	Units
	GRADING B-M2		
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	5.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.500	TON
411-01.10	ACS MIX(PG64-22) GRADING D	81.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	15.000	TON
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	3.000	EACH
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	613.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	3.000	EACH
706-01	GUARDRAIL REMOVED	923.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	436.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	2,710.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	147.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	35.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.400	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	331.000	S.Y.
801-01	SEEDING (WITH MULCH)	23.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	9.000	UNIT
801-03	WATER (SEEDING & SODDING)	1.500	M.G.
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	15.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	15.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	15.000	EACH
802-12.44	ULMUS AMERICANA (AMERICAN ELM SEEDLNG B.R.)	15.000	EACH

Contract ID CN263065 - HUMPHREYS

Item No.	Description	Quantity	Units
802-16.01	SALIX NIGRA (BLACK WILLOW 3FT LIVE STAKES)	194.000	EACH
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 43-A341-0.49)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	288.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	530.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	48.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	97,630.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	219.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	46,671.000	LB.
604-03.32	CLASS DS CONCRETE	347.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	5,236.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	511.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	14.000	EACH
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	1,238.000	L.F.
620-06	CONCRETE RAILING	910.000	L.F.
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	8.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (4'-6" DIA.)	209.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (4'-0"/4'-6" DIA.)	156.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (4'-6" INSIDE DIAMETER)	217.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	195.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	63,112.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	116.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	50.000	L.F.

() Item will be bid as lump sum.

Contract ID CN263063 - HUMPHREYS , LAWRENCE, ETC.

Contract ID: CN263063**Letting Date:** October 02, 2026 10:00 AM**Projects:** 43S001-F3-008

CRP-1(520)

50S006-F3-008

CRP-6(170)

50SVAR-F3-002

CRP-9308(12)

80S053-F3-004

CRP-53(67)

Counties: HUMPHREYS, LAWRENCE, SMITH**District:****DBE Goal Percent:****Description:** The traffic signal modernization improvements at various intersections along various U.S. and State Routes.**Contract Time:** DT - 10/31/2027

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
717-01	MOBILIZATION	(1)	LS
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	1.000	EACH
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	9.000	EACH
730-02.11	SIGNAL HEAD ASSEMBLY (130 A2 WITH BACKPLATE)	1.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	1.000	EACH
730-02.20	SIGNAL HEAD ASSEMBLY (150 A4H WITH BACKPLATE)	1.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	2,646.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	1,012.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	852.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	763.000	L.F.
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-13.18	VEHICLE DETECTOR (RADAR-SINGLE UNIT MULTI-APPROACH)	2.000	EACH
730-15.16	CABINET MAINTENANCE (FILTER)	7.000	EACH

Contract ID CN263063 - HUMPHREYS , LAWRENCE, ETC.

Item No.	Description	Quantity	Units
730-15.25	MODIFY CABINET (CONTROLLER PROGRAMMING)	1.000	EACH
730-15.26	MODIFY CABINET (RADAR INSTALLATION)	2.000	EACH
730-16.04	CONTROLLER (ATC)	4.000	EACH
730-16.51	CABINET MONITOR UNIT	4.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	16.000	EACH

() Item will be bid as lump sum.

Contract ID CN261072 - JOHNSON

Contract ID: CN261072**Letting Date:** October 02, 2026 10:00 AM**Projects:** 46S034-F3-006

ER-STP-34(146)

46S167-F3-007

ER-STP-167(14)

46S167-F3-008

ER-STP-167(15)

Counties: JOHNSON**District:****DBE Goal Percent:****Description:** The slope repair on U.S. 421 (S.R. 34) near L.M. 21.14, and on S.R. 167 near L.M. 7.3 and 16.54.**Contract Time:** DT - 8/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	11,227.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	23,786.000	TON
203-07	FURNISHING & SPREADING TOPSOIL	305.000	C.Y.
203-10.16	GRADED SOLID ROCK (IN-PLACE)	1,817.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.300	L.M.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	700.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-13.04	TURBIDITY CURTAIN(DESCRIPTION) (IN STREAM)	516.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	384.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	40.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	105.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	249.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	247.000	TON
607-03.30	18" PIPE CULVERT	9.000	L.F.

Contract ID CN261072 - JOHNSON

Item No.	Description	Quantity	Units
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	1,104.215	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
705-06.44	SHORT-RADIUS GR SYSTEM TO GR CONN (24FT RADIUS) MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	64.000	L.F.
706-10.73	REMOVAL OF GUARDRAIL & POST FOR REUSE	400.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	700.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	2.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	250.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	123.000	TON
709-10.01	GABIONS (DESCRIPTION) (FROM STATION 139+70.00 TO 145+20.00)	1,854.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,760.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	7.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	156.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	126.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	38.000	EACH
712-06	SIGNS (CONSTRUCTION)	944.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
712-09.01	REMOVABLE PAVEMENT MARKING LINE	7,800.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	94.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	4,805.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	4,253.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	1.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	35.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS

Contract ID CN261072 - JOHNSON

Item No.	Description	Quantity	Units
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	484.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	6,101.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	200.000	L.F.
801-02	SEEDING (WITHOUT MULCH)	16.000	UNIT
801-03	WATER (SEEDING & SODDING)	2.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	1,830.000	S.Y.

() Item will be bid as lump sum.

Contract ID CN261073 - KNOX

Contract ID: CN261073**Letting Date:** October 02, 2026 10:00 AM**Projects:** 47I075-S3-003

N/A

Counties: KNOX**District:****DBE Goal Percent:****Description:** The concrete pavement repair on I-75 from the I-40 Eastbound exit ramp (L.M. 0.00) to the bridge over Papermill Drive (L.M. 0.30).**Contract Time:** DT - 8/31/2027

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	164.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	162.000	TON
502-03.25	FULL DEPTH PCC PAVEMENT REPAIR HIGH EARLY	130.000	C.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	1,114.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	402.000	EACH
502-04.03	TRANSVERSE TIE-BARS	242.000	EACH
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	875.000	L.F.
502-08.03	SEALING SHOULDER JOINTS	285.000	L.F.
502-25	SAWING CONCRETE JOINTS	120.000	L.F.
503-01	GRINDING CONCRETE PAVEMENT	4,224.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	3,488.000	L.F.
712-02.36	REMOVE AND RELOCATE PORTABLE BARRIER RAIL	3,488.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	488.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	31.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	244.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,465.000	S.F.

Contract ID CN261073 - KNOX

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	6,281.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	2.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CN264060 - SHELBY**Contract ID:** CN264060**Letting Date:** October 02, 2026 10:00 AM**Projects:** 79S385-M3-002

N/A

Counties: SHELBY**District:****DBE Goal Percent:****Description:** The repair of the bridge on S.R. 385 over Riverdale Road (L.M. 3.57)**Contract Time:** DT - 4/30/2027

Item No.	Description	Quantity	Units
201-05.31	VEGETATION REMOVAL	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	185.000	TON
502-08.02	RESEALING JOINTS (SILICONE SEALANT)	831.000	L.F.
604-04.05	BRIDGE END DRAINS(SIZE) (12")	4.000	EACH
610-07.01	12" PIPE DRAIN (BRIDGE DRAIN)	403.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	18.200	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,270.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	119.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	568.000	S.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" LINE)	17,520.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	11,580.000	L.F.
716-01.11	RAISED PVMT MARKERS (BI-DIRECTIONAL) (1 COLOR LENS)	228.000	EACH
717-01	MOBILIZATION	(1)	LS
725-21.07	PORTABLE SMART WORK ZONE SYSTEM	25.000	DAY

() Item will be bid as lump sum.

Contract ID CN263066 - SMITH

Contract ID: CN263066**Letting Date:** October 02, 2026 10:00 AM**Projects:** 80002-3263-14

STP/PROT-24(70)

Counties: SMITH**District:****DBE Goal Percent:****Description:** The rockfall mitigation on U.S. 70N (S.R. 24) from near Waggoner Street (L.M. 9.88) to near Cedar Street (L.M. 10.46) in South Carthage.**Contract Time:** DT - 10/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	4.000	EACH
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,574.000	C.Y.
203-11	SCALING AND TRIMMING	46,844.000	S.Y.
203-40.17	ROCK DOWEL	1,345.000	L.F.
209-03.21	FILTER SOCK (12 INCH)	3,031.000	L.F.
209-05	SEDIMENT REMOVAL	421.000	C.Y.
209-08.07	ROCK CHECK DAM	6.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	3.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	4.000	EACH
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	675.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	1.200	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	10,186.000	S.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,150.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	3.000	EACH
706-01	GUARDRAIL REMOVED	2,276.000	L.F.
707-02.44	ROCK ANCHOR, TYPE II	4,520.000	L.F.
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (CHAIN LINK)	576.000	L.F.

Contract ID CN263066 - SMITH

Item No.	Description	Quantity	Units
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	259.000	L.F.
707-10.06	ROCKFALL DRAPE (TYPE II)	46,500.000	S.Y.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	9.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	6.000	EACH
712-06	SIGNS (CONSTRUCTION)	659.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	152.000	L.F.
712-09.33	MODIFY EXISTING OVERHEAD SIGNS	4.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	13.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	9.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	10.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W8-14)	5.000	EACH
713-16.21	SIGNS (DESCRIPTION) (W3-1)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (D9-2)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (M6-1L)	1.000	EACH
713-16.24	SIGNS (DESCRIPTION) (R1-1)	1.000	EACH
713-16.25	SIGNS (DESCRIPTION) (R1-3P)	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	39.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	39.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	60.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVT MRKNG (6IN LINE)	2.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.01	REMOVE & RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	172.000	S.Y.
801-01	SEEDING (WITH MULCH)	381.000	UNIT
801-03	WATER (SEEDING & SODDING)	39.000	M.G.

Contract ID CN263066 - SMITH

Item No.	Description	Quantity	Units
801-08	FERTILIZER (SUPPLEMENTAL APPLICATION)	5.000	TON

() Item will be bid as lump sum.

Contract ID CN261064 - SULLIVAN

Contract ID: CN261064**Letting Date:** October 02, 2026 10:00 AM**Projects:** 82956-3594-04

N/A

Counties: SULLIVAN**District:****DBE Goal Percent:****Description:** The grading, drainage, construction of bridges and a retaining wall, signals, and paving on a S.I.A. route serving Eastman Chemical Company.**Contract Time:** DT - 10/31/2028

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (SEE PLANS SHEET 2F1)	713.000	L.F.
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	16.000	EACH
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	600.000	S.Y.
202-08.10	REMOVAL OF CURB (DESCRIPTION) (EXISTING ROUNDABOUT)	800.000	L.F.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (EXISTING ROUNDABOUT)	1,500.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	88,915.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	42,423.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	10,138.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	9,185.000	C.Y.
203-06	WATER	520.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	200.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	125.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.360	L.M.
209-02.07	18" TEMPORARY SLOPE DRAIN	200.000	L.F.
209-05	SEDIMENT REMOVAL	650.000	C.Y.

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	19,000.000	L.F.
209-08.07	ROCK CHECK DAM	100.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	12.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	53.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	6.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	370.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	20,000.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	900.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	100.000	TON
303-10.07	MINERAL AGGREGATE (SIZE 4)	4,551.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	5,000.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	3,800.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	30.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	2,700.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	6,000.000	S.Y.
501-01.01	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 8"	280.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	76.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	16,700.000	LB.
604-07.01	RETAINING WALL (DESCRIPTION) (R1, STA. 113+18.00 TO STA. 118+60.00 RT RIVERPORT ROAD)	2,200.000	S.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	4,447.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	44.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	238.000	L.F.
607-50.12	PRECAST CONCRETE BOX CULVERT (SIZE) (8' X 3')	82.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	20.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	1,200.000	LB.
611-07.61	30IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	26.000	EACH

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	26.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	6.000	EACH
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	542.000	L.F.
621-03.11	72" TEMPORARY DRAINAGE PIPE	780.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	5,000.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	150.000	S.F.
701-02.03	CONCRETE CURB RAMP	1,000.000	S.F.
701-03	CONCRETE MEDIAN PAVEMENT	30.000	C.Y.
702-01	CONCRETE CURB	60.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	1,200.000	C.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,539.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	395.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	8.000	EACH
706-01	GUARDRAIL REMOVED	590.000	L.F.
706-06.03	RADIUS RAIL	100.000	L.F.
707-01.11	CHAIN LINK FENCE (6 FOOT)	600.000	L.F.
707-01.13	GATE - CHAIN-LINK FENCE-6 FOOT (DESCRIPTION) (TRACT 18 ACCESS CONTROL)	2.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (TRACTS 4 & 18)	1,910.000	L.F.
707-06.02	REMOVAL OF GATE (DESCRIPTION) (TRACT 4 STA. 54+30 LT.)	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,910.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	101.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	130.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	2,359.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	225.000	TON

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	3,100.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	40.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	513.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	400.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,800.000	L.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	42.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	350.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,000.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	400.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK)	72.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.35	METAL BARRICADE (TYPE III)	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R10-12A, (30"X36")	2.000	EACH
714-01.69	REMOVE CONDUCTOR	1,575.000	L.F.
714-03	JACKED OR BORED CONDUIT	220.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	6,125.000	L.F.
714-03.02	DIRECT BURIAL CONDUIT (3" PVC, SCHEDULE 40)	1,940.000	L.F.
714-05.04	PULL BOXES (TYPE C)	22.000	EACH
714-08.28	FOUNDATION FOR LIGHT STANDARDS - ROADWAY (DESCRIPTION) (POST TOP)	23.000	EACH
714-08.32	REMOVAL OF LIGHT STANDARD & FOUNDATION	5.000	EACH
714-09.47	LED LUMINAIRES (DESCRIPTION) (RELOCATE EXISTING)	1.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	17.000	S.Y.

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	200.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	14.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	740.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	250.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	6.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	80.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	3.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVM T MRKNG (6IN LINE)	8.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	9.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	4.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	600.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,675.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	150.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	675.000	L.F.
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	125.000	L.F.
730-12.27	CONDUIT 3" DIAMETER (PVC SCHEDULE 80)	20.000	L.F.
730-13.02	VEHICLE DETECTOR (VIDEO)	4.000	EACH
730-15.07	CABINET (DESCRIPTION) (TS2, TYPE 1 (BASE MOUNTED))	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-17.01	INSTALL MODEM	1.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	1.000	EACH
730-23.64	CANTILEVER SIGNAL SUPPORT (1 ARM @ 30')	1.000	EACH
730-23.80	CANTILEVER SIGNAL SUPPORT (1 ARM @ 40')	1.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	1.000	EACH

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH
730-26.06	PEDESTRIAN PUSHBUTTON POST	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	4.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	1.000	EACH
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	8,622.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	15,541.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	646.000	L.F.
801-01	SEEDING (WITH MULCH)	100.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	500.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	6.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	400.000	UNIT
801-03	WATER (SEEDING & SODDING)	100.000	M.G.
801-07	SEED (SUPPLEMENTAL APPLICATION)	300.000	LB.
803-01	SODDING (NEW SOD)	19,930.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	5,000.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	32,000.000	S.Y.
204-02.01	DRY EXCAVATION (BRIDGES)	381.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	201.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	52.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	108.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO.1, STA. 36+25.00)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.1, STA. 73+15.70)	(1)	LS
204-10.03	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO.2, STA. 37+05.50)	(1)	LS
204-10.04	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO.2, STA. 73+75.70)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	200.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	141.000	TON

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
604-02.03	EPOXY COATED REINFORCING STEEL	213,888.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	657.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	120,210.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	444.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	560.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,813.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,767.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	500.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	19.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE DRAINS TYPE 2)	6.000	EACH
615-01.03	PRESTRESSED CONCRETE I-BEAM (TYPE III)	868.000	L.F.
615-02.10	PRESTRESSED CONCRETE BOX BEAM (27" X 48")	986.000	L.F.
620-05.02	STANDARD CONCRETE CLASSIC PARAPET RAIL	823.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	236.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	84.000	L.F.
790-04.02	POLE 45FT CLASS 2 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	5.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	4.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	2.000	EACH
790-26.01	3PH CROSSARM 25KV	1.000	EACH
790-26.12	3PH CROSSARM DBL SM ANGLE 25KV	4.000	EACH
790-26.14	3PH CROSSARM DBL 10FT SM ANGLE 25KV	1.000	EACH
790-26.15	3PH XARM DBL 10FT LRG COND SM ANGLE 25KV	3.000	EACH
790-26.25	3PH CROSSARM DDE 25KV	4.000	EACH
790-26.27	3PH CROSSARM DBL DDE 25KV	2.000	EACH
790-31.02	SERVICE ASSEMBLY-POLE TYPE	6.000	EACH
790-31.11	SERVICE CONDUCTOR 2 AL TRIPLEX	78.000	L.F.
790-32.01	DOWN GUY - THROUGH BOLT TYPE	13.000	EACH
790-32.06	DOWN GUY - INSULATED	13.000	EACH

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
790-32.07	OH GUY - THROUGH BOLT TYPE	1.000	EACH
790-32.23	GUY GUARD	11.000	EACH
790-32.27	OVERHEAD GUY LIGHT CONSTRUCTION - PREFORM	1.000	EACH
790-33.31	SCREW TYPE ANCHOR 23,000LB (F1-5D-P)	11.000	EACH
790-36.10	TRANSFER - LIGHT ASSEMBLY	1.000	EACH
790-36.21	SWITCH-900A-UNDERSLUNG (THREE PHASE)	1.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	1,370.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	4,110.000	L.F.
790-40.06	OH COND 4/0 6/1 ACSR PENGUIN	883.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	2,649.000	L.F.
790-41.16	UG PRI COND 4/0 AL 25KV	2,121.000	L.F.
790-42.10	4IN DIA PVC PIPE	3,868.000	L.F.
790-42.19	4 DUCT BANK @ 36IN-48IN DEPTH	1,040.000	L.F.
790-43.29	DEADBREAK ELBOW 600A 25KV	12.000	EACH
790-43.47	PRIMARY PULLBOX	4.000	EACH
790-51.07	3PH TRANSFORMER PAD - GROUND SLEEVE	1.000	EACH
790-61.01	1PH FUSE CUTOFF XARM MOUNT 25KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	8.000	EACH
790-68.13	SGL PHASE MOUNTING BRACKET - FIBERGLASS	1.000	EACH
790-69.32	ARM PIN	9.000	EACH
790-98.01	REMOVE WIRE	12,384.000	L.F.
790-98.02	REMOVE POLES	13.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	68.000	EACH
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-03.04	4IN HDPE GAS MAIN	297.000	L.F.
791-04.11	HDD 2IN PE PIPE - ROCK	764.000	L.F.
791-04.13	HDD 4IN PE PIPE - ROCK	66.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	2.000	EACH

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
791-07.02	4IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
793-01.40	ANCHOR 3/4IN	4.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	9.000	EACH
793-02.99	INSTALL GUY GUARD	9.000	EACH
793-03.01	25 PAIR GROUP AERIAL SPLICE	28.000	EACH
793-03.03	10M STRAND	745.000	L.F.
793-03.12	50 PAIR CABLE	815.000	L.F.
793-03.40	INSTALL STRAND BOND	9.000	EACH
793-04.01	RELASH/DELASH CABLE	200.000	L.F.
793-04.06	READY ACCESS CLOSURE	6.000	EACH
793-04.08	TRANSFER AERIAL CABLE	17.000	EACH
793-04.12	UNDERGROUND SPLICE CLOSURE	4.000	EACH
793-07.04	48 FIBER(MATERIAL ONLY)	1,500.000	L.F.
793-07.16	12-96 FIBER(INSTALLATION ONLY)	1,500.000	L.F.
793-07.23	FIBER OPTIC MAINTENANCE LOOP	4.000	EACH
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	120.000	EACH
793-07.73	FIBER(48) AERIAL PRESSURIZED SPLICE CLOSURE	2.000	EACH
793-07.99	TEST BARE FIBER	96.000	EACH
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	60.000	L.F.
793-11.13	BURIED RISER GUARD	4.000	EACH
793-11.17	COMPOSITE HANDHOLE 5FTX3FTX3FT	2.000	EACH
793-11.20	HANDHOLE 30INX48IN	2.000	EACH
793-11.31	REMOVE HANDHOLE	3.000	EACH
793-12.02	REARRANGEMENT EXISTING CABLE	10.000	EACH
793-12.05	200 PAIR UG CABLE	1,060.000	L.F.
793-13.06	25 PAIR GROUP UG SPLICE	17.000	EACH
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	230.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	900.000	L.F.
793-14.01	SAND ENCASEMENT PER DUCT	660.000	L.F.

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
793-14.02	CONCRETE ENCASEMENT PER DUCT	1,370.000	L.F.
793-14.09	BRIDGE CONDUIT HANGER SYSTEM	(1)	LS
793-14.12	1 1/4IN INNERDUCT	2,760.000	L.F.
793-14.41	LATERALLY ADJUST CONDUIT BANK	60.000	L.F.
793-80.01	REMOVE CONDUIT/DUCT BANK FROM EXISTING CABLE	8.000	L.F.
793-98.01	REMOVE AERIAL CABLE AND WIRE	6,300.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	10.000	EACH
793-98.05	RETIRE BURIED FACILITIES IN PLACE	530.000	L.F.
793-98.08	REMOVE ANCHOR (ANY SIZE)	4.000	EACH
793-98.09	REMOVE DOWN GUY	7.000	EACH
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	520.000	L.F.
795-01.13	16IN DIP RESTRAINED JOINT WATER LINE	320.000	L.F.
795-06.07	CONNECT TO 12IN WATER LINE	2.000	EACH
795-06.09	CONNECT TO 16IN WATER LINE	2.000	EACH
795-06.37	CUT AND CAP 12IN WATER LINE	2.000	EACH
795-06.39	CUT AND CAP 16IN WATER LINE	2.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.13	16IN BUTTERFLY VALVE ASSEMBLY	2.000	EACH
795-12.35	REMOVAL OF EXISTING LINE 4" OD OR GREATER	630.000	L.F.
795-15.10	30IN STEEL CASING PIPE OPEN CUT METHOD	115.000	L.F.
797-02.05	3IN HDPE FORCE MAIN	460.000	L.F.
797-05.19	18IN DIP GRAVITY SEWER 12FT-18FT DEPTH	233.000	L.F.
797-05.20	18IN DIP GRAVITY SEWER >18FT DEPTH	125.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	70.000	L.F.
797-06.95	OPEN CUT 36IN STEEL CASING PIPE	310.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	2.000	EACH
797-07.17	60IN MANHOLE 12FT-14FT DEPTH	1.000	EACH
797-07.21	60IN MANHOLE 24FT-28FT DEPTH	1.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	1.000	EACH

Contract ID CN261064 - SULLIVAN

Item No.	Description	Quantity	Units
797-07.80	REMOVE SEWER MANHOLE	2.000	EACH
797-10.15	CONNECT TO 3IN FORCE MAIN	1.000	EACH
797-11.32	REIREIN PLACE EXISTING SEWER 15IN-24IN	417.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS

() Item will be bid as lump sum.

