

## **ASPHALT CEMENT**

### **GENERAL**

This evaluation procedure outlines the Department's approval process for asphalt cement terminals

### **SPECIFICATIONS**

904.01

TDOT SOP 3-1

AASHTO M 320

AASHTO T 350

### **PROCEDURES**

Submit 3 consecutive passing split samples of each Performance Grade being considered as well as a completed quality control plan for the terminal to Headquarters Materials and Tests Division.

The quality control plan must be updated annually.

**Contact:** Matthew Chandler,                      615.840.2918                      matthew.chandler@tn.gov

***For additional guidance, please refer to TDOT Standard Operating Procedure (SOP) 3-1.***