



## ADDENDUM NO. 1

**PROJECT:** Indiana Avenue Sidewalks (TDOT PIN 128164.00)

**ADDENDUM NO.:** 1

**ADDENDUM DATE:** April 9, 2026

**OWNER:** City of LaFollette  
207 South Tennessee Avenue  
LaFollette, TN 37766

**ENGINEER:** CCI (Cannon & Cannon, Inc.)  
10025 Investment Drive, Suite 120  
Knoxville, TN 37932

### ALL BIDS SHALL CONFORM TO THIS ADDENDUM:

This addendum forms a part of the Contract referenced above. The following items covering changes in the bidding requirements shall apply to and become a part of the requirements thereof.

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space on the Bid Form. Failure to do so may result in disqualification of the Bidder. A Mandatory Pre-Bid Meeting was held on Thursday, April 2, 2026, at the City of LaFollette offices. The sign-in sheet from the meeting has been previously sent out to all who attended the meeting.

This Addendum consists of one (1) page and the following attachments.

- Revised Plan Sheets 2, 4B, & 7B
- Revised Bid Form

### TEM NO. 1 ADDITIONS / MODIFICATIONS / CLARIFICATIONS

The following items have been added to the proposed project.

1. Plan Sheet 2 – Estimated Roadway Quantities
  - a. Add Item 707-16.01, Bike/Pedestrian Box Tube Safety Rail, 40 LF
  - b. Add Item 407-20.05, Saw Cutting Asphalt Pavement, 1,000 LF
  - c. Increase item 740-11.01, Temporary Sediment Tube 8in to 4,200 LF
  - d. Increase item 611-09.01, Adjustment of Existing Catch Basin to 5 Each
  - e. Modify Item 712-02.02 from concrete portable barrier rail to water filled plastic barriers, must comply with TDOT Qualified Products List. See modified Footnote 4 for more information.
2. Plan Sheet 4B - Adjustment of Existing Catch Basin to beginning of project
3. Plan Shet 7B - Adjustment of Existing Catch Basin to end of project

**Clarification** – The headwall / wingwall repair under the proposed pedestrian safety rail at STA 30+19 will not be included as part of this project. City of LaFollette Public Works will repair prior to the start date of construction.

**END ADDENDUM NO. 1**

FOOT NOTES	ITEM NO.	DESCRIPTION	UNIT	PARTICIPATING QUANTITIES
	105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1
	202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	S.Y.	935
	202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	456
	203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	179
	203-05	UNDERCUTTING	C.Y.	100
	203-07	FURNISHING & SPREADING TOPSOIL	C.Y.	42
1	209-05	SEDIMENT REMOVAL	C.Y.	250
1	209-09.43	CURB INLET PROTECTION (TYPE 4)	EACH	23
1	209-40.33	CATCH BASIN PROTECTION (TYPE D)	EACH	3
	303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	TON	50
	307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	TON	25
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	0.2
	407-20.05	SAW CUTTING ASPHALT PAVEMENT	L.F.	1000
	411-01.10	ACS MIX(PG64-22) GRADING D	TON	21
	415-01.01	COLD PLANING OF BITUMINOUS PAVEMENT	TON	8
2	611-01.20	ADJUSTMENT OF EXISTING MANHOLE	EACH	1
2	611-05.01	TRENCH DRAIN	L.F.	5
2	611-09.01	ADJUSTMENT OF EXISTING CATCH BASIN	EACH	5
2	611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	EACH	1
	701-01.01	CONCRETE SIDEWALK (4")	S.F.	7208
	701-02	CONCRETE DRIVEWAY	S.F.	1938
	701-02.03	CONCRETE CURB RAMP	S.F.	1479
	701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	S.F.	55
	702-01	CONCRETE CURB	C.Y.	10
	702-03	CONCRETE COMBINED CURB & GUTTER	C.Y.	11
	707-11.01	PEDESTRIAN CONSTRUCTION BARRIER FENCE	L.F.	1075
	707-16.01	BIKE/PEDESTRIAN BOX TUBE SAFETY RAIL	L.F.	40
3	712-01	TRAFFIC CONTROL	LS	1
4	712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	L.F.	1100
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	100
	712-05.03	WARNING LIGHTS (TYPE C)	EACH	100
	712-06	SIGNS (CONSTRUCTION)	S.F.	250
	713-16.20	SIGNS (R1-1, STOP)	EACH	7
	713-16.21	SIGNS (W11-2, PEDESTRIAN)	EACH	1
5	716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	231
5	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	15
5	716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSSWALK)	L.F.	336
6	716-02.12	PLASTIC PAVEMENT MARKING (8" LINE)	L.M.	0.35
	717-01	MOBILIZATION	LS	1
1	740-11.01	TEMPORARY SEDIMENT TUBE 8IN	L.F.	4200
7	801-03	WATER (SEEDING & SODDING)	M.G.	5
	803-01	SODDING (NEW SOD)	S.Y.	500

FOOTNOTES:

- SEE SUBSECTION 209.07 OF THE STANDARD SPECIFICATIONS FOR MAINTENANCE REPLACEMENT. ALL QUANTITIES ARE TO BE USED AS DIRECTED BY THE ENGINEER.
- ITEM INCLUDES ALL MATERIALS, LABOR, AND EQUIPMENT FOR ADJUSTMENT OF EXIST. AND PROPOSED STRUCTURE.
- ITEM INCLUDES ALL MATERIALS, LABOR, EQUIPMENT, AND TRAFFIC CONTROL IMPLEMENTATION.
- CONTRACTOR SHALL SUBSTITUTE CONCRETE PORTABLE BARRIER RAIL FOR WATER FILLED PLASTIC CHANNELIZING DEVICE. CONTRACTOR SHALL USE A SUPPLIER FROM THE TDOT APPROVED QUALIFIED PRODUCTS LIST (PRODUCT CATEGORY 34 - APPROVED ROADSIDE HARDWARE; MATERIAL QPL.34.018 "WATER FILLED PLASTIC CHANNELIZING DEVICE"). CHANNELIZING DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 6K.10 OF THE 2023 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). UNIT PRICE SHALL REFLECT THE COST FOR THE SUBSTITUTED MATERIAL.
- CONTRACTOR MAY ELECT TO SUBSTITUTE PREFORMED PLASTIC FOR THERMOPLASTIC. PREFORMED PLASTIC SHALL BE PAID FOR AT THE SAME UNIT PRICE AS BID FOR THERMOPLASTIC.
- ALL QUANTITIES ARE TO BE USED AS DIRECTED BY THE ENGINEER.
- INCLUDES 1 THOUSAND GALLONS FOR EROSION PREVENTION AND SEDIMENT CONTROL.

ADDED ITEM NO. 407-20.05	4-9-2026
ADDED ITEM NO. 707-16.01	4-9-2026
INCREASED ITEM NO. 611-09.01	4-9-2026
INCREASED ITEM NO. 740-11.01	4-9-2026
ADDED FOOTNOTE FOR ITEM NO. 712-02.02	4-9-2026
REVISIONS	DATE



10025 Investment Drive, Suite 120  
Knoxville, TN 37932  
865.670.8555  
www.cci-corp.com

CLIENT:  
**CITY OF LaFOLLETTE**

PROJECT:  
**PIN 128164.00  
SR-9 (INDIANA AVENUE)  
SIDEWALK IMPROVEMENTS**

**ESTIMATED ROADWAY QUANTITIES**

CCI PROJECT NO. 01324-0003
DATE 7-7-2025
P.M. RJB
DRAWN SKO
O.C. RJB



THIS REVISED SHEET IS ISSUED UNDER ADDENDUM NO. 1. ENGINEER'S SEAL APPLIES ONLY TO REVISIONS SHOWN HEREIN. ORIGINAL DRAWINGS MUST REMAIN UNDER THE RESPONSIBLE CHARGE OF THE ORIGINAL ENGINEER OF RECORD.





**BID FORM**

ITEM NO.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	TOTAL PRICE
105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1		
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	S.Y.	935		
202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	456		
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	179		
203-05	UNDERCUTTING	C.Y.	100		
203-07	FURNISHING & SPREADING TOPSOIL	C.Y.	42		
209-05	SEDIMENT REMOVAL	C.Y.	250		
209-09.43	CURB INLET PROTECTION (TYPE 4)	EACH	23		
209-40.33	CATCH BASIN PROTECTION (TYPE D)	EACH	3		
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	TON	50		
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	TON	25		
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	0.2		
407-20.05	SAW CUTTING ASPHALT PAVEMENT	L.F.	1000		
411-01.10	ACS MIX(PG64-22) GRADING D	TON	21		
415-01.01	COLD PLANING OF BITUMINOUS PAVEMENT	TON	8		
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	EACH	1		
611-05.01	TRENCH DRAIN	L.F.	5		
611-09.01	ADJUSTMENT OF EXISTING CATCH BASIN	EACH	5		
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	EACH	1		
701-01.01	CONCRETE SIDEWALK (4")	S.F.	7208		
701-02	CONCRETE DRIVEWAY	S.F.	1938		
701-02.03	CONCRETE CURB RAMP	S.F.	1479		
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	S.F.	55		
702-01	CONCRETE CURB	C.Y.	10		
702-03	CONCRETE COMBINED CURB & GUTTER	C.Y.	11		
707-11.01	PEDESTRIAN CONSTRUCTION BARRIER FENCE	L.F.	1075		
707-16.01	BIKE/PEDESTRIAN BOX TUBE SAFETY RAIL	L.F.	40		
712-01	TRAFFIC CONTROL	LS	1		
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	L.F.	1100		
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	100		
712-05.03	WARNING LIGHTS (TYPE C)	EACH	100		
712-06	SIGNS (CONSTRUCTION)	S.F.	250		
713-16.20	SIGNS (R1-1, STOP)	EACH	7		
713-16.21	SIGNS (W11-2, PEDESTRIAN)	EACH	1		
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	231		
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	15		
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSSWALK)	L.F.	336		
716-02.12	PLASTIC PAVEMENT MARKING (8" LINE)	L.F.	0.35		

ITEM NO.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	TOTAL PRICE
717-01	MOBILIZATION	LS	1		
740-11.00	TEMPORARY SEDIMENT TUBE 8IN	L.F.	4200		
801-03	WATER (SEEDING & SODDING	M.G.	5		
803-01	SODDING (NEW SOD)	S.Y.	500		

**TOTAL BID \$** \_\_\_\_\_

**TOTAL BID IN WORDS**

The bidder acknowledges receipt of the following addenda.

**Addendum No.** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Addendum No.** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Addendum No.** \_\_\_\_\_

**Date:** \_\_\_\_\_