TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2018	33002-4177-04	14

TRAFFIC CONTROL QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	ITEM NO. 712-06 (S.F.)	SIZE	M.U.T.C.D. NO.	REMARKS
		END ROAD WORK	S.F.	4	32	48"X24"	G20-2	INTERSTATE
		END ROAD WORK	S.F.	2	9	36"X18"	G20-2	STATE ROUTE
		EXIT CLOSED	S.F.	1	12	48"X36"	E5-2A	
		DIRECTIONAL ARROW LT & RT	S.F.	1	3	21"X15"	M6-4	STATE ROUTE
		ROAD WORK AHEAD	S.F.	4	64	48"X48"	W20-1	INTERSTATE
		ROAD WORK AHEAD	S.F.	2	18	36"X36"	W20-1	STATE ROUTE
		ROAD WORK 1/2 MILE	S.F.	4	64	48"X48"	W20-1	INTERSTATE
		TDOT CONSTRUCTION RECORD-A-COMMENT	S.F.	2	64	96"X48"	TN-55A	INTERSTATE
		TDOT CONSTRUCTION RECORD-A-COMMENT	S.F.	2	42	84"X36"	TN-55B	STATE ROUTE
		DETOUR AHEAD	S.F.	4	64	48"X48"	W20-2	INTERSTATE
		END DETOUR	S.F.	3	9	24"X18"	M4-8A	STATE ROUTE
		CUMMINGS HWY S.R. 2	S.F.	2	16	48"X24"		INTERSTATE SUPPLEMENTAL
		CUMMINGS HWY S.R. 2	S.F.	10	60	36"X24"		S.R. SUPPLEMENTAL
		DETOUR	S.F.	1	5	30"X24"	M4-9R	
		DETOUR WITH ARROW	S.F.	4	24	48"X18"	M4-10R	RIGHT
		DETOUR WITH ARROW	S.F.	4	24	48"X18"	M4-10L	LEFT
		ROAD CLOSED	S.F.	3	30	48"X30"	R11-2	FOR BARRICADES
		ROAD CLOSED AHEAD	S.F.	4	36	36"X36"	W20-3	
		RIGHT LANE CLOSED 1500 FT	S.F.	1	9	36"X36"	W20-5R	
		RIGHT LANE CLOSED AHEAD	S.F.	1	9	36"X36"	W20-5R	
		RIGHT LANE ENDS SYMBOL	S.F.	1	9	36"X36"	W4-2R	
		LEFT LANE CLOSED 1500 FT	S.F.	1	9	36"X36"	W20-5L	
		LEFT LANE CLOSED AHEAD	S.F.	1	9	36"X36"	W20-5L	
		LEFT LANE ENDS SYMBOL	S.F.	1	9	36"X36"	W4-2L	
		RIGHT SHOULDER CLOSED AHEAD	S.F.	1	9	36"X36"	W21-5B	
		WEST	S.F.	1	2	24"X12"	M3-4	
		I-24	S.F.	1	4	24"X24"	M1-1	
		DIRECTIONAL ARROW LT & RT	S.F.	1	3	21"X15"	M6-2	
1)	705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL3	EACH	3				
	712-01	TRAFFIC CONTROL	L.S.	1				
	712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	L.F.	1120				
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	96				
	712-04.50	PORTABLE BARRIER RAIL DELINEATOR	EACH	56				
	712-05.01	WARNING LIGHTS (TYPE A)	EACH	8				
	712-07.03	TEMPORARY BARRICADES (TYPE III)	L.F.	175				
	712-08.03	ARROW BOARD (TYPE C)	EACH	1				
	713-16.01	CHANGEABLE MESSAGE SIGN UNIT	EACH	6				
	717-01	MOBILIZATION	LS	1				
	TOTAL				**648**			

NOTES:

1) THIS ITEM SHALL BE A PORTABLE ENERGY ABSORBING TERMINAL MEETING THE REQUIREMENTS OF NCHRP 350 FOR TEST LEVEL 3. EXAMPLES WOULD BE A QUAD-GUARD, A REACT 350 OR A TRACC. THE PAY ITEM WILL INCLUDE FURNISHING AND INSTALLING ALL COMPONENTS AS SHOWN ON THE MANUFACTURER'S DRAWING.

NOTES:
1. RAMP 2 WILL REMAIN OPEN BETWEEN 6 A.M. AND 8 P.M. DAILY.
2. RAMP CLOSURE AND S.R. 2 CLOSURE WILL NOT OCCUR SIMULTANEOUSLY.
3. FOR RAMP CLOSURE DETOUR MAP SEE SHT. 19.
4. FOR S.R. 2 CLOSURE DETOUR MAP SEE SHT. 20.

TRAFFIC CONTROL LEGEND	
SYMBOL	ITEM
	WORK ZONE
	FLEXIBLE DRUMS (CHANNELIZING)
	SIGN (CONSTRUCTION)
→	TRAFFIC FLOW
	PORTABLE BARRIER RAIL (WITH BARRIER RAIL DELINEATORS)
	TEMPORARY ATTENUATOR
	ARROW BOARD TYPE C
	CHANGEABLE MESSAGE SIGN

SEALED BY

08/03/2018

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL PHASING NOTES, LEGEND AND TABULATION

CELL BDR2ND
03-AUG-2018 08:44
\\jj02wf01\02shared\Design County Folders\Hamilton\SR 2 RSAR Cummings Hwy\Proposed Drainage Solutions May 2018\014.sht