TYPE	YEAR	PROJECT NO.	SHEET NO.
CONST.	2018	33002-4177-04	8

EPSC NOTES

ENVIRONMENTAL

(1) EXCEPT AS OTHERWISE SPECIFIED, THERE ARE NO KNOWN SPECIAL ENVIRONMENTAL FACTORS PRESENT ON THIS PROJECT THAT INDICATE A NEED FOR SEASONAL LIMITATIONS ON THE CLEARING, GRUBBING, EXCAVATION, GRADING, CUTTING OR FILLING OPERATIONS OR ON THE TOTAL AREA OF EXPOSED SOIL.

EROSION PREVENTION AND SEDIMENT CONTROL LEGEND

SYMBOL	ITEM	STD. DWG.
D	CATCH BASIN PROTECTION (TYPE D)	EC-STR-19
	CULVERT PROTECTION (TYPE 1)	EC-STR-11
TCE	TEMPORARY CONSTRUCTION EXIT	EC-STR-25
** SOCK ** SOCK **	FILTER SOCK	EC-STR-8
	ROCK CHECK DAM (V-DITCH)	EC-STR-6
	ENHANCED ROCK CHECK DAM (V-DITCH)	EC-STR-6A

EROSION PREVENTION AND SEDIMENT CONTROL QUANTITIES

	ITEM NO.	DESCRIPTION	UNIT	QUANTITY
1)	203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	4129
2)	209-03.22	FILTER SOCK (18 INCH)	L.F.	1456
2)	209-05	SEDIMENT REMOVAL	C.Y.	36
2)	209-08.07	ROCK CHECK DAM PER	EACH	9
2)	209-08.08	ENHANCED ROCK CHECK DAM	EACH	1
2)	209-40.33	CATCH BASIN PROTECTION (TYPE D)	EACH	2
2)	303-10.01	MINERAL AGGREGATE (SIZE 57)	TON	3
2)4)	709-05.05	MACHINED RIP-RAP (CLASS A-3)	TON	213
2)3)	740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	S.Y.	360
2)	801-01.07	TEMPORARY SEEDING (WITH MULCH)	UNIT	26
2)	801-03	WATER (SEEDING & SODDING)	M.G.	3
2)	803-01	SODDING (NEW SOD)	S.Y.	2831

NOTES:

1) REFER TO SPECIAL NOTES.
2) SEE SECTION 209.07 OF THE STANDARD SPECIFICATIONS FOR MAINTENANCE AND REPLACEMENT.
3) INCLUDES 137 S.Y. FOR CULVERT PROTECTION TYPE I.
4) INCLUDES 83 TONS FOR CULVERT PROTECTION TYPE I.
5) ALL ITEMS ARE TO BE USED AS DIRECTED BY THE ENGINEER.

SEALED BY



STATE OF TENNESSEE
DEPARTMENT OF
TRANSPORTATION

EROSION PREVENTION & SEDIMENT CONTROL (EPSC) LEGEND & TABULATION

CELL BDR2ND
03-AUG-2018 08:43
\\jj02wf01\02shared\Design County Folders\Hamilton\SR 2 RSAR Cummings Hwy\Proposed Drainage Solutions May 2018\008.sht