# TRAFFIC DESIGN MANUAL

# APPENDIX B

# Traffic Signal Installation Inspection Forms

**Traffic Operations Division Traffic Engineering Office** 

# SHEET 1 OF 3

	TRAFFIC SIGNAL INSTALLATION - PRELIMINARY HARDWARE INSPECTION CHECKLIS	CHECKLIST
	INTERSECTION LOCATION:	
AGENCY / CONTRACTOR	DATE:	
0907	CONTRACTOR:	
	INSPECTOR:	
ACCEPT   DECLINE	PULL BOXES	COMMENTS
-	1 Check size, type and location as detailed in the plans and specifications, or "as builts"	
	2 Check pull box is leveled, flush with ground or sidewalk (not on street or driveway)	
	3 Check for at least 12 inches of gravel in the bottom of the box (drainage)	
	- 1	
	- 1	
	- 1	
	- 1	
	8 Check if splice Wires (it spliced) in pull boxes are tabeled	
	(some in German considering and the considerin	
	CONDUITS	
ACCEPT DECLINE	N/A	
	11 Check size and type as detailed in the plans and specifications	
	12 Check if conduits are at proper height inside pull box	
	13 Check for conduit terminations to be free of sharp edges	
	14. Check for bushings, if metal conduit	
	POLES AND PEDESTALS	
ACCEPT DECLINE	N/A	
	15 Check for proper type as detailed in the plans	
	16 Check for proper position as detailed in the plans	
	17 Check for proper grade as detailed in the plans	
	18 Check for proper height as detailed in the plans	
	19 Check that the load race of the pole is onented towards the load 20 Check for proper clearance from workead utilities and cables	
	2 of carbor hold size in implier and placement 2.1 Check another hold size in implier and placement 2.2 Check another hold size in implier and placement 2.3 Check another hold size in implier another hold size in implier another hold size in implier and placement 2.3 Check another hold size in implier and placement 2.3 Check another hold size in implier another hold	
	22. Check that anchor body are cut with footcovers installed and secured	
	23 Check for extra conduit being placed in pole foundation	
	24 Check for concrete being completed around poles and pedestals	
	25 Check for caps being in place to prevent water from entering the poles/pedestals	
	26 Check for all openings on pole/pedestal being plugged if not used	
	27 Check for wiring inside handholes with proper splicing method	
	28 Check for all handhole covers being in place for pole/pedestals	
	29 Check for ground rod being installed at each pole/pedestal	
	30 Check for monkey face to be installed on each weatherhead	
	31 Check for loop & signal wring being labeled (only if spliced) inside handholes	
	32. CHECK for no splices in opinion cabiling or video cabiling (ii used)	

# SHEET 2 OF 3

	LOOP DETECTION	COMMENTS
ACCEPT DECLINE	N/A 75. Chack if loons are located as named an	
	75 Check if hoops are correct size as per plan 77 Check if hoops are sealed properly in roadway 78 Check for correct winn and splicing (if spliced) at pull boxes	
ACCEPT DECLINE		
ACCEPT DECLINE	79 Check if detection zones are located as per plan	
	80 Check if video cameras meet minimum height requirements (∠4 tt) 81 Check if equipment is securely fastened	
	82 Check if correct IMSA cabling is used 83 Check that video cable is routed neatly and secured properly	
ACCEPT   DECLINE	SIGNS	
	+++	
	86 Check if sign saddles are tight with lockwasher(s) in place 87 Check if signs are properly attached to tethers with lockwasher(s) in place 88 Check if signs are in alignment with proper lane(s) 89 Check if signs and restrict view of any signals	
-	PREEMPTION EQUIPMENT	
ACCEPT DECLINE	N/A	
	90 Check if defectors, confirmation lamps, and beacons are located as per plans 191 Check if detectors have weep holes opened on each unit 192 Check if detectors are aligned properly, both horizontally and vertically with roadway 193 Check if the correct attachment hardware is used on all defectors and confirmation lamps 194 Check if locking rings on confirmation lamps and detectors are tightened	
	PAVEMENT MARKINGS	
ACCEPT DECLINE	N/A   95 Check if correct material is used on stripping (Thermoplastic)	
	96 Check if all crosswalks are located as per plan 97 Check if all stop lines are located as per plan	
	98 Check if all lane stripping are located as per plan 99 Check if gore markings, if used, are located as per plan	
	FIBER OPTIC CABLING	
ACCEPT DECLINE		
	100 Check if fiber optic routing located as per plan 101 Check if overhead cabling (if routed) is secured with proper hardware	
	102 Check if cabling meets minimum bend radius requirements throughout according to specifications 103 Check if specified cabling is used as per plan and marked on outer jacket	
	104 Check if proper splicing method used in each pull box (if used) 105 Check if proper amount of stack is provided in pull boxes and at cabinat	
	106 Check if proper tracer is provided (minimum 14 gauge) on in ground conduits	
	MISCELLANEOUS	
ACCEPT DECLINE	107 Check that overhead service wire meets the pole at a point that is less than 2 feet from the weatherhead 108 Check if overhead cabiling (if contrad) is serviced with proper hardware	
-	Too oncome to ordinary (a routed) to occared man proper manance	

NSPECTOR SIGNATURE

# SHEET 3 OF 3

ACCEPT   DECLINE	42	
_	33 Check that cabinet is leveled and sealed at the base	
	34 Check that concrete is completed around cabinet base and pad	
	35 Check that cabinet botts are tight	
	36 Check that ground rod is present and wired to ground buss	
	37 Check that future conduit is installed in cabinet base (one required)	
	38 Check that all cabling entering and exiting the cabinet meets IMSA specs	
	39 Check that conduits, if metal, have bushings installed	Ī
	40 Check that service wires are neatly routed and phased properly to neutral buss and breaker	
	41 Check that serviced wires are phased properly at top of pole or from pull box	
	42 Check that AC power is present at breaker in the cabinet	
	43 Check that banana plug is present inside police panel	
	44 Check that conflict monitor is inside the cabinet	
	45 Check that cabinet wiring is neat and all wires from the field are labeled	
	46 Check that cabinet has sticker "Call Before You Dig"	
	SIGNALS AND SPANS	
ACCEPT DECLINE	NA	
	47 Check that signal heads are located as per plans	
	48 Check that signal heads are no lower than 176" & plumbed with ground	
	49 Check for proper clearance from overhead utilities and cables	
	50 Check that pole/pedestal mounted signals are no lower than 10' and aligned with appropriate lanes	
	51 Check that pole/pedestal mounted signals are banded properly	
	52 Check that no open holes on any signal sections exist	
	53 Check that rubber grommets are in place on all goosenecks	
	54 Check that saddles are tight with lockwasher(s) in place	
	55 Check that goosenecks are tight with cotter pin and set screw in place	
	56 Check for correct drip loops for goosenecks	
	57 Check that metal plates have been installed and botted in red sections on span mounted signals	
	58 Check that tether bracket(s) in green sections are tight with lockwasher in place	
	59 Check that pipedowns are painted and all associated hardware is tight, set screws in place	
	60 Check that backplates are properly installed	
	61 Check that correct lashing rods are used throughout installation	
	Check that signal heads	
	63 Check that drip loops are in place neatly with tie wraps	
	Check that span wires a	
	65 Check that insulators (if used) are installed below utility primary lines	
	66 Check that spans are grounded to poles and terminated properly	
	67 Check that deadends are closed at tethers and spans	
	68 Check that thimbles are used at tether brackets mounted to poles	
	69 Check that tethers are tighten with minimum slack	
	PEDESTRIAN SIGNAL HEADS AND PUSHBUTTONS	
ACCEPT DECLINE	NA	
	70 Check if pedestrian displays are mounted at the proper height (minimum 8')	
	71 Check if pedestrian pushbuttons are the proper type according to plans	
	72 Check if pedestrian pushbuttons are mounted at the proper height (minimum 3'6")	
	73 Check if pedestrian placards are the correct type and positioned property	

# SHEET 1 OF 2


	TRAFFIC SIGNAL INSTALLATION - ACTIVATION DAY INSPECTION CHECKLIST
	INTERSECTION LOCATION:
AGENCY / CONTRACTOR	DATE: ACTIVATION TIME:
0907	CONTRACTOR:
	INSPECTOR:
ACCEPT   DECLINE   N/A	CABINET
	Signal timing received from Traffic Engineer
	<ul> <li>2 Signal timing properly installed on traffic signal controller</li> <li>3 Check that cabinet prints are provided and in place in the cabinet</li> </ul>
	1 1
	5 Check that intersection plans or "as built" plans are provided and in place in the cabinet 6. Check that timing directives are provided and in place in the cabinet
	1 1
	9 Check that cabinet has been "flashed out" for conflict monitor verification
	10 Check that cabinet fan is operational via thermostat
	12 Check that special detectors are wired correctly on "D" connector
	13 Check that all wires are routed neatly, tie wrapped and labeled properly (signal, detection, etc)
	14. Check that signal wiring is terminated properly on field terminal strip and at busses.
	16. Check that cabinet keys have been provided
	17 Check that cabinet lights are working properly
	18 Check that all cabinet door switches operate properly
_	SIGNALS AND SPANS
ACCEPT DECLINE N/A	19 Check that the correct indications are displayed
ACCEPT   DECLINE   N/A	PEDESTRIAN SIGNAL HEADS AND PUSHBUTTONS
$\sqcup$	<ul> <li>21 Check that pedestrian indications are clearly visible at any point within appropriate crosswalk area</li> <li>22 Check that pedestrian detection is calling proper phase</li> </ul>
	LOOP DETECTION
ACCEPT DECLINE N/A	23 Check that detection loops lead in is twisted in the cabinet
	24 Check that vehicle detection is calling proper phase


# SHEET 2 OF 2

ALCEP! DECLINE NA	Video de lection	2
25 Check tha	25 Check that field of view is horizontal to roadway with no horizon	
26 Check tha	<ol><li>Check that field of view is focused clearly with sufficient area for "down" algorithm</li></ol>	
27 Check if for	27 Check if fog zones are drawn for each camera view	
28 Check that detection	t detection zones call proper vehicle phases when occupied	
29 Check tha	29 Check that surge supression is in place for each coaxial line within cabinet	
30 Check tha	30 Check that surge supression is used for AC power line on camera power panel	
31 Check tha	31 Check that stop line detection zones set up for each direction via "D" connector when advanced	
32 detection is used	s used	
33 Check tha	33 Check that BNC connectors are crimped properly and surge supression installed on coax cables	
	PREEMPTION EQUIPMENT	
ACCEPT DECLINE N/A		
34 Check if preemption	reemption box is grounded and detector wires are labeled as per direction	
35 Check tha	35 Check that equipment communicates to all detectors	
36 Check tha	36 Check that preemption calls proper phase when activated from field	
37 Check tha	37 Check that proper Hi/Lo is displayed based on preempt received	
38 Check tha	38 Check that confirmation lamps are operational for specified direction	
39 Check tha	39 Check that beacons work properly on all preempts	
	FIBER OPTIC CABLING	
ACCEPI DECLINE N/A		
40 Check that fiber optic	t fiber optic cabling is terminated properly at WIC box	
41 Check tha	41 Check that fiber jumpers are provided within cabinet	
42 Test fiber optics from	optics from nearest intersection	
	MISCELLANEOUS	
ACCEPT DECLINE N/A		
43 Check tha	43 Check that Stop signs have been removed	
44 Check tha		
45 Check that vehicular		
46 Check if entire constr	ntire construction site is clean of debris	

#### **PULL BOXES**

#### TRAFFIC SIGNAL PULL BOX DETAILS





Extend the end of the conduit in the pull box above the drainage material by 1 to 2 inches. but don't go all the way to the top!

TOP VIEW

MIN, DIMENSIONS TYPE LENGTH WIDTH DEPTH A 12" 12" 6" 28" 16" 12" B

Type "A" Pull Boires are used for spilling loop lead-ins. Type 'B' Pull Boxes are used for all signal cable muting.

PULLBOX NOTES 1. GRAVEL, 12" DEEP. IS REQUIRED INDER PULLBOXES FOR DRAINAGE 2. TRAFFIC SIGNAL, TRAFFIC OR SIGNAL LEGEND REQUIRED.

SIDE VIEW

- 3. COVERS SHALL BOLT DOWN.
- 4. PULL BOXES AND COVERS SHALL MEET TIER 15 REQUIREMENTS PER ANSI/SCTE 77 2002 STANDARDS. 5. TYPE A PULL BOXES TO BE USED FOR SPLICING LOOP LEAD IN WINES TO SHIELDED CABLE DALY.
  - TYPE B PULL BOXES TO BE USED FOR ALL OTHER TRAFFIG SIGNAL APPLICATIONS.
- 6. RIGID COMBUIT TO BE CROUNCED WITH NO. 6 SOLED BARE EUPPER WHRE ATTACHED TO CROUNDING BUSHINGS IN PLAL BOX.

#### Considerations

Approximately 3 feet (1 meter) of slack cable must be left in each handhole that houses a cable run and approximately 2 feet (600 millimeters) of slack cable must be left in each mast arm pole base, light standard base and pedestal base.






#### CONDUITS

#### **Material**

Rigid Nonmetallic Conduit (RNMC or RNC)
 PVC (Polyvinyl Chloride)

Schedule 40 - belowground applications

Schedule 80 - above and belowground (roadways) applications



- High-density Polyethylene (HDPE)

Note: do NOT use schedule 40 and schedule 80 conduit together on the same run – different inside diameter!

Use multiple conduit runs if larger conduit capacity is needed; The sizing of conduit should be such as to not fill over 40% internal area of the conduit.



NEC Usable area of conduit:

- 1 conductor: 53%

- 2 conductors: 31%

- 3 or more: 40%

# POLES AND PEDESTALS



The access door of the base must be oriented away from traffic to allow maintenance personnel to see the intersection while servicing the base.



Weatherhead



Pedestal cap

#### CABINETS

Before the cabinet is installed, make sure that all proper conduits are in place and the anchor bolts fit the cabinet. Refer to the Contract Documents for details. Clean any dirt and debris from the top of the foundation.






 A four Section Rubber Gasket, and four Anchor Bolts including nuts and stainless steel washers.


Lay the rubber gasket carefully in place and set the cabinet on top of the gasket, making sure the gasket is neatly positioned under the cabinet.

The cabinet must be securely bolted to the cast in-place pad with anchor bolts.




#### CABINETS





- A. Local controller
- B. Conflict monitor
- C. Master controller
- D. Single channel loop detector amplifiers
- E. Multi-channel detector rack
- F. Pre-emption phase selector
- G. Telephone modem
- H. Fiber-optic modem
- Load switches
- J. Flasher
- K. Conduits


# CABINETS



Neatly wired



Labeling



#### SIGNALS AND SPANS

The LED signal indication must operate on a nominal 120 VAC power source.







# Drip Loops

Used to avoid water to get into electrical connections inside the signal head.

